

**INSTALLATION RESTORATION  
PROGRAM  
SITE INVESTIGATION REPORT  
IRP SITES NO.1, NO.2, AND NO.3**

**VOLUME II  
APPENDICIES A-G**

**106th CIVIL ENGINEERING FLIGHT  
NEW YORK AIR NATIONAL GUARD  
ROSLYN AIR NATIONAL GUARD STATION  
ROSLYN, NEW YORK**

**NOVEMBER 1996**



**DISTRIBUTION STATEMENT A**

**Approved for public release  
Distribution Unlimited**

**19970825 032**

**DTIC QUALITY INSPECTED 8**

***Prepared For*  
ANGRC/CEVR  
ANDREWS AFB, MARYLAND**

REPORT DOCUMENTATION PAGE			Page Approved OMB No. 0704-0188	
<small>Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.</small>				
1. AGENCY USE ONLY (Leave blank)	2. REPORT DATE NOVEMBER 1996	3. REPORT TYPE AND DATES COVERED SITE INVESTIGATION REPORT		
4. TITLE AND SUBTITLE SITE INVESTIGATION REPORT, 106TH CIVIL ENGINEERING FLIGHT, NEW YORK AIR NATIONAL GUARD, ROSLYN AIR NATIONAL GUARD STATION, ROSLYN, NEW YORK, VOL II / OF FOUR		5. FUNDING NUMBERS		
6. AUTHOR(S)				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) OPERATIONAL TECHNOLOGIES CORPORATION 4100 N.W. LOOP 410, SUITE 230 SAN ANTONIO, TEXAS 78229-4253		8. PERFORMING ORGANIZATION REPORT NUMBER		
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) ANG/CEVR 3500 FETCHET AVE ANDREWS AFB MD 20762-5157		10. SPONSORING/MONITORING AGENCY REPORT NUMBER		
11. SUPPLEMENTARY NOTES				
12a. DISTRIBUTION AVAILABILITY STATEMENT APPROVED FOR PUBLIC RELEASE; DISTRIBUTION IS UNLIMITED		12b. DISTRIBUTION CODE		
13. ABSTRACT (Maximum 200 words) SITE INVESTIGATION REPORT, 106TH CIVIL ENGINEERING FLIGHT, NEW YORK AIR NATIONAL GUARD, ROSLYN AIR NATIONAL GUARD STATION, ROSLYN, NEW YORK, VOL II - APPENDICES A-G / OF FOUR THREE SITES WERE INVESTIGATED UNDER THE INSTALLATION RESTORATION PROGRAM: SITE 1 - ACCESS ROAD TO THE AGE SHOP, SITE 2 - OLD WASTE HOLDING AREA NO. 1, SITE 3 - OLD WASTE HOLDING AREA NO. 2. FURTHER INVESTIGATION IS RECOMMENDED AT SITE 2, NO FURTHER ACTION IS RECOMMENDED AT SITES 1 & 3.				
14. SUBJECT TERMS INSTALLATION RESTORATION PROGRAM; COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATION AND LIABILITY ACT (CERCLA); AIR NATIONAL GUARD, SITE INVESTIGATION, NEW YORK AIR NATIONAL GUARD; ROSLYN, NEW YORK		15. NUMBER OF PAGES 250		16. PRICE CODE
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICATION OF ABSTRACT UNCLASSIFIED	20. LIMITATION OF ABSTRACT NONE	



**INSTALLATION RESTORATION  
PROGRAM  
SITE INVESTIGATION REPORT  
IRP SITES NO.1, NO.2, AND NO.3**

**VOLUME II  
APPENDICIES A-G**

**106th CIVIL ENGINEERING FLIGHT  
NEW YORK AIR NATIONAL GUARD  
ROSLYN AIR NATIONAL GUARD STATION  
ROSLYN, NEW YORK**

**NOVEMBER 1996**

*Prepared For*

**ANGRC/CEVR  
ANDREWS AFB, MARYLAND**

**DTIC QUALITY INSPECTED 3**

*Prepared By*

**Operational Technologies Corporation  
4100 N.W. Loop 410, Suite 230  
San Antonio, Texas 78229-4253  
(210) 731-0000**

**APPENDIX A**

**SOIL BORING LOGS**

**THIS PAGE INTENTIONALLY LEFT BLANK**

## SECTION A.1 INTRODUCTION

Boring log diagrams have been compiled for each borehole location drilled during this study. Boring diagrams for piezometers and monitoring wells are also included. Diagrams are presented in numerical order. The borehole identification is keyed to the site number and background (BG), piezometer (PZ), or monitoring well designation (MW) (i.e., 01-001MW). The diagrams combine in one page both a verbal and graphical illustration of the lithology encountered during drilling, water level data encountered during drilling and surveyed elevation of the ground surface at the borehole location.

The sample description includes the color, texture, mineralogy, moisture and consistency for each sample collected. The proportions of sand, gravel, and fines are visually estimated and described using the following semi-quantitative adjectives:

<u>Adjective</u>	<u>Estimated Percent of Total Sample</u>
Trace	0 - 5
Few	5 - 10
Little	15 - 25
Some	30 - 45
Mostly	50 - 100

Proportional adjectives precede the lithology, such as little gravel (15 - 25% gravel) and trace of silt (0 - 5% silt).

Lithologic symbols are derived and generalized from the Unified Soil Classification System shown in Figure A.1.

In the boring logs that follow, the column headings have the following meanings:

Depth:	Depth in feet below land surface.
Blows/6 in.:	The number of blow required to drive a split-spoon sampler each of the 6-inch intervals.
Sampled:	The interval of sample cored below land surface.
Percent Recovery:	The percentage of sample recovered in the split-spoon sampler per sampling run.
Field Screening:	The reading of photoionization compounds detected in soil samples by a photoionization detector during initial sampler opening and ATHA, and BTEX and benzene from field GC analysis.

Figure A.1

# KEY TO BORING LOG SYMBOLS

UNIFIED SOIL CLASSIFICATION SYSTEM - ASTM D2487				
MAJOR DIVISIONS			SYMBOL/ GRAPHIC	DESCRIPTIONS
COARSE-GRAINED SOILS (>50% Smaller Than #200 Sieve)	GRAVELS  (More than 50% of coarse fraction is larger than the #4 sieve size.)	Clean gravels with little or no fines	GW	Well-Graded Gravels, Gravel - Sand Mixtures
			GP	Poorly Graded Gravels, Gravels - Sand Mixtures
		Gravels with over 12% fines	GM	Silty Gravels, Poorly Graded Gravel-Sand-Clay Mixtures
			GC	Clayey Gravels, Poorly Graded Gravel-Sand-Clay Mixtures
	SANDS  (More than 50% of coarse fraction is smaller than the #4 sieve size.)	Clean sands with little or no fines	SW	Well-Graded Sands, Gravelly Sands
			SP	Poorly Graded Sands, Gravelly Sands
		Sands with over 12% fines	SM	Silty Sands, Poorly Graded Sand-Silt Mixtures
			SC	Clayey Sands, Poorly Graded Sand-Clay Mixtures
FINE-GRAINED SOILS (>50% Smaller Than #200 Sieve)	SILTS AND CLAYS  (Liquid limit less than 50)		ML	Inorganic Silts and Very Fine Sands, Silty or Clayey Fine Sands
			CL	Inorganic Clays of Low to Medium Plasticity: Gravelly, Sandy or Silty Clays; Lean Clays
			OL	Organic Clays and Organic Silty Clays of Low Plasticity
	SILTS AND CLAYS  (Liquid limit greater than 50)		MH	Inorganic Silts, Micaceous or Diatomaceous Fine Sandy or Silty Soils, Elastic Silts
			CH	Inorganic Clays of High Plasticity Fat Clays
			OH	Organic Clays of Medium to High Plasticity, Organic Silts
HIGHLY ORGANIC SOILS			Pt	Peat and Other Highly Organic Soils



Sample retained for on-site screening.




Sample prepared for laboratory analysis.



Water Table Level

PID Photo-Ionization Detector readings (ppm)



Asphaltic Concrete



Portland Cement Concrete



Cement Grout



Boulders or Bedrock

DRAFT  
FIGURE A.1

P\KEYLOG2

KEY TO BORING LOG  
Roslyn Air National Guard Station  
New York Air National Guard  
Roslyn, New York

O P T E C H  
OPERATIONAL TECHNOLOGIES  
CORPORATION

1994

**THIS PAGE INTENTIONALLY LEFT BLANK**

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 01-001**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 9/20/93  
 Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler  
 Depth Drilled: 11.50 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 204.14 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
7		100	⊗		Asphalt Cover	2.1	1.5	ND	ND
15					Sand, silt, gravel (fill)				
21					Light brown silty sand.				
					Brown/tan sand, trace gravel				
5		90	⊗			0.0	0.5	ND	ND
22									
34									
33									
10		90	⊗		Brown gravelly sand, trace silt and cobbles.	7.3	6.8	169.9	ND
15									
37									
					Boring Terminated at 11.5				



106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 01-002**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 4/7/94  
 Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler  
 Depth Drilled: 13.00 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 203.23 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
	15	90	✗		Asphalt Cover				
	12		✗		Sand, silt, gravel (fill)	0.0	0.0	ND	ND
	17								
5	3	80	✗		Brown silty sand with trace of gravel.	0.0	0.0	ND	ND
	9		✗						
	13								
10	26	70	✗		Brown gravelly sand, trace of silt.	0.0	0.0	ND	ND
	37		✗						
	43		✗						
	25	90	✗		Brown gravelly sand, trace of silt.	0.0	0.0	ND	ND
	27		✗						
	25								
					Boring Terminated at 13.0 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 01-003**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 9/21/93  
 Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler  
 Depth Drilled: 13.00 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 202.05 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
19		70	X		Asphalt Cover	8.5	7.5	ND	ND
20					Sand, silt, gravel with wood fragments (fill)				
15									
5									
1		0	X			-	-	-	-
1			X						
1			X						
P		90	X		Gray sandy silt with some gravel	15.5	3.5	ND	ND
P									
2									
10									
12		80	X		Brown silt and silty sand with some gravel.	5.3	3.2	ND	ND
15									
17									
20		80	X		Brown silt and silty sand with some gravel.	-	-	-	-
18									
16									
					Boring Terminated at 13.0 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 01-004**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 9/21/93  
 Drilling Method: Hollow-Stem Auger













































Sampling Method: California Style Samplers  
 Depth Drilled: 11.50 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 202.45 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
15		0			Asphalt Cover	-	-	-	-
28					Sand, silt, gravel, cobble with charcoal (fill).				
20									
11		70				6.8	3.5	62.3	35.7
28					Sand, silt, gravel with wood and charcoal fragments (fill).				
29									
5		50			Light brown sand, trace of silt and gravel.	7.9	-	ND	ND
1									
3									
5					Light brown sand, trace of silt and gravel.				
10		70			Light brown sand, trace of silt and gravel.	4.0	10.3	2.7	ND
16									
30									
40					Boring Terminated at 11.5 ft.				

**Roslyn, New York**

**OPERATIONAL TECHNOLOGIES  
CORPORATION**

<b>Project No.:</b>	<b>1315-143</b>	<b>Sampling Method:</b>	<b>California Style Sampler</b>
<b>Logged By:</b>	<b>Earl Parker</b>	<b>Depth Drilled:</b>	<b>13.00 ft.</b>
<b>Drilling Co.:</b>	<b>Soil Mechanics Drilling Co.</b>	<b>Depth To Water:</b>	<b>Not Encountered</b>
<b>Driller:</b>	<b>Robert Rogers</b>	<b>Date Measured:</b>	<b>N/A</b>
<b>Date Drilled:</b>	<b>9/21/93</b>	<b>Surface Elevation:</b>	<b>202.41 ft.</b>
<b>Drilling Method:</b>	<b>Hollow-Stem Auger</b>		

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
5	5	80	☒		Asphalt Cover	0.0	0.0	11.3	ND
6	6		☒		Sand, silt, gravel (fill)				
6			☒						
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									
									

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 02-002**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 9/21/93  
 Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler  
 Depth Drilled: 13.00 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 203.61 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
4	4	80	×		Asphalt Cover	134.0	813.0	10,734	ND
5	5				Sand, silt, gravel (fill)				
	5								
5	13	70	×		Brown sandy silt with a trace of gravel.	0.0	0.0	ND	ND
	14								
	13								
10	19	70	×		Brown silty sand with a trace of gravel.	0.0	0.0	ND	ND
	19								
	16								
	13	70	×		Brown silty sand with a trace of gravel.	-	-	-	-
	14								
	13								
					Boring Terminated at 13.0 ft.				

## Roslyn, New York

# O P T E C H

**OPERATIONAL TECHNOLOGIES  
CORPORATION**

## LOG OF BORING 02-003

Project No.:	1315-143
Logged By:	Earl Parker
Drilling Co.:	Soil Mechanics Drilling Co.
Driller:	Robert Rogers
Date Drilled:	4/7/94
Drilling Method:	Hollow-Stem Auger

<b>Sampling Method:</b>	<b>California Style Sampler</b>
<b>Depth Drilled:</b>	<b>11.50 ft.</b>
<b>Depth To Water:</b>	<b>Not Encountered</b>
<b>Date Measured:</b>	<b>N/A</b>
<b>Surface Elevation:</b>	<b>204.24 ft.</b>

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
					Asphalt Cover				
5	5	70	X		Sand, silt, gravel, charcoal fragments (fill)	0.0	0.0	ND	ND
	4								
	5								
5	6	60	X		Brown silty sand, trace of gravel and cobbles. (fill?)	1.7	3.3	ND	ND
	7								
	7								
					Brown to black silty sand and sand with trace gravel and clay.				
10	19	80	X			1.6	2.5	5.3	ND
	24								
	19								
					Boring Terminated at 11.5 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 02-004**

Project No.:	1315-143	Sampling Method:	California Style Sampler
Logged By:	Earl Parker	Depth Drilled:	5.50 ft.
Drilling Co.:	OpTech	Depth To Water:	Not Encountered
Driller:	Jerry Arriaga	Date Measured:	N/A
Date Drilled:	9/23/94	Surface Elevation:	204.18 ft.
Drilling Method:	Hand Auger		

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
		90			Sand, silt, gravel (fill)	40.8	-	66.8	ND
5		90			Sand, silt, gravel with some cobbles.	251	-	10,296	144.1
					Boring Terminated at 5.5 ft.				

## Roslyn, New York

# OPTECH

**OPERATIONAL TECHNOLOGIES  
CORPORATION**

## LOG OF BORING 02-005

<b>Project No.:</b>	<b>1315-143</b>
<b>Logged By:</b>	<b>Earl Parker</b>
<b>Drilling Co.:</b>	<b>OpTech</b>
<b>Driller:</b>	<b>Jerry Arriaga</b>
<b>Date Drilled:</b>	<b>9/23/94</b>
<b>Drilling Method:</b>	<b>Hand Auger</b>

<b>Sampling Method:</b>	<b>California Style Sampler</b>
<b>Depth Drilled:</b>	<b>5.50 ft.</b>
<b>Depth To Water:</b>	<b>Not Encountered</b>
<b>Date Measured:</b>	<b>N/A</b>
<b>Surface Elevation:</b>	<b>204.79 ft.</b>

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
<div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div>&lt;/</div></div>									



106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 02-006**

Project No.:	1315-143	Sampling Method:	California Style Sampler
Logged By:	Earl Parker	Depth Drilled:	5.50 ft.
Drilling Co.:	OpTech	Depth To Water:	Not Encountered
Driller:	Jerry Arriaga	Date Measured:	N/A
Date Drilled:	9/23/94	Surface Elevation:	203.29 ft.
Drilling Method:	Hand Auger		

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
		80			Sand, silt, gravel (fill)	5.5	-	27.1	15.0
5		80			Dark brown silty sand and sand with gravel.	2.3	-	33.3	ND
					Boring Terminated at 5.5 ft.				

**Roslyn, New York**

# O P T E C H

**OPERATIONAL TECHNOLOGIES  
CORPORATION**

## LOG OF BORING 02-007

<b>Project No.:</b>	<b>1315-143</b>
<b>Logged By:</b>	<b>Earl Parker</b>
<b>Drilling Co.:</b>	<b>OpTech</b>
<b>Driller:</b>	<b>Jerry Arriaga</b>
<b>Date Drilled:</b>	<b>9/23/94</b>
<b>Drilling Method:</b>	<b>Hand Auger</b>

Sampling Method:	California Style Sampler
Depth Drilled:	5.50 ft.
Depth To Water:	Not Encountered
Date Measured:	N/A
Surface Elevation:	204.77 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
5		80			Sand, silt, gravel (fill) some charcoal fragments	1.2	-	105.5	0.7
		80			Brown silty sand with gravel.	6.5	-	21.5	2.1
					Boring Terminated at 5.5 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 02-008**

<b>Project No.:</b> 1315-143	<b>Sampling Method:</b> California Style Sampler
<b>Logged By:</b> Earl Parker	<b>Depth Drilled:</b> 5.50 ft.
<b>Drilling Co.:</b> OpTech	<b>Depth To Water:</b> Not Encountered
<b>Driller:</b> Jerry Arriaga	<b>Date Measured:</b> N/A
<b>Date Drilled:</b> 9/23/94	<b>Surface Elevation:</b> 204.67 ft.
<b>Drilling Method:</b> Hand Auger	

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
		80			Sand, silt, gravel with charcoal fragment (fill)	20	-	2.1	0.9
5		80			Brown silty sand with gravel	48	-	21.1	ND
					Boring Terminated at 5.5 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 03-001**

<b>Project No.:</b>	<b>1315-143</b>	<b>Sampling Method:</b>	<b>California Style Sampler</b>
<b>Logged By:</b>	<b>Earl Parker</b>	<b>Depth Drilled:</b>	<b>11.50 ft.</b>
<b>Drilling Co.:</b>	<b>Soil Mechanics Drilling Co.</b>	<b>Depth To Water:</b>	<b>Not Encountered</b>
<b>Driller:</b>	<b>Robert Rogers</b>	<b>Date Measured:</b>	<b>N/A</b>
<b>Date Drilled:</b>	<b>9/20/93</b>	<b>Surface Elevation:</b>	<b>202.67 ft.</b>
<b>Drilling Method:</b>	<b>Hollow-Stem Auger</b>		

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
16	16	80	X		Asphalt Cover	1.2	9.5	17.1	3.8
24					Sand, silt, gravel (fill)				
16									
5	3	80	X		Light brown silty sand and gravel.	1.3	4.1	3.4	ND
3									
3									
4									
					Light brown sand with some gravel and trace of silt.				
10	10		X			1.6	2.4	ND	ND
15									
15									
					Boring Terminated at 11.5 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 03-002**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 9/20/93  
 Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler  
 Depth Drilled: 11.50 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 201.98 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
15	15	80	×		Asphalt Cover	0.4	5.3	3.2	ND
9	9				Sand, silt, gravel (fill)				
15	15								
5	3	90	×		Gray silty sand, with some gravel.	0.4	5.1	ND	ND
5	5								
4	4								
10	16	80	×		Brown sand to silty sand with trace of gravel and clay.	0.3	3.1	3.3	ND
10	19								
15	15								
					Boring Terminated at 11.5 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 03-003**

Project No.: 1315-143

Logged By: Earl Parker

Drilling Co.: Soil Mechanics Drilling Co.

Driller: Robert Rogers

Date Drilled: 9/20/93

Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler

Depth Drilled: 13.00 ft.

Depth To Water: Not Encountered

Date Measured: N/A

Surface Elevation: 202.44 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
8		80	X		Asphalt Cover	4.2	6.3	ND	ND
9					Sand, silt, gravel (fill)				
9									
5	3	80	X		Sand, silt, and gravel with wood fragments (fill).	2.9	5.7	5.4	ND
5									
4									
					Brown medium sand with some silt, gravel, and angular cobbles.				
10	17	80	X			5.9	6.8	ND	ND
28									
29									
27		90	X		Brown medium sand with some silt, gravel, and angular cobbles.	4.8	-	ND	ND
27									
26									
					Boring Terminated at 13.0 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 03-004**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 9/20/93  
 Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler  
 Depth Drilled: 13.00 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 202.69 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
14		70			Asphalt Cover	24.6	42.6	17.4	ND
14					Sand, silt, and gravel (fill)				
10									
5		80							
5									
18		80			Gravelly silty sand and sand with some silt and gravel.	6.4	10.7	ND	ND
25									
27									
					Sand, silt, and gravel with medium to fine sand and some cobbles.				
10		90				4.2	11.1	4.1	ND
15									
12						3.6	21.6	16.2	ND
					Boring Terminated at 13.0 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 03-005**

Project No.: 1315-143

Logged By: Earl Parker

Drilling Co.: Soil Mechanics Drilling Co.

Driller: Robert Rogers

Date Drilled: 4/7/94

Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler

Depth Drilled: 13.00 ft.

Depth To Water: Not Encountered

Date Measured: N/A

Surface Elevation: 202.30 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
7	80				Asphalt Cover				
10					Sand, silt, and gravel (fill)	0.0	0.0	ND	ND
14									
5	3	80			Light brown sand, silty sand with some gravel and little clay.	0.5	0.0	ND	ND
6									
7									
10	15	80			Light brown, sand, silty sand with gravel.	0.0	0.0	ND	ND
21									
14									
9		80				0.0	0.0	ND	ND
11									
10									
					Boring Terminated at 13.0 ft.				



106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 03-006**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Soil Mechanics Drilling Co.  
 Driller: Robert Rogers  
 Date Drilled: 9/20/93  
 Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler  
 Depth Drilled: 11.50 ft.  
 Depth To Water: Not Encountered  
 Date Measured: N/A  
 Surface Elevation: 201.80 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
11		80	⊗		Asphalt Cover	6.7	50.5	ND	59.0
9					Sand, silt, gravel (fill)				
8									
					Light brown fine to medium sand, silty sand, and some gravel.	1.3	6.3	ND	ND
5									
3		90	⊗						
3									
					Light brown sand, fine sand and silty sand with gravel.	2.7	3.4	ND	ND
10									
22		80	⊗						
29									
27					Boring Terminated at 11.5 ft.				

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING BG-001**

Project No.: 1315-143

Logged By: Earl Parker

Drilling Co.: Soil Mechanics Drilling Co.

Driller: Robert Rogers

Date Drilled: 4/7/94

Drilling Method: Hollow-Stem Auger

Sampling Method: California Style Sampler

Depth Drilled: 11.5 ft.

Depth To Water: Not Encountered

Date Measured: N/A

Surface Elevation: 204.40 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING			
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)
2 2 4		80	⊗		Sand, silt, and gravel, trace of clay	0	0	ND	ND
5 8 11 16		80	⊗		Light brown sand, silty sand with some gravel and little clay.	0	0	ND	ND
10 11 12 9		70	⊗		Light brown, sand, silty sand with gravel.	0	0	ND	ND
					Boring Terminated at 11.5 ft.				

**THIS PAGE INTENTIONALLY LEFT BLANK**



## Roslyn, New York

# OPTECH

**OPERATIONAL TECHNOLOGIES  
CORPORATION**

## LOG OF BORING 01-001MW

<b>Project No.:</b>	<b>1315-143</b>
<b>Logged By:</b>	<b>Earl Parker</b>
<b>Drilling Co.:</b>	<b>Water Resources, Inc.</b>
<b>Driller:</b>	<b>John Barnes</b>
<b>Date Drilled:</b>	<b>2/06/94</b>
<b>Drilling Method:</b>	<b>O-DEX</b>

<b>Sampling Method:</b>	<b>Surface Return</b>
<b>Depth Drilled:</b>	<b>155.67 ft.</b>
<b>Depth To Water:</b>	<b>142.24 ft.</b>
<b>Date Measured:</b>	<b>5/13/94</b>
<b>Surface Elevation:</b>	<b>204.38 ft.</b>
<b>TOC Elevation:</b>	<b>204.02 ft.</b>

[illegible]

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING 02-001MW**

Project No.: 1315-143

Logged By: Earl Parker

Drilling Co.: Water Resources, Inc.

Driller: John Barnes

Date Drilled: 5/11/94

Drilling Method: O-DEX

Sampling Method: Surface Return

Depth Drilled: 155.00 ft.

Depth To Water: 141.56 ft.

Date Measured: 5/13/94

Surface Elevation: 203.66 ft.

TOC Elevation: 203.22 ft.

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING				Monitoring Well
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)	
5					Unsorted fill material and road base to poorly sorted sand, silt, gravel, and angular rock fragments.					
10					Sandy gravel and rock fragments with coarse sand.					
15										
20										
25					Medium to fine sand and gravel.					
30										
35					Sand, silt, and gravel with larger gravel and rock fragments.					
40										
45					Sand, silt, and gravel.					
50										
55					Fine to medium sand, gravel, and rock fragments.					
60										
65										
70					Sand, silt and larger gravel. Few rock fragments.					
75										
80					Sand, silt, and gravel with clay.					

## Roslyn, New York

# OPTECH

**OPERATIONAL TECHNOLOGIES  
CORPORATION**

## LOG OF BORING 02-001MW

<b>Project No.:</b>	<b>1315-143</b>
<b>Logged By:</b>	<b>Earl Parker</b>
<b>Drilling Co.:</b>	<b>Water Resources, Inc.</b>
<b>Driller:</b>	<b>John Barnes</b>
<b>Date Drilled:</b>	<b>5/11/94</b>
<b>Drilling Method:</b>	<b>O-DEX</b>

<b>Sampling Method:</b>	<b>Surface Return</b>
<b>Depth Drilled:</b>	<b>155.00 ft.</b>
<b>Depth To Water:</b>	<b>141.56 ft.</b>
<b>Date Measured:</b>	<b>5/13/94</b>
<b>Surface Elevation:</b>	<b>203.66 ft.</b>
<b>TOC Elevation:</b>	<b>203.22 ft.</b>

[illegible]

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H**

OPERATIONAL TECHNOLOGIES  
CORPORATION

**LOG OF WELL 03-001MW**

<b>Project No.:</b>	1315-143	<b>Sampling Method:</b>	Surface Return
<b>Logged By:</b>	Earl Parker	<b>Depth Drilled:</b>	153.00 ft
<b>Drilling Co.:</b>	Water Resources, Inc.	<b>Depth To Water:</b>	139.63 ft.
<b>Driller:</b>	John Barnes	<b>Date Measured:</b>	5/13/94
<b>Date Drilled:</b>	9/10/94	<b>Surface Elevation:</b>	201.53 ft.
<b>Drilling Method:</b>	O-DEX	<b>TOC Elevation:</b>	201.22 ft.

Depth (ft.)	Samples	Graphics	DESCRIPTION OF MATERIALS	Monitoring Well	CONSTRUCTION DETAIL
5			Blacktop and road base material to VPS sand, silt, and gravel.		Flush Mount Steel Vault Box
10			Sand, silt, and gravel.		
15					
20					
25					
30			Fine to medium sand and gravel.		Bentonite Grout
35					
40			Rock fragments, gravel, and fine sand becoming medium sand, gravel.		
45					
50			Medium sand, silt, and gravel		
55					
60					
65					4in. Sch 40 PVC Flush Thread Riser
70					
75			Medium to fine sand and gravel.		
80					














106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF WELL 03-001MW**

Project No.: 1315-143  
 Logged By: Earl Parker  
 Drilling Co.: Water Resources, Inc.  
 Driller: John Barnes  
 Date Drilled: 9/10/94  
 Drilling Method: O-DEX

Sampling Method: Surface Return  
 Depth Drilled: 153.00 ft  
 Depth To Water: 139.63 ft.  
 Date Measured: 5/13/94  
 Surface Elevation: 201.53 ft.  
 TOC Elevation: 201.22 ft.

Depth (ft.)	Samples	Graphics	DESCRIPTION OF MATERIALS	Monitoring Well	CONSTRUCTION DETAIL
90			Medium to fine sand, gravel and rock fragments. Gravelly sand and rock fragments.		Bentonite Grout
95					
100			Sand, silt, and gravel.		
105					
110			Medium sand with fine sand and gravel.		
115					
120					Bentonite Pellet Seal
125					
130					
135					#2 Washed Gravel Sand Pack
140					
145			Medium sand, fine sand and gravel.		Depth To Water at 139.63 ft.
150					4in. Sch 40 PVC Flush Thread Screen, 0.010 in. Slotted
			Boring Terminated at 153.0 ft.		Well Terminated at 153.0 ft.

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING PS1**

Project No.: 1315-143

Logged By: Earl Parker

Drilling Co.: Water Resources, Inc.

Driller: John Barnes

Date Drilled: 4/19/94

Drilling Method: O-DEX

Sampling Method: Surface Return

Depth Drilled: 160.00 ft.

Depth To Water: 141.65 ft.

Date Measured: 4/29/94

Surface Elevation: 201.92 ft.

TOC Elevation: NA

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING				Monitoring Well
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)	
5					Sand and gravel. Silty sand with small gravel. (fill)					
10					Clay, silty clay with fine to medium sand. Few gravel.					
15										
20					Clayey silt and fine sand with gravel.					
25										
30					Silty sand, some medium sand with gravel. Intervals of clayey silt.					
35					Silty clay to sandy silty clay.					
40										
45					Fine sand and silt with small rounded gravel.					
50										
55										
60										
65					Silty fine sand. Silt and sand with gravel.					
70										
75										
80					Medium sand with increasing rock fragments. More gravel.					

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF BORING PS1**

Project No.: 1315-143

Logged By: Earl Parker

Drilling Co.: Water Resources, Inc.

Driller: John Barnes

Date Drilled: 4/19/94

Drilling Method: O-DEX

Sampling Method: Surface Return

Depth Drilled: 160.00 ft.

Depth To Water: 141.65 ft.

Date Measured: 4/29/94

Surface Elevation: 201.92 ft.

TOC Elevation: NA

Depth (ft.)	Blows/6"	% Recovery	Samples	Graphic	DESCRIPTION OF MATERIALS	FIELD SCREENING				Monitoring Well
						PID (ppm)	ATHA (ppm)	BTEX (ppb)	Benzene (ppb)	
90					Sand to silty sand with well rounded gravel.					
95					Course sand and gravel. Some medium to fine sand.					
100										
105										
110										
115					Sand. Medium to fine sand with silt, gravel, and rock fragments.					
120										
125					Fine sand, silt, and clay. To medium and coarse sand and gravel.					
130										
135										
140					Sand and gravel. Medium sand and rounded gravel.					
145										
150										
155										
160										
165					Boring Terminated at 160.00 ft.					

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H**

OPERATIONAL TECHNOLOGIES  
CORPORATION

LOG OF WELL PS2

Project No.:	1315-143	Sampling Method:	Surface Return
Logged By:	Earl Parker	Depth Drilled:	160.00 ft.
Drilling Co.:	Water Resources, Inc.	Depth To Water:	144.20 ft.
Driller:	John Barnes	Date Measured:	4/23/94
Date Drilled:	4/22/94	Surface Elevation:	206.01 ft.
Drilling Method:	O-DEX	TOC Elevation:	205.75 ft.

Depth (ft.)	Samples	Graphics	DESCRIPTION OF MATERIALS	Monitoring Well	CONSTRUCTION DETAIL
5			Medium sand with small gravel, black coal grains (fill).		Flush Mount Steel Vault Box
10			Sand, silt and gravel.		
15					
20					
25					
30					
35					Bentonite Grout
40			Silty sand, gravel and rock fragments.		
45					
50			Medium to fine sand with gravel.		
55					
60			Silt, sandy silt and clay.		
65					2in. Sch 40 PVC Flush Thread Riser
70			Fine to medium sand and silt with gravel.		
75					
80					

106th CEF, Roslyn Air National Guard Station


Roslyn, New York

**O P T E C H**

**OPERATIONAL TECHNOLOGIES  
CORPORATION**

**LOG OF WELL PS2**

<b>Project No.:</b>	1315-143	<b>Sampling Method:</b>	Surface Return
<b>Logged By:</b>	Earl Parker	<b>Depth Drilled:</b>	160.00 ft.
<b>Drilling Co.:</b>	Water Resources, Inc.	<b>Depth To Water:</b>	144.20 ft.
<b>Driller:</b>	John Barnes	<b>Date Measured:</b>	4/23/94
<b>Date Drilled:</b>	4/22/94	<b>Surface Elevation:</b>	206.01 ft.
<b>Drilling Method:</b>	O-DEX	<b>TOC Elevation:</b>	205.75 ft.



106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF WELL PS3**

<b>Project No.:</b> 1315-143	<b>Sampling Method:</b> Surface Return
<b>Logged By:</b> Earl Parker	<b>Depth Drilled:</b> 160.05 ft.
<b>Drilling Co.:</b> Water Resources, Inc.	<b>Depth To Water:</b> 142.25 ft.
<b>Driller:</b> John Barnes	<b>Date Measured:</b> 4/23/94
<b>Date Drilled:</b> 4/26/94	<b>Surface Elevation:</b> 203.42 ft.
<b>Drilling Method:</b> O-DEX	<b>TOC Elevation:</b> 203.10 ft.

Depth (ft.)	Samples	Graphics	DESCRIPTION OF MATERIALS	Monitoring Well	CONSTRUCTION DETAIL
5			Gravel, cobbles, and rock fragments.		Flush Mount Steel Vault Box
10			Sand, silt, gravel and rock fragments.		
15					
20			Sand, silt, and gravel.		
25					
30			Coarse sand and gravel. Gravel and rock fragments.		Bentonite Grout
35					
40					
45					
50					
55			Sand and gravel. Rock fragments.		
60					
65					2in. Sch 40 PVC Flush Thread Riser
70			Fine sand, silt, and clayey silt with some gravel.		
75					
80					

106th CEF, Roslyn Air National Guard Station

Roslyn, New York

**O P T E C H****OPERATIONAL TECHNOLOGIES  
CORPORATION****LOG OF WELL PS3**

<b>Project No.:</b>	<b>1315-143</b>	<b>Sampling Method:</b>	<b>Surface Return</b>
<b>Logged By:</b>	<b>Earl Parker</b>	<b>Depth Drilled:</b>	<b>160.05 ft.</b>
<b>Drilling Co.:</b>	<b>Water Resources, Inc.</b>	<b>Depth To Water:</b>	<b>142.25 ft.</b>
<b>Driller:</b>	<b>John Barnes</b>	<b>Date Measured:</b>	<b>4/23/94</b>
<b>Date Drilled:</b>	<b>4/26/94</b>	<b>Surface Elevation:</b>	<b>203.42 ft.</b>
<b>Drilling Method:</b>	<b>O-DEX</b>	<b>TOC Elevation:</b>	<b>203.10 ft.</b>

Depth (ft.)	Samples	Graphics	DESCRIPTION OF MATERIALS	Monitoring Well	CONSTRUCTION DETAIL
90			Fine to medium sand, silty sand and small rounded gravel.		
95					
100					Bentonite Grout
105			Fine to medium sand, silt, and gravel with few rock fragments.		
110			Fine to medium sand, silt with gravel and rock fragments.		
115					
120			Sand and silt, with more gravel. Gravelly medium sand and silt.		
125					
130					
135			Medium sand and some gravel and fine sand.		
140					
145					Depth To Water at 142.25 ft. Bentonite Pellet Seal
150					#2 Washed Gravel Sand Pack
155					2in. Sch 40 PVC Flush Thread Screen, 0.010 in. Slotted
160			Well Terminated at 160.05 ft.		Well Terminated at 160.05 ft.

**APPENDIX B**

**SOIL GAS SURVEY RESULTS**



**THIS PAGE INTENTIONALLY LEFT BLANK**



Shallow Soil Gas Investigation

ROSLYN AIR NATIONAL GUARD STATION  
Roslyn, New York

September 13 - 15, 1993



Shallow Soil Gas Investigation

ROSLYN AIR NATIONAL GUARD STATION  
Roslyn, New York

September 13 - 15, 1993

Prepared for:

OPERATIONAL TECHNOLOGIES CORPORATION  
4100 Northwest Loop 410, Suite 230  
San Antonio, Texas 78229-4253

Telephone: (210) 731-0000  
FAX: (210) 731-0008

Prepared by:

TRACER RESEARCH CORPORATION  
3855 North Business Center Drive  
Tucson, Arizona 85705-2944

Telephone: (602) 888-9400  
FAX: (602) 293-1306

Submitted by:

Maïorie D. Stivers  
Karen L. McWhirter

9-93-287-S



## TABLE OF CONTENTS

1.0	ROSLYN AIR NATIONAL GUARD STATION INVESTIGATION.....	1
1.1	Objective.....	1
1.2	Overview of Results.....	1
2.0	SITE DESCRIPTION.....	2
3.0	SOIL GAS SAMPLING PARAMETERS.....	2
4.0	ANALYTICAL PARAMETERS.....	3
4.1	Chromatographic System.....	3
4.2	Analyses.....	4
5.0	QUALITY ASSURANCE AND QUALITY CONTROL.....	5
6.0	RESULTS.....	7
	APPENDIX A Condensed Data.....	A-1

## TABLES

Table 1.	Soil Gas Sample Summary.....	1
Table 2.	Detection Limits for Target Compounds.....	4
Table 3.	Quality Assurance Samples.....	6



## 1.0 ROSLYN AIR NATIONAL GUARD STATION INVESTIGATION

Tracer Research Corporation (Tracer Research) performed a shallow soil gas investigation at the Roslyn Air National Guard Station located at 209 Harbor Hills Road, Village of East Hills, in the town of Roslyn, Long Island, New York. The investigation was conducted September 13 through 15, 1993 for Operational Technologies Corporation (Op Tech) of San Antonio, Texas.

### 1.1 Objective

The purpose of the investigation was to determine the extent of possible soil and/or groundwater contamination by screening the shallow soil gas for the presence of volatile organic compounds (VOCs). The soil gas samples were collected and analyzed for the following analyte class and compounds:

**Analyte Class: Hydrocarbon**

benzene, toluene, ethylbenzene, xylenes (BTEX)

total volatile hydrocarbons (TVHC C1 - C9)

### 1.2 Overview of Results

For this investigation, fifty-eight samples were collected from fifty-eight sampling locations. Samples were collected at depths of 4 to 5 feet below ground surface (bgs). A summary of the results of the investigation is presented in Table 1.

Table 1. Soil Gas Sample Summary

Compound	# of samples in which compound was detected	Low conc. $\mu\text{g/L}$	High conc. $\mu\text{g/L}$	Sample(s) with high conc.
benzene	30	0.01	0.4	S2-5-5'
toluene	28	0.02	110	S2-9-5'
ethylbenzene	1	NA	2	S3-9-5'
xylenes	9	0.1	12	S3-9-5'
TVHC C1 - C9	58	0.3	30,000	S1-10-5'

NA = Not Applicable



## 2.0 SITE DESCRIPTION

The soil gas samples were collected at three different areas at the Air National Guard Station. Site 1 is located between Building 36 and Building 17. Site 2 is located to the north of Building 16 and Site 3 is located to the north of Building 36. Samples were collected through asphalt cover.

The subsurface of this site consists of glacial till and glacial outwash deposits. The depth to groundwater was reported to be 60 feet bgs. Groundwater flow is to the southeast.

## 3.0 SOIL GAS SAMPLING PARAMETERS

Soil gas sampling probes consisted of 7-foot lengths of 3/4-inch diameter hollow steel pipe. The probes were fitted with detachable drive tips and hydraulically pushed and/or pounded to depths of 4 to 5 feet bgs. Where there was not van access the probes were handpounded to depth. A pneumatic rotary hammer drill and air compressor were used to drill holes through the asphalt.

The aboveground end of each probe was fitted with an aluminum reducer (manifold) and a length of polyethylene tubing leading to a vacuum pump. Soil gas was pulled by the vacuum pump into the probe. Samples were collected in a syringe by inserting a syringe needle through a silicone rubber segment in the evacuation line and down into the steel probe. The vacuum was monitored by a vacuum gauge to ensure an adequate gas flow from the vadose zone was maintained.

The volume of air within the probe was purged by evacuating 2 to 5 probe volumes of gas. The evacuation time in minutes versus the vacuum in inches of mercury (Hg) was used to calculate the necessary evacuation time. The vacuum in inches Hg was recorded at each sampling location.

Sample probe vacuums ranged from 2 to 15 inches Hg. The vacuum capacity of the pump was approximately 22 inches Hg.



#### 4.0 ANALYTICAL PARAMETERS

During this investigation, 5 to 10 milliliters (mL) of soil gas were collected for each sample and immediately analyzed in the Tracer Research analytical van. Subsamples (replicates) from these samples were injected into the gas chromatograph (GC) in volumes of 1 to 1,000 microliters ( $\mu\text{L}$ ).

Analytical instruments were calibrated daily using fresh working standards made from National Institute of Sciences and Technology (NIST) traceable standards and reagent blanked solvents.

##### 4.1 Chromatographic System

A Hewlett Packard 5890 Series II gas chromatograph, equipped with a flame ionization detector (FID) and one computing integrator, was used for the soil gas analyses. The compounds were separated in the GC on one 6 foot by 1/8 inch outer diameter (OD) packed analytical column (10% TCEP stationary phase bonded to 80/100 mesh Chromosorb PAW support) in a temperature controlled oven. Nitrogen was used as the carrier gas.

The instrument calibrations were checked periodically throughout the day to monitor the response factor and retention time. The following paragraphs explain the GC and FID processes.

##### GC Process

The soil gas is injected into the GC where it is swept through the analytical column by the carrier gas. The detector senses the presence of a component different from the carrier gas and converts that information to an electrical signal. The components of the sample pass through the column at different rates, according to their individual properties, and are detected by the detector. Compounds are identified by the time it takes them to pass through the column (retention time).



### FID Process

The FID utilizes a flame produced by the combustion of hydrogen and air. When a component, which has been separated on the GC analytical column, is introduced into the flame, a large increase in ions occurs. A collector with a polarizing voltage is applied near the flame and the ions are attracted and produce a current, which is proportional to the amount of the sample compound in the flame. The electrical current causes the computing integrator to record a peak on a chromatogram. By measuring the area of the peak and comparing that area to the integrator response of a known aqueous standard, the concentration of the analyte in the sample is determined.

### 4.2 Analyses

The detection limits for target compounds depend on the sensitivity of the detector to the individual compound as well as the volume of the sample injection. The detection limits of the target compounds were calculated from the response factors, the sample injection sizes, and the calculated minimum peak size (area) observed under the conditions of the analyses. If any compound was not detected in an analysis, the detection limit is given as a "less than" value, e.g.,  $<0.01 \mu\text{g/L}$ . The approximate detection limits for the target compounds are presented in Table 2.

Table 2. Detection Limits for Target Compounds

Compound	Detection Limits ( $\mu\text{g/L}$ )
benzene	0.01
toluene	0.02
ethylbenzene	0.03
xylene	0.05
TVHC	0.05





## 5.0 QUALITY ASSURANCE AND QUALITY CONTROL

Tracer Research's Quality Assurance (QA) and Quality Control (QC) program was followed to maintain data that was reproducible through the investigation. An overview presenting the significant aspects of this program is presented below.

### Soil Gas Sampling Quality Assurance

To ensure consistent collection of samples, the following procedures are performed:

#### - Sampling Manifolds

Tracer Research's custom designed sampling manifold connects the sample probe to the vacuum line and pump. The manifold is designed to eliminate sample exposure to the polymeric (plastic) materials that connect the probe to the vacuum pump.

The sampling manifold is attached to the end of the probe, forming an air tight union between the probe and the silicone tubing septum. The septum connects the manifold to the pump vacuum line and permits syringe sampling.

This sampling system allows the sample to be taken upstream of the sampling pump, manifold, and septum. Since cross contamination of sampling equipment can be a major problem, Tracer Research replaces the materials (probe and syringe), between sampling points, that contact the soil gas before or during sampling.

#### -Sampling Probes

Steel probes are used only once each day. To eliminate the possibility of cross contamination, they are washed with high pressure soap and hot water spray, or steam-cleaned. Enough sampling probes are carried on each van to avoid the need to re-use any during the day.



#### -Glass Syringes

Glass syringes are used for only one sample a day and are washed and baked out at night. If they must be used twice, they are purged with carrier gas (nitrogen) and baked out between probe samplings.

#### -Sampling Efficiency

Soil gas pumping is monitored by a vacuum gauge to ensure that an adequate flow of gas from the soil is maintained. A reliable gas sample can be obtained if the sample vacuum gauge reading is at least 2 inches Hg less than the maximum measured vacuum of the vacuum pump.

#### Analytical Quality Assurance Samples

Quality assurance samples are performed at the minimum frequencies listed in Table 3. The actual frequency depends on the number of samples analyzed each day and the length of time of the survey.

Table 3. Quality Assurance Samples

Sample type	Frequency
Ambient Air Samples	3 per day or 1 per site
Analytical Method Blanks	5% (1 per 20 samples or 1 a day)
Continuing Calibration Check	20% (1 every 5 samples)
Field System Blank	1 per day
Reagent Blank	1 per set of working standards
Replicate Samples	10 to 100% of all samples

The ambient air samples are obtained on site by sampling the air immediately outside the mobile analytical van and directly injecting it into the GC. Analytical method blanks are taken to demonstrate that the analytical instrumentation is not contaminated. These are performed by injecting carrier gas (nitrogen) into the GC with the sampling syringe. Subsampling syringes are also checked in this fashion.



The injector port septa through which soil gas samples are injected into the GC are replaced daily to prevent possible gas leaks from the chromatographic column. All sampling and subsampling syringes are decontaminated after use and are not used again until they have been decontaminated by washing in anionic detergent and baking at 90°C.

Field system blanks are analyzed to check for contamination of the sampling apparatus, e.g., probe and sampling syringe. A sample is collected using standard soil gas sampling procedures, but without putting the probe into the ground. The results are compared to those obtained from a concurrently sampled ambient air analysis.

If the blanks detect compounds of interest at concentrations that indicate equipment contamination or concentrations that exceed normal background levels (ambient air analysis), corrective actions are performed. If the problem cannot be corrected, an out-of-control event is documented and reported. Field system blanks are not performed every day if clean probes are still available. Field system blanks are performed after any probe decontamination process.

A reagent blank is performed to ensure the solvent used to dilute the stock standards is not contaminated. Analytical instruments are calibrated daily using fresh working standards made from National Institute of Sciences and Technology traceable standards and reagent blanked solvents.

Quantitative precision is assured by replicating analysis of 10 to 100 percent of the samples. The percentage is based on the sample analysis time. Replicate analyses are performed by subsampling vapors from the same sampling syringe.

## 6.0 RESULTS

The analytical results from this soil gas investigation are condensed in Appendix A. The data are presented by location and by analyte concentration. When the compound was not detected, the detection limit is presented as a "less than" value, e.g., <0.01 µg/L. TVHC is defined as total volatile hydrocarbons in the range of C1 through C9.

Soil gas samples are identified by sample location and sampling depth. For



example, S2-2-4' represents a soil gas sample collected at Site 2 location 2 at a depth of 4 feet bgs.




APPENDIX A Condensed Data

TRACER RESEARCH CORPORATION - ANALYTICAL RESULTS  
 OPERATIONAL TECHNOLOGIES CORPORATION/ ROSLYN AIR NATIONAL GUARD STATION/ ROSLYN, NEW YORK/ 9-93-287-S  
 09/13/93

SAMPLE	BENZENE		TOLUENE		ETHYL BENZENE		XYLENES		TVHC C1 - C9	
	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
AIR	0.04	0.04	0.04	<0.03	<0.05	<0.05	<0.05	<0.05	1	
S3-2-5'	0.04	0.06	0.06	<0.03	<0.05	<0.05	<0.05	<0.05	0.7	
S3-1-5'	0.01	0.02	0.02	<0.03	<0.05	<0.05	<0.05	<0.05	0.5	
S3-5-5'	0.04	<0.02	<0.02	<0.03	<0.05	<0.05	<0.05	<0.05	0.7	
S3-3-5'	0.03	<0.02	<0.02	<0.03	<0.05	<0.05	<0.05	<0.05	0.4	
S3-4-5'	0.03	<0.02	<0.02	<0.03	<0.05	<0.05	<0.05	<0.05	0.7	
S3-6-5'	0.05	0.07	0.07	<0.03	<0.05	<0.05	<0.05	<0.05	2	
S3-8-5'	<0.03	<0.06	<0.06	<0.1	<0.2	<0.2	<0.2	<0.2	340*	
S3-7-5'	<0.2	<0.06	<0.06	<0.1	<0.2	<0.2	<0.2	<0.2	1500*	
S3-9-5'	<10	19	19	2	12	12	12	12	27000	
AIR	0.03	0.05	0.05	<0.03	<0.05	<0.05	<0.05	<0.05	1	
S1-31-5'	<0.01	<0.02	<0.02	<0.03	<0.05	<0.05	<0.05	<0.05	0.3	
S1-28-5'	0.1	<0.02	<0.02	<0.03	<0.05	<0.05	<0.05	<0.05	0.8	
S1-25-5'	0.02	0.04	0.04	<0.03	<0.05	<0.05	<0.05	<0.05	1	
S1-22-5'	0.06	0.02	0.02	<0.03	<0.05	<0.05	<0.05	<0.05	1	
S1-19-5'	0.03	0.02	0.02	<0.03	<0.05	<0.05	<0.05	<0.05	2	
S1-16-5'	0.03	<0.02	<0.02	<0.03	<0.05	<0.05	<0.05	<0.05	5	
S1-13-5'	<0.1	<0.2	<0.2	<0.3	<0.5	<0.5	<0.5	<0.5	1300*	
S1-10-5'	<0.2	<0.4	<0.4	<0.6	<0.9	<0.9	<0.9	<0.9	30000*	
S1-7-5'	<0.1	<0.2	<0.2	<0.3	<0.5	<0.5	<0.5	<0.5	1300*	

\* TVHC may contain elevated levels of nonaromatic compounds

Analyzed by: L. Schenmeyer  
 Proofed by: M. Schenmeyer



TRACER RESEARCH CORPORATION - ANALYTICAL RESULTS  
OPERATIONAL TECHNOLOGIES CORPORATION/ ROSLYN AIR NATIONAL GUARD STATION/ ROSLYN, NEW YORK/ 9-93-287-S  
09/13/93

SAMPLE	BENZENE µg/L	TOLUENE µg/L	ETHYL BENZENE µg/L	XYLENES µg/L	TVHC C1 - C9 µg/L
S1-4-5'	<0.03	<0.06	<0.1	<0.2	540*
S1-1-5'	0.2	0.02	<0.03	<0.05	4
S1-2-5'	0.01	<0.02	<0.03	<0.05	150*
S1-5-5'	<0.1	<0.2	<0.3	<0.5	1300*
S1-8-5'	<0.03	<0.06	<0.1	<0.2	740*
AIR	0.02	<0.02	<0.03	<0.05	1

\* TVHC may contain elevated levels of nonaromatic compounds

Analyzed by: L. Schenmeyer  
Proofed by: M. Stiles

TRACER RESEARCH CORPORATION - ANALYTICAL RESULTS  
 OPERATIONAL TECHNOLOGIES CORPORATION/ ROSLYN AIR NATIONAL GUARD STATION/ ROSLYN, NEW YORK/ 9-93-287-S  
 09/14/93

SAMPLE	BENZENE		TOLUENE		ETHYL BENZENE		XYLENES		TVHC C1 - C9	
	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
AIR	0.05	0.2	<0.03	<0.05	2					
SI-11-5'	<0.1	<0.1	<0.2	<0.2	1900*					
SI-14-5'	<0.2	<0.2	<0.3	<0.5	3800*					
SI-17-5'	<0.05	0.2	<0.2	<0.2	500*					
SI-20-5'	0.04	0.2	<0.03	0.2	2					
SI-26-5'	0.09	0.1	<0.03	0.2	2					
SI-32-5'	0.03	0.2	<0.03	<0.05	0.7					
SI-33-5'	0.01	0.02	<0.03	<0.05	1					
SI-30-5'	0.01	0.02	<0.02	<0.02	0.8					
SI-27-5'	0.03	0.1	<0.03	0.1	1					
SI-24-5'	0.02	0.04	<0.03	0.1	2					
AIR	0.03	0.07	<0.03	0.1	2					
SI-21-5'	0.02	0.1	<0.03	0.1	1					
SI-18-4'	<0.2	<0.4	<0.7	<0.9	1700*					
SI-15-5'	<0.2	<0.4	<0.7	<1	4600*					
SI-12-5'	<0.2	<0.4	<0.7	<1	3600*					
SI-9-5'	<0.1	<0.2	<0.3	<0.5	1600*					
AIR	0.01	0.03	<0.03	<0.05	1					

\* TVHC may contain elevated levels of nonaromatic compounds

Analyzed by: L. Scheinmeyer  
 Proofed by: MS



TRACER RESEARCH CORPORATION - ANALYTICAL RESULTS  
 OPERATIONAL TECHNOLOGIES CORPORATION/ ROSLYN AIR NATIONAL GUARD STATION/ ROSLYN, NEW YORK/ 9-93-287-S  
 09/14/93

SAMPLE	BENZENE		TOLUENE		ETHYL BENZENE		XYLENES		TVHC	
	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	C1 - C9	µg/L
S1-6-5'	<0.02		<0.04		<0.07		<0.1		280*	
S1-3-5'	0.04		0.09		<0.03		<0.05		1	
S3-11-5'	<0.03		<0.06		<0.1		<0.2		420*	
S3-10-5'	0.01		<0.02		<0.03		<0.05		0.6	
AIR	0.03		0.04		<0.03		<0.05		1	
S2-15-5'	<0.01		0.02		<0.03		<0.05		0.7	
S2-16-5'	0.01		0.02		<0.03		<0.05		0.3	
S2-12-5'	<2		<4		<7		<10		18000*	
S2-7-5'	<0.2		<0.4		<0.7		<1		6000*	
S2-10-5'	<0.1		<0.2		<0.3		<0.5		540*	

\* TVHC may contain elevated levels of nonaromatic compounds

Analyzed by: L. Schenmeyer

Proofed by: ML



Tracer Research Corporation

TRACER RESEARCH CORPORATION - ANALYTICAL RESULTS  
 OPERATIONAL TECHNOLOGIES CORPORATION/ ROSLYN AIR NATIONAL GUARD STATION/ ROSLYN, NEW YORK/ 9-93-287-S  
 09/15/93

SAMPLE	BENZENE µg/L	TOLUENE µg/L	ETHYL BENZENE µg/L	XYLENES µg/L	TVHC C1 - C9 µg/L
AIR	0.03	0.03	<0.04	<0.05	1
S2-2-4'	0.01	0.02	<0.04	<0.05	0.5
S2-3-5'	0.07	0.9	<0.04	<0.05	18
S2-4-4'	0.01	<0.02	<0.04	<0.05	2
S2-6-5'	0.01	1	<0.04	<0.05	72
S2-5-5'	0.4	0.2	<0.04	0.2	2
S2-1-5'	<0.01	0.05	<0.04	0.1	3
S2-8-5'	0.07	0.06	<0.04	0.1	1
S2-9-5'	<2	110	<7	<10	14000*
S2-11-5'	<0.01	<0.02	<0.04	<0.05	1
S2-13-5'	<0.2	28	<0.7	<1	2000*
S2-14-5'	<0.01	<0.02	<0.04	<0.05	0.9
AIR	<0.01	<0.02	<0.04	<0.05	1

\* TVHC may contain elevated levels of nonaromatic compounds

Analyzed by: L. Schenmeyer

Proofed by: MS



Tracer Research Corporation appreciates the opportunity of being of service to your organization. Because we are constantly striving to improve our service to you, we welcome any comments or suggestions you may have about how we can be more responsive to the needs of your organization. If you have any questions about the field work, analytical results, or this report, please give Marty Favero a call at (602) 888-9400.

**APPENDIX C**

**WELL CONSTRUCTION DIAGRAMS**

**THIS PAGE INTENTIONALLY LEFT BLANK**


## SECTION C.1 INTRODUCTION

Well construction diagrams have been completed for each piezometer and monitoring well installed as part of the Site Investigation. Diagrams are presented in numerical order. The diagrams include water level data and well construction information for each individual well. Well construction information includes an outline of the wellbore, depth of the borehole, the screened interval, and the sand packed and bentonite seal interval. Due to the collapse and subsequent abandonment, there is no well construction diagram for piezometer 3 (PS-3).

**THIS PAGE INTENTIONALLY LEFT BLANK**

Project: Roslyn ANGSI  
Town/City: Roslyn  
County: Nassau State: New York  
TOC Elev: 204.25 ft.  
Ground Elev.: 204.38 ft.  
Water Level: 142.24 ft. TOC  
Total Well Depth: 48.88 ft.

Date Installed: May 2-6, 1994  
Drilling Contractor: Water Resources, Inc.  
Drilling Method: O-DEX  
Borehole Diameter: 6 in.  
Development Technique: Electric Submersible Pump  
Not To Scale




WELL CONSTRUCTION LOG  
Well No. 01-001MW

O P T E C H  
OPERATIONAL TECHNOLOGIES  
CORPORATION  
JULY 1994 ROSLYN\01-001MW



Project: <u>Roslyn ANGSI</u>	Date Installed: <u>May 11-12, 1994</u>
Town/City: <u>Roslyn</u>	Drilling Contractor: <u>Water Resources, Inc.</u>
County: <u>Nassau</u> State: <u>New York</u>	Drilling Method: <u>O-DEX</u>
TOC Elev: <u>203.35 ft.</u>	Borehole Diameter: <u>6 in.</u>
Ground Elev.: <u>203.66 ft.</u>	Development Technique: <u>Electric Submersible Pump</u>
Water Level: <u>141.56 ft.</u> TOC	Not To Scale
Total Well Depth: <u>48.68 ft.</u>	




WELL CONSTRUCTION LOG  
Well No. 02-001MW

OPTech  
OPERATIONAL TECHNOLOGIES  
CORPORATION  
JULY 1994 ROSLYN\02-001MW

Project: Roslyn ANGSI  
Town/City: Roslyn  
County: Nassau State: New York  
TOC Elev: 201.22 ft.  
Ground Elev.: 201.53 ft.  
Water Level: 139.63 ft. TOC  
Total Well Depth: 48.3 ft.

Date Installed: May 9-10, 1994  
Drilling Contractor: Water Resources, Inc.  
Drilling Method: O-DEX  
Borehole Diameter: 6 in.  
Development Technique: Electric Submersible Pump  
Not To Scale



WELL CONSTRUCTION LOG  
Well No. 03-001MW

OPT ECH  
OPERATIONAL TECHNOLOGIES  
CORPORATION  
JULY 1994 ROSLYN\03-001MW

Project: Roslyn ANGSI

Town/City: Roslyn

County: Nassau State: New York

TOC Elev: 205.75 ft.

Ground Elev.: 206.01 ft.

Water Level: 144.20 ft. TOC

Total Well Depth: 46.0 ft.

Date Installed: April 22-25, 1994


Drilling Contractor: Water Resources, Inc.

Drilling Method: O-DEX

Borehole Diameter: 6 in.

Development Technique: Not Developed

Not To Scale




WELL CONSTRUCTION LOG  
Well No. PS-2

OPT ECH  
OPERATIONAL TECHNOLOGIES  
CORPORATION  
JULY 1994 ROSLYN/PS2

Project: Roslyn ANGSI  
Town/City: Roslyn  
County: Nassau State: New York  
TOC Elev: 203.10 ft.  
Ground Elev.: 203.42 ft.  
Water Level: 142.25 ft. TOC  
Total Well Depth: 43.3 ft.

Date Installed: April 26-27, 1994  
Drilling Contractor: Water Resources, Inc.  
Drilling Method: O-DEX  
Borehole Diameter: 6 in.  
Development Technique: Not Developed  
Not To Scale



WELL CONSTRUCTION LOG  
Well No. PS-3

O P T E C H  
OPERATIONAL TECHNOLOGIES  
CORPORATION  
JULY 1994 ROSLYN\PS3

**THIS PAGE INTENTIONALLY LEFT BLANK**

**APPENDIX D**

**FIELD GC SCREENING RESULTS**

**THIS PAGE INTENTIONALLY LEFT BLANK**

## SECTION D.1 INTRODUCTION

This section includes the raw Gas Chromatograph (GC) data generated during the field screening of soil samples collected during the drilling of boreholes, and of groundwater samples collected concurrently with groundwater sampling. Table D-1 summarize the GC screening results for soil and groundwater samples. Table D-2 indicates field GC results from soil cuttings obtained during piezometer and monitoring well drilling. A copy of all field GC chromatograms are also presented.



**Table D-1**  
**Field GC Results of Soil and Groundwater Samples**  
**Roslyn ANGS, Roslyn, New York**

Concentration:	Benzene (ppb)	Toluene (ppb)	Ethyl- benzene (ppb)	m,p- Xylene (ppb)	o- Xylene (ppb)	Total BTEX (ppb)	MTBE (ppb)
Borehole/Interval (ft BLS)							
01-001BH 0.0 - 1.5	ND	ND	ND	ND	ND	ND	NC
01-001BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	NC
01-001BH 10.0 - 11.5	ND	169.9	ND	ND	ND	169.9	NC
01-002BH 0.5 - 2.0	ND	ND	ND	ND	ND	ND	26.36
01-002BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	ND
01-002BH 10.0 - 10.5	ND	ND	ND	ND	ND	ND	ND
01-002BH 10.0 - 10.5 Dup	ND	ND	ND	ND	ND	ND	ND
01-003BH 0.0 - 1.5	ND	ND	ND	ND	ND	ND	NC
01-003BH 6.5 - 8.0	ND	ND	ND	ND	ND	ND	NC
01-003BH 10.0 - 11.5	ND	ND	ND	ND	ND	ND	NC
01-004BH 0.0 - 1.5	35.73	ND	ND	ND	26.52	62.25	NC
01-004BH 5.0 - 6.5	NC	NC	NC	NC	NC	NC	NC
01-004BH 10.0 - 11.5	ND	2.73	ND	ND	ND	2.73	NC
02-001BH 0.0 - 1.5	ND	11.32	ND	ND	ND	11.32	NC
02-001BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	NC
02-001BH 10.0 - 11.5	ND	4.67	ND	ND	ND	4.67	NC
02-002BH 0.0 - 1.5	ND	1.54	1,098.0	ND	9,635.0	10,734.5	NC
02-002BH 5.0 - 6.5	*	*	*	*	*	*	NC
02-002BH 10.0 - 11.5	*	*	*	*	*	*	NC
02-003BH 0.5 - 2.0	ND	ND	ND	ND	ND	ND	ND
02-003BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	ND
02-003BH 10.0 - 11.5	ND	5.25	ND	ND	ND	5.25	ND
02-004BH 0.0 - 0.5	ND	39.33	ND	ND	27.50	66.83	NC
02-004BH 5.0 - 5.5	144.11	7,713.0	885.3	ND	1,554.0	10,296.41	NC
02-005BH 0.0 - 0.5	ND	6.12	ND	ND	ND	6.12	NC
02-005BH 5.0 - 5.5	276.63	2,526.8	531.3	ND	1,710.3	5,045.06	NC
02-006BH 0.0 - 0.5	ND	14.99	ND	ND	12.12	27.11	NC
02-006BH 5.0 - 5.5	ND	15.16	5.40	ND	12.77	33.33	NC
02-007BH 0.0 - 0.5	0.72	104.8	ND	ND	ND	105.5	NC
02-007BH 5.0 - 5.5	2.09	15.90	ND	ND	3.49	21.48	NC
02-008BH 0.0 - 0.5	0.85	ND	1.20	ND	ND	2.05	NC
02-008BH 5.0 - 5.5	ND	21.07	ND	ND	ND	21.07	NC
03-001BH 0.0 - 1.5	2.98	ND	2.49	ND	11.64	17.12	NC
03-001BH 5.0 - 6.5	ND	3.45	ND	ND	ND	3.45	NC
03-001BH 10.0 - 11.5	ND	ND	ND	ND	ND	ND	NC
03-002BH 0.0 - 1.5	ND	3.18	ND	ND	ND	3.18	NC
03-002BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	NC
03-002BH 10.0 - 11.5	ND	ND	3.35	ND	ND	3.35	NC

**Table D-1 (Concluded)**  
**Field GC Results of Soil and Groundwater Samples**  
**Roslyn ANG, Roslyn, New York**

Concentration: Borehole/Interval (ft BLS)	Benzene (ppb)	Toluene (ppb)	Ethyl- benzene (ppb)	m,p- Xylene (ppb)	o- Xylene (ppb)	Total BTEX (ppb)	MTBE (ppb)
03-003BH 0.0 - 1.5	ND	ND	ND	ND	ND	ND	ND
03-003BH 5.0 - 6.5	ND	ND	5.43	ND	ND	5.43	NC
03-003BH 10.0 - 11.5	ND	ND	ND	ND	ND	ND	ND
03-004BH 0.0 - 1.5	ND	ND	12.61	ND	4.78	17.39	NC
03-004BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	NC
03-004BH 10.0 - 11.5	ND	ND	4.09	ND	ND	4.09	NC
03-004BH 10.0 - 11.5 Dup	ND	164.2	ND	ND	ND	164.2	NC
03-005BH 0.5 - 2.0	ND	ND	ND	ND	ND	ND	ND
03-005BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	ND
03-005BH 10.0 - 11.5	ND	ND	ND	ND	ND	ND	ND
03-006BH 0.0 - 1.5	ND	4.22	17.11	ND	37.61	58.94	NC
03-006BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	NC
03-006BH 10.0 - 11.5	ND	ND	ND	ND	ND	ND	NC
BG-001BH 0.0 - 1.5	ND	ND	ND	ND	ND	ND	ND
BG-001BH 5.0 - 6.5	ND	ND	ND	ND	ND	ND	ND
BG-001BH 10.0 - 11.5	ND	ND	ND	ND	ND	ND	ND
01-001MW	ND	ND	ND	ND	ND	ND	NC
02-001MW	ND	ND	12.0	ND	ND	12.0	NC
03-001MW	ND	ND	ND	ND	ND	ND	NC

GC - Gas Chromatograph.

BTEX - Benzene, Toluene, Ethylbenzene, and Xylenes.

MTBE - Methyl-t-butyl-ether.

ft BLS - feet Below Land Surface.

ppb - parts per billion.

BH - Borehole.

BG - Background sample.

MW - Monitoring Well.

Dup - Duplicate sample.

ND - Analyte not detected.

NC - Analysis not conducted.

\* - Analyte concentrations exceeded the maximum calibration range for the field GC and individual analytes were not identified.

**Table D-2**  
**Field GC Results During Piezometers/Monitoring Well Installation**  
**Roslyn ANG, Roslyn, New York**

Concentration:						
Well ID/Interval (ft BLS)	Benzene (ppb)	Toluene (ppb)	Ethylbenzene (ppb)	Xylene (ppb)	Total BTEX (ppb)	MTBE (ppb)
PZ-1-A	ND	ND	ND	ND	ND	ND
PZ-1-B	ND	ND	ND	ND	ND	ND
PZ-1-C	ND	ND	ND	ND	ND	ND
PZ-Drum A Composite	ND	ND	ND	ND	ND	ND
PZ-Drum B Composite	ND	ND	ND	ND	ND	ND
PZ-Drum C Composite	ND	ND	ND	ND	ND	ND
PZ-1 Retest A	ND	ND	ND	ND	ND	51.87
PZ-1 Retest B	ND	ND	ND	ND	ND	ND
PZ-1 Retest C	ND	ND	ND	ND	ND	ND
PZ-1 Retest D	ND	ND	ND	ND	ND	ND
PZ-1 A	ND	10.49	ND	24.56	35.05	ND
PZ-1 B	ND	8.25	ND	24.64	32.89	ND
PZ-1 C	ND	ND	ND	ND	ND	ND
PZ-1 D	ND	ND	ND	ND	ND	ND
Existing Dirt	26.22	27.16	18.42	34.12	105.92	ND
Pile Dirt	ND	18.58	23.27	37.36	79.21	ND
Pile Dirt	ND	ND	ND	9.39	9.39	ND
Pile Dirt	ND	ND	ND	ND	ND	ND
PZ-2 15	ND	6.63	8.33	20.79	35.76	ND
PZ-2 30	ND	ND	ND	ND	ND	ND
PZ-2 30 Dup	14.00	40.72	30.15	57.24	142.11	ND
PZ-2 45	ND	ND	22.62	ND	22.62	ND
PZ-2 60	ND	ND	ND	ND	ND	ND
PZ-2 75	ND	ND	ND	ND	ND	ND
PZ-2 160	ND	ND	ND	5.24	5.24	ND
PZ-3 15	ND	ND	ND	ND	ND	ND
PZ-3 30	ND	ND	ND	ND	ND	ND
PZ-3 45	16.12	37.17	27.39	54.38	135.06	ND
PZ-3 60	ND	6.58	ND	4.13	10.71	ND
PZ-3 90	ND	13.23	30.02	60.95	104.21	ND
PZ-3 105	ND	ND	16.67	ND	16.67	ND
PZ-3 155	ND	ND	ND	ND	ND	ND
(01-001MW)						
MW-1 8	ND	ND	ND	ND	ND	ND
MW-1 45	ND	ND	ND	ND	ND	ND
MW-1 75	ND	ND	ND	ND	ND	ND
MW-1 100	ND	ND	ND	18.89	18.89	ND
MW-1 120	ND	ND	ND	ND	ND	161.0
MW-1 140	ND	ND	ND	ND	ND	616.7
MW-1 155	ND	ND	ND	ND	ND	ND

**Table D-2 (Concluded)**  
**Field GC Results During Piezometers/Monitoring Well Installation**  
**Roslyn ANG, Roslyn, New York**

Concentration:						
Well ID/Interval (ft BLS)	Benzene (ppb)	Toluene (ppb)	Ethylbenzene (ppb)	Xylene (ppb)	Total BTEX (ppb)	MTBE (ppb)
03-001MW 15	ND	ND	ND	ND	ND	ND
03-001MW 35	ND	ND	ND	ND	ND	ND
03-001MW 55	ND	ND	ND	ND	ND	36.20
03-001MW 80	ND	ND	ND	ND	ND	11.31
03-001MW 80 Dup	ND	ND	ND	ND	ND	51.13
03-001MW 100	ND	ND	ND	ND	ND	29.50
03-001MW 140	ND	ND	ND	ND	ND	69.94
03-001MW 153	ND	ND	ND	ND	ND	3.82
02-001MW 30	ND	ND	ND	ND	ND	ND
02-001MW 50	ND	ND	ND	ND	ND	ND
02-001MW 85	ND	ND	ND	ND	ND	ND
02-001MW 100	ND	ND	ND	ND	ND	394.7
02-001MW 130	ND	ND	ND	ND	ND	79.22
02-001MW 145	ND	ND	ND	ND	ND	ND
02-001MW 155	ND	ND	ND	ND	ND	9.2
02-001MW 155 Dup	ND	ND	ND	ND	ND	21.52
Water						
01-001MW	ND	ND	ND	ND	ND	ND
02-001MW	ND	ND	12.00	ND	12.00	ND
03-001MW	ND	ND	ND	ND	ND	ND

GC - Gas Chromatograph.

BTEX - Benzene, Toluene, Ethylbenzene, and Xylenes.

MTBE - Methyl-t-butyl-ether.

ft BLS - feet Below Land Surface.

PZ - Piezometer Well.

MW - Monitoring Well.

Dup - Duplicate sample.

ND - Analyte not detected.

ppb - parts per billion.

- Notes:
- PZ-1 analyses not identified by interval. GC analysis conducted from grab samples obtained from drummed cuttings.
  - Existing dirt and dirt pile analysis conducted on fill dirt before piezometer/monitoring well soil cuttings were deposited.
  - Numbers following well identification (with the exception of PZ-1) indicate interval (in feet BLS) from which the sample was obtained.


**THIS PAGE INTENTIONALLY LEFT BLANK**

Values stored in  
Library

# PHOTOVAC

1	COMPOUND	ID #	R.T.	LIMIT
BENZENE	1	78.1	1.000 PPM	
TOLUENE	2	135.6	1.000 PPM	
ETHYLBENZENE	3	243.0	1.000 PPM	
D-XYLENE	4	278.7	1.000 PPM	

# PHOTOVAC




STOP # 630.0  
SAMPLE LIBRARY 1 SEP 21 1993 21:12  
ANALYSIS # 2  
INTERNAL TEMP 27  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	35.2	1.5 US
UNKNOWN	2	46.7	460.2 mUS
UNKNOWN	3	51.7	11.9 US
UNKNOWN	4	176.2	5.4 US
UNKNOWN	5	350.2	2.3 US
UNKNOWN	6	376.2	6.1 US
UNKNOWN	7	442.4	2.3 US

CALIBRANT

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 21:29  
ANALYSIS # 3  
INTERNAL TEMP 27  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	54.1	1.2 US
UNKNOWN	2	63.7	384.1 mUS
BENZENE	3	84.7	2.984 PPB
UNKNOWN	4	106.0	5.7 mUS
UNKNOWN	5	226.8	31.9 mUS
ETHYLBENZENE	6	330.2	2.491 PPB
D-XYLENE	7	460.4	11.64 PPB

03-001  
Depth 0-1.5'

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 21:39  
ANALYSIS # 4  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	36.2	221.5 mUS
UNKNOWN	2	42.8	5.9 mUS
TOLUENE	3	120.2	3.449 PPB
UNKNOWN	4	520.5	11.8 mUS

03-001BH  
Depth 5.0-6.5

Bottle D  
03-001 Depth 10-11.5'

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 22:0  
ANALYSIS # 6  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	43.7	362.3 mUS
UNKNOWN	2	51.3	239.7 mUS
UNKNOWN	4	285.8	18.8 mUS

Bottle D  
03-002 Depth: 0-1.5'

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 22:11  
ANALYSIS # 7  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	35.7	316.9 mUS
UNKNOWN	2	43.3	20.2 mUS
UNKNOWN	3	58.3	28.5 mUS
TOLUENE	4	182.2	3.128 PPB

Bottle E

03-002 Depth 5.0-6.5'

PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 22:46  
ANALYSIS # 8  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.7	79.4 mUS
UNKNOWN	2	34.2	14.9 mUS
UNKNOWN	3	45.9	10.0 mUS
UNKNOWN	4	144.4	19.0 mUS
UNKNOWN	5	532.7	23.0 mUS

03-003 'Depth 0-1.5'

Bottle G

PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 23:10  
ANALYSIS # 10  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	50.1	3.2 US
UNKNOWN	2	58.9	656.9 mUS
UNKNOWN	3	225.6	26.4 mUS

03-003 Depth 10.0-11.5'

Bottle I

PHOTOVAC




STOP # 552.3  
SAMPLE LIBRARY 1 SEP 21 1993 23:33  
ANALYSIS # 12  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	7.5	13.9 mUS
UNKNOWN	2	12.7	58.2 mUS
UNKNOWN	3	46.9	595.6 mUS
UNKNOWN	4	54.3	9.4 mUS
UNKNOWN	6	132.4	15.0 mUS
UNKNOWN	7	214.2	15.0 mUS

03-002 Bottle F

Depth: 10.0-11.5

PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 22:58  
ANALYSIS # 9  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	50.3	1.3 US
UNKNOWN	2	52.3	338.4 mUS
UNKNOWN	4	138.2	18.8 mUS
ETHYLBENZENE	5	186.2	3.346 PPM

03-003 Depth: 5.0-6.5

Bottle H

PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 21 1993 23:21  
ANALYSIS # 11  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	38.3	72.3 mUS
UNKNOWN	2	40.7	5.4 mUS
UNKNOWN	3	51.9	6.7 mUS
UNKNOWN	5	212.4	14.1 mUS
ETHYLBENZENE	6	323.2	5.434 PPM

03-004 Depth: 0-1.5'

Bottle J


PHOTOVAC



STOP # 550.3  
SAMPLE LIBRARY 1 SEP 21 1993 23:44  
ANALYSIS # 13  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	44.3	386.7 mUS
UNKNOWN	2	52.3	12.7 mUS
UNKNOWN	3	138.2	18.1 mUS
ETHYLBENZENE	4	186.2	10.65 PPM
ETHYLBENZENE	5	336.2	1.802 PPM
O-XYLENE	6	480.6	4.728 PPM
UNKNOWN	7	512.4	14.2 mUS

# PHOTOVAC




STOP # 550.0  
 SAMPLE LIBRARY 1 SEP 21 1993 23:57  
 ANALYSIS # 19  
 INTERNAL TEMP 29  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	10.1	14.4 mUS
UNKNOWN	2	11.9	5.5 mUS
UNKNOWN	3	42.1	458.9 mUS
UNKNOWN	4	200.4	32.7 mUS

03-004 Depth 5.0-6.5'  
 Bottle K



# PHOTOVAC




STOP @ 550.0  
 SAMPLE LIBRARY 1 SEP 22 1993 0:7  
 ANALYSIS # 15  
 INTERNAL TEMP 28  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.7	12.3 mUS
UNKNOWN	2	47.3	2.5 US
UNKNOWN	3	54.9	1.1 US
UNKNOWN	4	211.9	1.1 US
ETHYLBENZENE	5	378.2	4.082 PPB

03-004 Depth 10.0-11.5'  
 Bottle L

# PHOTOVAC




STOP @ 550.0  
 SAMPLE LIBRARY 1 SEP 22 1993 0:28  
 ANALYSIS # 17  
 INTERNAL TEMP 29  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.1	517.5 mUS
UNKNOWN	2	36.2	59.7 mUS
UNKNOWN	3	74.7	33.7 mUS
UNKNOWN	4	151.6	123.0 mUS
TOLUENE	5	178.2	4.218 PPB
UNKNOWN	6	223.2	36.5 mUS
UNKNOWN	7	323.2	36.5 mUS
ETHYLBENZENE	8	404.7	17.11 PPB
O-XYLENE	9	424.4	37.01 PPB
UNKNOWN	10	508.3	156.3 mUS

03-006 Bottle  
 Depth 0-1.5 N

# PHOTOVAC




STOP @ 550.0  
 SAMPLE LIBRARY 1 SEP 22 1993 0:49  
 ANALYSIS # 19  
 INTERNAL TEMP 29  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.4	19.6 mUS
UNKNOWN	2	77.1	53.5 US
UNKNOWN	3	316.3	42.8 mUS

03-006 Vial  
 Depth: 10.0-11.5 P

# PHOTOVAC




STOP @ 550.0  
 SAMPLE LIBRARY 1 SEP 22 1993 0:18  
 ANALYSIS # 16  
 INTERNAL TEMP 29  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	39.2	64.0 US
TOLUENE	3	164.2	144.0 PPB
UNKNOWN	4	505.1	205.0 mUS

03-004 Duplicate Bottle  
 Depth 10-11.5' N

# PHOTOVAC




STOP @ 550.0  
 SAMPLE LIBRARY 1 SEP 22 1993 0:39  
 ANALYSIS # 18  
 INTERNAL TEMP 29  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	62.1	4.9 US
UNKNOWN	2	74.3	1.2 US
UNKNOWN	3	105.1	6.6 mUS
UNKNOWN	4	293.3	73.7 mUS

03-006 Bial "O"  
 Depth: 5.0-6.5

# PHOTOVAC




STOP @ 550.0  
 SAMPLE LIBRARY 1 SEP 22 1993 0:59  
 ANALYSIS # 20  
 INTERNAL TEMP 29  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	46.1	48.3 US
UNKNOWN	2	228.3	128.3 mUS
UNKNOWN	3	516.1	19.1 mUS

01-001 BH Bottle A  
 Depth: 0-1.5'

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 1:9  
ANALYSIS # 21  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	59.3	62.3 US
UNKNOWN	2	238.8	46.8 mUS

01-001 BH Vial B  
Depth: 5.0-6.5

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 1:29  
ANALYSIS # 23  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	9.6	16.9 mUS
UNKNOWN	3	50.9	7.0 US
UNKNOWN	4	61.1	1.5 US
UNKNOWN	6	236.4	13.2 mUS

01-003 BH Vial D  
Depth 0.0-1.5'

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 1:49  
ANALYSIS # 25  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.6	20.6 mUS
UNKNOWN	2	51.3	30.9 US
UNKNOWN	3	238.8	24.7 mUS

01-003 BH Vial F  
Depth: 10.0-11.5

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 1:13  
ANALYSIS # 22  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	50.5	162.3 US
UNKNOWN	2	121.2	40.3 mUS
TOLLENE	3	186.2	169.9 PPM

01-001 BH Vial C  
Depth: 10.0-11.5

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 1:39  
ANALYSIS # 24  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	38.2 mUS
UNKNOWN	2	44.0	10.0 US

01-003 BH Vial E  
Depth: 6.5-8.5'

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 1:59  
ANALYSIS # 26  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	23.5	10.8 US
UNKNOWN	2	44.1	1.3 US
UNKNOWN	3	52.3	48.4 mUS
UNKNOWN	4	65.3	540.5 mUS
BENZENE	5	120.2	35.73 PPM
UNKNOWN	6	130.4	172.0 mUS
O-XYLENE	7	487.5	26.52 PPM

01-004 BH Vial G  
Depth: 0-1.5'

# PHOTOVAC




STOP # 552.0  
SAMPLE LIBRARY 1 SEP 22 1993 2:9  
ANALYSIS # 27  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	34.4	8.3 US
TOLUENE	2	167.7	2.732 PFB

01-004BH  
Depth 10-11.5

Vial  
H

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 2:29  
ANALYSIS # 29  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	60.7	44.5 US
UNKNOWN	2	259.8	10.9 μUS

02-002BH  
Depth: 5.0-6.5'

Vial  
J

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 2:49  
ANALYSIS # 31  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	42.8	82.0 US
UNKNOWN	2	61.4	7.2 US
UNKNOWN	3	72.1	11.2 US
UNKNOWN	4	102.7	61.9 μUS
UNKNOWN	5	120.8	1.6 US
UNKNOWN	7	148.4	1.8 US
TOLUENE	8	178.2	1.544 PFB
UNKNOWN	9	218.4	4.5 US
UNKNOWN	10	249.3	2.0 US
UNKNOWN	11	263.3	1.5 US
UNKNOWN	12	326.7	17.7 US
ETHYLBENZENE	13	378.2	1.338 PFB
O-XYLENE	14	412.4	1.738 PFB
O-XYLENE	15	466.4	2.000 PFB
UNKNOWN	16	501.8	22.2 US

02-002BH  
Depth: 0-1.5'

Vial  
S

# PHOTOVAC




STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 2:19  
ANALYSIS # 28  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	41.8	41.8 US
TOLUENE	2	186.7	11.32 PFB

02-002BH  
Depth: 0-1.5'

Vial  
I

# PHOTOVAC



STOP # 550.0  
SAMPLE LIBRARY 1 SEP 22 1993 2:39  
ANALYSIS # 30  
INTERNAL TEMP 28  
GAIN 10


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	42.8	35.4 US
UNKNOWN	2	120.8	31.3 μUS
TOLUENE	3	186.2	4.666 PFB

02-002BH  
Depth 11.5-13

Vial  
K

# PHOTOVAC

START -----




STOP @ 352.0  
 SAMPLE LIBRARY 1 SEP 22 1993 3:1  
 ANALYSIS # 32  
 INTERNAL TEMP 28  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.4	83.4 mUS

02-002 Vial  
 Depth: 5.0-6.5 T

# PHOTOVAC

START -----




STOP @ 550.0  
 SAMPLE LIBRARY 1 SEP 22 1993 3:13  
 ANALYSIS # 33  
 INTERNAL TEMP 28  
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	155.1	4.0 MUS

02-002 Vial  
 Depth: 10-11.5 W

# CALIBRATION SHOT


## PHOTOVAC



STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 14:52  
ANALYSIS # 6  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	33.2	722.4 mUS
BENZENE	2	78.1	257.0 PPB
BENZENE	3	114.4	2.704 PPB
UNKNOWN	4	135.5	3.8 US
TOLUENE	5	204.3	1.134 PPB
UNKNOWN	6	243.3	5.7 US
UNKNOWN	7	278.7	2.2 US

## PHOTOVAC




STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 15:37  
ANALYSIS # 8  
INTERNAL TEMP 31  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.6	42.8 mUS
UNKNOWN	2	44.3	767.4 mUS
UNKNOWN	3	63.3	14.8 mUS
BENZENE	4	91.3	0.760 PPB
UNKNOWN	5	120.0	31.4 mUS
UNKNOWN	6	103.6	673.2 mUS
TOLUENE	7	127.2	2.513 PPB
TOLUENE	8	135.6	35.16 PPB
TOLUENE	9	146.8	458.8 PPB
TOLUENE	10	162.2	133.4 PPB
UNKNOWN	11	171.2	334.2 mUS
UNKNOWN	12	184.2	662.6 mUS
ETHYLBENZENE	13	221.4	263.3 PPB
ETHYLBENZENE	14	241.6	231.1 PPB
O-XYLENE	15	284.3	1.860 PPM
O-XYLENE	16	332.6	664.3 PPB

02-004 Bottle F  
Depth 3.5

## PHOTOVAC




STOP # 452.0  
SAMPLE LIBRARY 1 SEP 24 1993 16:7  
ANALYSIS # 9  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	36.2	103.2 mUS
UNKNOWN	2	48.3	211.0 mUS
UNKNOWN	3	46.2	5.7 mUS
UNKNOWN	4	58.9	105.7 mUS
UNKNOWN	5	62.1	59.9 mUS
BENZENE	6	67.3	1.132 PPB
BENZENE	7	75.3	13.25 PPB
BENZENE	8	80.2	78.41 PPB
UNKNOWN	9	102.7	1.3 US
TOLUENE	10	117.1	25.25 PPB
TOLUENE	11	125.2	84.14 PPB
TOLUENE	12	135.6	1.026 PPM
TOLUENE	13	143.6	318.3 PPB
TOLUENE	14	157.6	248.7 PPB
UNKNOWN	15	171.2	1.3 US
ETHYLBENZENE	16	206.4	602.4 PPB
ETHYLBENZENE	17	225.5	518.5 PPB
O-XYLENE	18	262.4	3.271 PPM
O-XYLENE	19	317.1	1.376 PPM

02-004 Bottle G  
Depth 4'

02-004 Depth 0.0-0.5'  
BOTTLE E


## PHOTOVAC



STOP # 452.0  
SAMPLE LIBRARY 1 SEP 24 1993 15:23  
ANALYSIS # 7  
INTERNAL TEMP 30  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.0	634.4 mUS
TOLUENE	2	114.1	10.15 PPB
TOLUENE	3	120.3	13.01 PPB
TOLUENE	4	143.3	3.712 PPB
O-XYLENE	5	203.3	02.61 PPB
O-XYLENE	6	205.3	4.302 PPB
UNKNOWN	7	286.1	21.3 mUS

# PHOTOVAC




STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 16:36  
ANALYSIS # 11  
INTERNAL TEMP 29  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	52.9	170.4 mUS
UNKNOWN	2	61.5	24.3 mUS
BENZENE	3	78.1	29.87 PFB
BENZENE	4	82.3	50.33 PFB
BENZENE	5	87.7	50.39 PFB
BENZENE	6	96.4	50.32 PFB
UNKNOWN	7	111.4	2.9 US
TOLUENE	8	118.9	1.410 PPM
TOLUENE	9	132.2	438.9 PFB
TOLUENE	10	148.4	610.1 PFB
TOLUENE	11	148.4	3.625 PPM
TOLUENE	12	164.2	1.625 PPM
UNKNOWN	13	184.2	384.4 mUS
ETHYLBENZENE	14	219.4	434.3 PFB
ETHYLBENZENE	15	235.9	162.0 PFB
ETHYLBENZENE	16	246.5	236.5 PFB
O-XYLENE	17	273.8	1.554 PPM

02-004 Vial  
Depth 5' I

# PHOTOVAC




STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 17:9  
ANALYSIS # 13  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.4	16.2 mUS
UNKNOWN	2	11.7	35.8 mUS
UNKNOWN	3	47.5	7.5 mUS
UNKNOWN	4	59.3	191.0 mUS
UNKNOWN	5	62.3	102.0 mUS
BENZENE	6	66.9	11.33 PFB
BENZENE	7	74.7	21.78 PFB
BENZENE	8	87.7	117.4 PFB
BENZENE	9	94.3	126.1 PFB
UNKNOWN	10	121.2	1.0 US
UNKNOWN	11	128.1	355.4 mUS
TOLUENE	12	117.1	1.124 PPM
TOLUENE	13	134.9	20.63 PFB
TOLUENE	14	152.4	882.3 PFB
TOLUENE	15	164.7	489.1 PFB
UNKNOWN	16	201.2	5.5 US
ETHYLBENZENE	17	220.8	302.7 PFB
ETHYLBENZENE	18	257.0	226.6 PFB
O-XYLENE	19	273.8	350.3 PFB
O-XYLENE	20	302.5	760.0 PFB

02-005, Vial  
Depth 5ft P

# PHOTOVAC




STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 17:39  
ANALYSIS # 16  
INTERNAL TEMP 28  
GAIN 18

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	39.9	141.7 mUS
UNKNOWN	4	112.0	69.6 mUS
TOLUENE	5	135.2	15.16 PFB
UNKNOWN	6	194.2	25.8 mUS
ETHYLBENZENE	8	223.8	2.226 PFB
ETHYLBENZENE	9	239.5	0.986 PFB
ETHYLBENZENE	10	254.9	2.189 PFB
O-XYLENE	11	261.9	9.030 PFB
O-XYLENE	12	323.2	3.625 PFB

02-006  
5 FT Vial  
R

# PHOTOVAC




STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 16:52  
ANALYSIS # 12  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	33.6	51.7 mUS
UNKNOWN	2	50.1	17.9 mUS
UNKNOWN	3	111.1	38.4 mUS
TOLUENE	4	139.6	6.115 PFB

02-005 Vial  
Depth 0.0-0.5' J

# PHOTOVAC




STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 17:17  
ANALYSIS # 14  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.9	32.5 mUS
UNKNOWN	2	28.3	145.9 mUS
UNKNOWN	5	111.1	110.9 mUS
TOLUENE	6	150.6	14.39 PFB
UNKNOWN	9	186.2	17.4 mUS
UNKNOWN	9	189.2	20.9 mUS
O-XYLENE	12	311.5	10.10 PFB

02-006 Vial  
Depth: 0.0-0.5ft Q

# PHOTOVAC



STOP # 450.0  
SAMPLE LIBRARY 1 SEP 24 1993 17:51  
ANALYSIS # 17  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.2	41.0 mUS
UNKNOWN	2	39.3	47.2 mUS
BENZENE	3	80.4	0.718 PFB
TOLUENE	4	136.3	104.3 PFB
UNKNOWN	5	192.7	16.2 mUS

02-007 Vial  
Depth 0.0-0.5ft S

# PHOTOVAC

START # 1

# 2  
# 3  
# 4  
# 5  
# 6  
# 7  
# 8  
# 9  
# 10  
# 11

STOP # 450.0

SAMPLE LIBRARY 1 SEP 24 1993 18:3  
ANALYSIS # 18  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	14.4 μS
UNKNOWN	2	32.3	35.2 μS
BENZENE	3	65.1	2.563 PPB
BENZENE	4	82.3	0.383 PPB
BENZENE	5	20.1	0.325 PPB
TOLUENE	7	110.2	12.13 PPB
TOLUENE	8	129.2	3.373 PPB
D-XYLENE	11	261.2	3.463 PPB

02-007 Vial  
Depth 5.0-5.5 FT V

# PHOTOVAC

START

# 1  
# 2  
# 3  
# 4  
# 5  
# 6

STOP # 450.0

SAMPLE LIBRARY 1 SEP 24 1993 18:13  
ANALYSIS # 19  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	51.7	85.2 μS
BENZENE	2	73.3	0.253 PPB
UNKNOWN	3	105.1	116.0 μS
UNKNOWN	4	188.7	13.8 μS
ETHYLBENZENE	5	204.3	1.197 PPB
UNKNOWN	6	364.2	10.7 μS

02-008 Vial  
Depth 0.0-0.5 FT W

# PHOTOVAC

START

# 1  
# 2  
# 3  
# 4  
# 5  
# 6  
# 7


STOP # 450.0

SAMPLE LIBRARY 1 SEP 24 1993 18:23  
ANALYSIS # 20  
INTERNAL TEMP 28  
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	41.9	18.5 μS
UNKNOWN	2	45.9	7.2 μS
TOLUENE	5	114.7	18.30 PPB
TOLUENE	6	143.6	2.766 PPB
UNKNOWN	7	194.2	17.0 μS

02-008 Vial  
Depth 5 FT


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 15:50  
 ANALYSIS # 23 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGOS  
 GAIN 20 STANDARD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	13.3	158.6 mUS
UNKNOWN	2	20.5	1.3 US
UNKNOWN	3	22.9	1.3 US
UNKNOWN	4	29.2	2.4 US
UNKNOWN	5	41.1	5.9 US
UNKNOWN	6	75.2	1.8 US
UNKNOWN	7	115.7	11.2 mUS
UNKNOWN	8	184.1	51.5 mUS
ETHYLBENZENE	10	200.7	3.529 PPM
UNKNOWN	11	250.1	441.6 mUS
UNKNOWN	12	412.5	470.7 mUS


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 16:11  
 ANALYSIS # 25 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGOS  
 GAIN 20 60-821EH 2-1.5

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	13.3	100.7 mUS
UNKNOWN	2	20.6	265.1 mUS
UNKNOWN	3	116.4	11.0 mUS

# PHOTOVAC




STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 16:28  
 ANALYSIS # 37 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGOS  
 GAIN 20 60-821EH 2-1.5  
 10.0-11.5

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	20.2	1.9 US
UNKNOWN	2	115.6	10.5 mUS
UNKNOWN	4	406.9	146.9 mUS

# PHOTOVAC

1	COMPOUND	ID #	R.T.	LIMIT
MTBE	1	29.2	1.000 PPM	
BENZENE	2	41.1	1.000 PPM	
TOLUENE	3	75.2	1.000 PPM	
ETHYLBENZENE	4	184.1	1.000 PPM	
MP XYLENE	5	200.7	1.000 PPM	
O XYLENE	6	250.1	1.000 PPM	


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 16:28  
 ANALYSIS # 35 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGOS  
 GAIN 20 60-821EH 2-1.5  
 5.0-6.5

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	20.2	1.2 US
UNKNOWN	2	115.5	11.2 mUS

# PHOTOVAC




STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 16:3  
 ANALYSIS # 34 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGOS  
 GAIN 20 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	163.8 mUS
UNKNOWN	2	20.7	137.2 mUS
UNKNOWN	3	115.0	12.4 mUS




# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.4	152.5 mUS
UNKNOWN	2	21.0	2.2 US
TOLUENE	3	87.3	5.250 PPB
UNKNOWN	4	116.0	12.2 mUS
UNKNOWN	6	413.7	25.2 mUS

# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.9	224.0 mUS
UNKNOWN	2	21.5	292.5 mUS
UNKNOWN	3	116.3	12.5 mUS

# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.2	404.4 mUS
UNKNOWN	2	24.0	505.7 mUS
UNKNOWN	4	38.0	16.3 mUS
UNKNOWN	5	116.0	11.6 mUS

# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	303.9 mUS
UNKNOWN	2	23.0	5.9 US
UNKNOWN	3	31.0	4.2 US
UNKNOWN	4	45.8	7.6 US
UNKNOWN	5	84.8	1.9 US
UNKNOWN	7	209.7	104.5 mUS
ETHYLBENZENE	8	228.5	598.0 PPB
UNKNOWN	9	280.7	517.5 mUS

# PHOTOVAC



COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	204.0 mUS
UNKNOWN	2	21.5	216.6 mUS
UNKNOWN	3	24.2	76.0 mUS
UNKNOWN	4	115.7	13.8 mUS

# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.4	200.7 mUS
UNKNOWN	2	21.4	589.7 mUS
UNKNOWN	3	116.0	12.3 mUS
UNKNOWN	6	420.1	9.2 mUS

# PHOTOVAC

1	COMPOUND	ID #	R.T.	LIMIT
MTBE		1	31.6	1.000 PPM
BENZENE		2	45.8	1.000 PPM
TOLUENE		3	84.8	1.000 PPM
ETHYLBENZENE		4	209.7	1.000 PPM
MP XYLENE		5	228.5	1.000 PPM
O XYLENE		6	280.7	1.000 PPM

# PHOTOVAC



STOP @ 150.0  
 SAMPLE LIBRARY 1 APR 7 1994 13:45  
 ANALYSIS # 22 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGUS  
 GAIN 20 STANDARD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	20.0	1.7 US
UNKNOWN	2	22.7	1.0 US
UNKNOWN	3	28.3	3.0 US
UNKNOWN	4	40.5	7.8 US
UNKNOWN	5	74.0	2.8 US
UNKNOWN	6	115.5	14.6 mUS
UNKNOWN	8	180.1	94.9 mUS
UNKNOWN	9	196.7	4.444 PPM
ETHYLBENZENE	10	245.9	861.1 mUS
UNKNOWN	11	487.7	625.5 mUS


# PHOTOVAC

CALIBRATED PEAK 4, BENZENE

SAMPLE LIBRARY 1 APR 7 1994 13:51  
 ANALYSIS # 22 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGUS  
 GAIN 20 STANDARD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	20.0	1.7 US
UNKNOWN	2	22.7	1.0 US
MTBE	3	28.3	940.6 PPB
BENZENE	4	40.5	1.000 PPM
TOLUENE	5	74.0	719.7 PPB
UNKNOWN	6	115.5	14.6 mUS
UNKNOWN	8	180.1	497.7 PPB
ETHYLBENZENE	9	196.7	743.3 PPB
MP XYLENE	10	245.9	887.3 PPB
O XYLENE	11	487.7	625.5 mUS

# PHOTOVAC



STOP @ 150.0  
 SAMPLE LIBRARY 1 APR 7 1994 14:1  
 ANALYSIS # 23 MARY ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGUS  
 GAIN 20 STANDARD


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	397.3 mUS
UNKNOWN	2	24.8	17.1 US
UNKNOWN	3	34.2	18.3 US
UNKNOWN	4	49.2	12.4 US
UNKNOWN	5	91.2	4.6 US
UNKNOWN	8	225.1	1.0 US
O XYLENE	9	240.2	2.263 PPM
UNKNOWN	10	298.7	924.7 mUS

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

MTBE	1	34.2	1.000 PPM
BENZENE	2	45.2	1.000 PPM
TOLUENE	3	91.2	1.000 PPM
ETHYLBENZENE	4	225.1	1.000 PPM
MP XYLENE	5	240.2	1.000 PPM
O XYLENE	6	298.7	1.000 PPM


# PHOTOVAC



STOP @ 150.0  
 SAMPLE LIBRARY 1 APR 7 1994 14:13  
 ANALYSIS # 24 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGUS  
 GAIN 20 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	20.0	684.1 mUS
UNKNOWN	2	115.9	14.0 mUS


# PHOTOVAC



STOP @ 150.0  
 SAMPLE LIBRARY 1 APR 7 1994 14:23  
 ANALYSIS # 25 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGUS  
 GAIN 20 02-003PM 15-2.0

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	288.8 mUS
UNKNOWN	2	28.9	311.7 mUS
UNKNOWN	3	52.9	24.2 mUS
UNKNOWN	4	116.1	12.6 mUS


# PHOTOVAC



STOP @ 150.0  
 SAMPLE LIBRARY 1 APR 7 1994 14:40  
 ANALYSIS # 26 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGUS  
 GAIN 20 02-003PM 5-6.5

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.4	374.9 mUS
UNKNOWN	2	23.2	345.2 mUS
UNKNOWN	3	117.2	9.2 mUS

# PHOTOVAC




STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 12:38  
 ANALYSIS # 15 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGOS  
 GAIN 20 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.6	172.6 $\mu$ S
UNKNOWN	2	20.9	959.8 $\mu$ S
UNKNOWN	3	23.7	1.5 US
UNKNOWN	4	29.9	4.4 US
UNKNOWN	5	42.9	9.0 US
UNKNOWN	6	78.5	4.4 US
UNKNOWN	8	116.1	16.8 $\mu$ S
UNKNOWN	10	192.7	219.5 $\mu$ S
UNKNOWN	11	210.1	1.5 US
UNKNOWN	12	260.8	1.2 US

# PHOTOVAC

1	COMPOUND	ID #	R.T.	LIMIT
MTBE	1	29.9	1.000 PPM	
BENZENE	2	42.9	1.000 PPM	
TOLUENE	3	78.5	1.000 PPM	
ETHYLBENZENE	4	192.7	1.000 PPM	
MP XYLENE	5	210.1	1.000 PPM	
O XYLENE	6	260.8	1.000 PPM	


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 12:56  
 ANALYSIS # 16 MARK ESCOBAR  
 INTERNAL TEMP 15 ROSLYN ANGOS  
 GAIN 20 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	13.2	1.3 US
UNKNOWN	2	21.8	197.7 $\mu$ S
UNKNOWN	3	115.3	15.9 $\mu$ S


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 13:06  
 ANALYSIS # 17 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGOS  
 GAIN 20 01-002BH .5-2.0

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.1	585.1 $\mu$ S
UNKNOWN	2	24.8	433.5 $\mu$ S
MTBE	3	28.6	26.36 PPB
UNKNOWN	4	119.1	12.9 $\mu$ S


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 13:15  
 ANALYSIS # 18 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGOS  
 GAIN 20 01-002BH 5-6.5

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.5	1.1 US
UNKNOWN	2	115.3	14.8 $\mu$ S

# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 13:24  
 ANALYSIS # 19 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGOS  
 GAIN 20 01-002BH 10-10.5


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	19.8	1.8 US
UNKNOWN	2	39.3	7.1 $\mu$ S
UNKNOWN	3	57.4	36.4 $\mu$ S
UNKNOWN	4	71.3	7.1 $\mu$ S
UNKNOWN	6	115.3	15.1 $\mu$ S

# PHOTOVAC

STOP # 1.7  
 SAMPLE LIBRARY 1 APR 7 1994 13:26  
 ANALYSIS # 20 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGOS  
 GAIN 20 01-002BH 10-10.5

COMPOUND NAME	PEAK	R.T.	AREA/PPM
---------------	------	------	----------

# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 7 1994 13:34  
 ANALYSIS # 21 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGOS  
 GAIN 20 01-002BH DUPP

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.5	145.6 $\mu$ S
UNKNOWN	2	20.8	486.8 $\mu$ S
UNKNOWN	3	115.8	15.0 $\mu$ S
UNKNOWN	5	157.9	9.9 $\mu$ S

# PHOTOVAC

APR 13 1994 8:28

FIELD: 30  
POWER: 51

SAMPLE	8.0	12.0
CAL	0.0	0.0
EVENT 3	0.0	100.0
EVENT 4	0.0	0.0
EVENT 5	0.0	0.0
EVENT 6	0.0	0.0
EVENT 7	0.0	0.0
EVENT 8	0.0	0.0

# PHOTOVAC

START 1 2

3

STOP 4 400.0

SAMPLE LIBRARY 1 APR 13 1994 9:15  
ANALYSIS # 3 MARK ESCOBAR  
INTERNAL TEMP 11 ROSLYN ANG  
GAIN 5 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.1	23.6 $\mu$ S
UNKNOWN	2	22.0	10.8 $\mu$ S

# PHOTOVAC

START 1 2

3

4

5

6

7

STOP 4 400.0

SAMPLE LIBRARY 1 APR 13 1994 9:53  
ANALYSIS # 6 MARK ESCOBAR  
INTERNAL TEMP 13 ROSLYN ANG  
GAIN 5 RECALIBRATE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	25.4	44.8 $\mu$ S
UNKNOWN	2	38.1	180.3 $\mu$ S
UNKNOWN	3	55.9	6.8 $\mu$ S
UNKNOWN	4	106.8	6.7 $\mu$ S
UNKNOWN	5	254.0	5.3 $\mu$ S
UNKNOWN	6	275.3	13.1 $\mu$ S
UNKNOWN	7	329.9	3.9 $\mu$ S

# PHOTOVAC

START 1 2

3

4

5

6

7

8

STOP 4 450.0

SAMPLE LIBRARY 1 APR 13 1994 8:52  
ANALYSIS # 1 MARK ESCOBAR  
INTERNAL TEMP 9 ROSLYN ANG  
GAIN 5 STANDARD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	29.8	671.2 $\mu$ S
UNKNOWN	3	43.0	7.6 $\mu$ S
UNKNOWN	4	80.1	7.2 $\mu$ S
UNKNOWN	6	192.3	5.5 $\mu$ S
UNKNOWN	7	208.5	17.4 $\mu$ S
UNKNOWN	8	255.2	6.0 $\mu$ S

# PHOTOVAC

START 1

STOP 4 400.0

SAMPLE LIBRARY 1 APR 13 1994 9:37  
ANALYSIS # 4 MARK ESCOBAR  
INTERNAL TEMP 12 ROSLYN ANG  
GAIN 5 P2-01-A

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	19.7	19.7 $\mu$ S

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

MTBE	1	39.1	1.000 PPM
BENZENE	2	55.9	1.000 PPM
TOLUENE	3	106.8	1.000 PPM
ETHYLBEZENE	4	254.0	1.000 PPM
MP XYLENE	5	275.3	1.000 PPM
O XYLENE	6	329.9	1.000 PPM

# PHOTOVAC

START 1

2

3

4

STOP 4 450.0

SAMPLE LIBRARY 1 APR 13 1994 9:3  
ANALYSIS # 2 MARK ESCOBAR  
INTERNAL TEMP 10 ROSLYN ANG  
GAIN 5 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MP XYLENE	3	204.5	0.000 PPB

# PHOTOVAC

START 1 2

3

4

5

6

7

STOP 4 400.0

SAMPLE LIBRARY 1 APR 13 1994 9:45  
ANALYSIS # 5 MARK ESCOBAR  
INTERNAL TEMP 12 ROSLYN ANG  
GAIN 5 RECALIBRATE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	20.5	35.5 $\mu$ S
MTBE	2	28.5	454.2 PPB
BENZENE	3	40.1	629.3 PPB
TOLUENE	4	73.7	583.7 PPB
ETHYLBEZENE	6	187.3	2.710 PPM
MP XYLENE	7	230.5	212.0 PPB

# PHOTOVAC

START 1 2

3

4


5

STOP 4 400.0

SAMPLE LIBRARY 1 APR 13 1994 10:9  
ANALYSIS # 7 MARK ESCOBAR  
INTERNAL TEMP 13 ROSLYN ANG  
GAIN 5 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	12.0	15.3 $\mu$ S
UNKNOWN	2	27.3	31.8 $\mu$ S
MP XYLENE	5	299.3	0.499 PPB


# PHOTOVAC



STOP # 400.0  
 SAMPLE LIBRARY 1 APR 13 1994 10:10  
 ANALYSIS # 8 MARK ESCOBAR  
 INTERNAL TEMP 13 ROSLYN ANGOS  
 GAIN 5 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.9	17.8 $\mu$ S


# PHOTOVAC



STOP # 400.0  
 SAMPLE LIBRARY 1 APR 13 1994 14:25  
 ANALYSIS # 11 MARK ESCOBAR  
 INTERNAL TEMP 10 ROSLYN ANGOS  
 GAIN 5 P21-DRUM A

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	22.0	22.4 $\mu$ S


# PHOTOVAC



STOP # 400.0  
 SAMPLE LIBRARY 1 APR 13 1994 10:24  
 ANALYSIS # 9 MARK ESCOBAR  
 INTERNAL TEMP 14 ROSLYN ANGOS  
 GAIN 5 P2-01-B

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	23.8	15.4 $\mu$ S


# PHOTOVAC



STOP # 400.0  
 SAMPLE LIBRARY 1 APR 13 1994 14:34  
 ANALYSIS # 12 MARK ESCOBAR  
 INTERNAL TEMP 16 ROSLYN ANGOS  
 GAIN 5 P21-DRUM B

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	20.9	19.3 $\mu$ S


# PHOTOVAC



STOP # 400.0  
 SAMPLE LIBRARY 1 APR 13 1994 10:32  
 ANALYSIS # 10 MARK ESCOBAR  
 INTERNAL TEMP 14 ROSLYN ANGOS  
 GAIN 5 P2-01-C

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	23.3	55.8 $\mu$ S

# PHOTOVAC



STOP # 400.0  
 SAMPLE LIBRARY 1 APR 13 1994 14:41  
 ANALYSIS # 13 MARK ESCOBAR  
 INTERNAL TEMP 17 ROSLYN ANGOS  
 GAIN 5 P21-DRUM B

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	21.8	69.3 $\mu$ S


# PHOTOVAC

APR 14 1994 7:58

FIELD: 30  
POWER: 51

SAMPLE	0.0	10.0
CAL	0.0	0.0
EVENT 3	0.0	100.0
EVENT 4	0.0	0.0
EVENT 5	0.0	0.0
EVENT 6	0.0	0.0
EVENT 7	0.0	0.0
EVENT 8	0.0	0.0

# PHOTOVAC



STOP # 400.0  
SAMPLE LIBRARY 1 APR 14 1994 8:32  
ANALYSIS # 1 MARK ESCOBAR  
INTERNAL TEMP 14 ROSLYN ANGOS  
GAIN 5 STANDARD


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	22.5	182.9 μS
UNKNOWN	2	33.3	1.0 US
UNKNOWN	3	48.4	8.8 US
UNKNOWN	4	91.1	8.8 US
UNKNOWN	5	237.5	8.8 US
UNKNOWN	6	259.4	22.1 US
UNKNOWN	7	318.2	7.1 US

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

MTBE	1	33.3	1.000 PPM
BENZENE	2	48.4	1.000 PPM
TOLUENE	3	91.1	1.000 PPM
ETHYLBENZENE	4	237.5	1.000 PPM
MP XYLENE	5	259.4	1.000 PPM
O XYLENE	6	318.2	1.000 PPM


# PHOTOVAC



STOP # 400.0  
SAMPLE LIBRARY 1 APR 14 1994 8:44  
ANALYSIS # 2 MARK ESCOBAR  
INTERNAL TEMP 15 ROSLYN ANGOS  
GAIN 5 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	24.1	29.3 μS


# PHOTOVAC



STOP # 400.0  
SAMPLE LIBRARY 1 APR 14 1994 11:23  
ANALYSIS # 3 MARK ESCOBAR  
INTERNAL TEMP 18 ROSLYN ANGOS  
GAIN 5 P201-RETEST A

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	23.8	44.4 μS
MTBE	2	35.3	14.42 PPB


# PHOTOVAC



STOP # 400.0  
SAMPLE LIBRARY 1 APR 14 1994 11:01  
ANALYSIS # 4 MARK ESCOBAR  
INTERNAL TEMP 19 ROSLYN ANGOS  
GAIN 5 P201-RETEST B

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	24.2	118.7 μS
MTBE	2	35.1	51.87 PPB


# PHOTOVAC



STOP # 400.0  
SAMPLE LIBRARY 1 APR 14 1994 13:31  
ANALYSIS # 5 MARK ESCOBAR  
INTERNAL TEMP 18 ROSLYN ANGOS  
GAIN 5 P201-RETEST C

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	24.0	112.8 μS


# PHOTOVAC



STOP # 400.0  
SAMPLE LIBRARY 1 APR 14 1994 13:39  
ANALYSIS # 6 MARK ESCOBAR  
INTERNAL TEMP 19 ROSLYN ANGOS  
GAIN 5 P201-RETEST D

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	24.1	321.5 μS

# PHOTOVAC



STOP # 400.0  
SAMPLE LIBRARY 1 APR 14 1994 13:48  
ANALYSIS # 7 MARK ESCOBAR  
INTERNAL TEMP 19 ROSLYN ANGOS  
GAIN 5 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	23.7	342.1 μS
MTBE	2	35.2	748.7 PPB
BENZENE	3	51.0	787.5 PPB
TOLUENE	4	95.3	715.9 PPB
ETHYLBENZENE	5	245.3	757.1 PPB
MP XYLENE	6	267.5	683.5 PPB
O XYLENE	7	325.1	666.3 PPB

# PHOTOVAC

CALIBRATED PEAK 3,BENZENE

SAMPLE LIBRARY 1 APR 14 1994 13:50  
ANALYSIS # 7 MARK ESCOBAR  
INTERNAL TEMP 19 ROSLYN ANGUS  
GAIN 5 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	23.7	342.1 MUS
MTBE	2	35.2	940.5 PPB
BENZENE	3	51.0	1000. PPB
TOLUENE	4	55.3	503.0 PPB
ETHYLBENZENE	5	245.3	501.3 PPB
MP XYLENE	6	267.5	867.8 PPB
O XYLENE	7	325.1	846.1 PPB

# PHOTOVAC

START

# 2

STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 22 1994 12:58  
 ANALYSIS # 13 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG  
 GAIN 2 P2 01 C

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.8	2.8 US

# PHOTOVAC

START

STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 22 1994 13:5  
 ANALYSIS # 14 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG  
 GAIN 2 P2 01 D

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.8	2.3 US

# PHOTOVAC

START

STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 22 1994 13:13  
 ANALYSIS # 15 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG  
 GAIN 2 AIR BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.8	3.3 US

# PHOTOVAC

START

# 3  
 # 4  
 # 5  
 # 6  
 # 7

STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 22 1994 13:34  
 ANALYSIS # 16 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG  
 GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.7	4.8 US
MTBE	2	44.6	554.3 PPB
BENZENE	3	67.8	381.7 PPB
TOLUENE	4	132.1	481.6 PPB
MP XYLENE	5	261.8	235.4 PPB
OP XYLENE	6	281.8	523.8 PPB
P XYLENE	7	330.5	528.8 PPB

# PHOTOVAC

START


# 2  
 # 3  
 # 4  
 # 5  
 # 6

STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 22 1994 19:19  
 ANALYSIS # 17 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG  
 GAIN 2 FILE DIRT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.1	1.0 US
BENZENE	2	65.3	26.22 PPB
TOLUENE	3	127.1	27.16 PPB
ETHYLBENZENE	4	251.6	18.42 PPB
MP XYLENE	5	285.3	28.43 PPB
P XYLENE	6	317.9	5.688 PPB



# PHOTOVAC



STOP # 100.0  
SAMPLE LIBRARY 1 APR 22 1994 11:45  
ANALYSIS # 3 J BYRD JR  
INTERNAL TEMP 24 ROSLYN ANG  
GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.2	687.6 MWS
BENZENE	2	65.4	17.18 PPM
TOLUENE	3	127.3	68.51 PPM
ETHYLBENZENE	4	258.7	183.3 PPM
MP XYLENE	5	263.3	118.1 PPM
OP XYLENE	6	315.8	82.13 PPM


# PHOTOVAC

CALIBRATED PEAK 3,BENZENE

SAMPLE LIBRARY 1 APR 22 1994 11:49  
ANALYSIS # 3 J BYRD JR  
INTERNAL TEMP 23 ROSLYN ANG  
GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.2	687.6 MWS
BENZENE	2	65.4	17.18 PPM
TOLUENE	3	127.3	68.51 PPM
ETHYLBENZENE	4	258.7	183.3 PPM
MP XYLENE	5	263.3	118.1 PPM
OP XYLENE	6	315.8	82.13 PPM

# PHOTOVAC



APR 22 1994 11:58

FIELD: 30  
POWER: 25

SAMPLE	0.0	10.0
CAL	0.0	0.0
EVENT 3	0.0	100.0
EVENT 4	0.0	0.0
EVENT 5	0.0	0.0
EVENT 6	0.0	0.0
EVENT 7	0.0	0.0
EVENT 8	0.0	0.0



STOP # 100.0  
SAMPLE LIBRARY 1 APR 22 1994 11:59  
ANALYSIS # 10 J BYRD JR  
INTERNAL TEMP 24 ROSLYN ANG  
GAIN 2 AIR BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.2	687.6 MWS
BENZENE	2	65.4	17.18 PPM
TOLUENE	3	127.3	68.51 PPM
ETHYLBENZENE	4	258.7	183.3 PPM
MP XYLENE	5	263.3	118.1 PPM
OP XYLENE	6	315.8	82.13 PPM

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

1	COMPOUND	ID #	R.T.	LIMIT
1	MTBE		42.8	1.000 PPM
2	BENZENE		65.2	1.000 PPM
3	TOLUENE		126.1	1.000 PPM
4	ETHYLBENZENE		247.6	1.000 PPM
5	MP XYLENE		265.5	1.000 PPM
6	OP XYLENE		312.0	1.000 PPM

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT


1	COMPOUND	ID #	R.T.	LIMIT
1	MTBE		42.8	1.000 PPM
2	BENZENE		65.2	1.000 PPM
3	TOLUENE		126.1	1.000 PPM
4	ETHYLBENZENE		247.6	1.000 PPM
5	MP XYLENE		265.5	1.000 PPM
6	OP XYLENE		312.0	1.000 PPM

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

1	COMPOUND	ID #	R.T.	LIMIT
1	MTBE		42.8	1.000 PPM
2	BENZENE		65.2	1.000 PPM
3	TOLUENE		126.1	1.000 PPM
4	ETHYLBENZENE		247.6	1.000 PPM
5	MP XYLENE		265.5	1.000 PPM
6	OP XYLENE		312.0	1.000 PPM

# PHOTOVAC



STOP # 100.0  
SAMPLE LIBRARY 1 APR 22 1994 12:36  
ANALYSIS # 11 J BYRD JR  
INTERNAL TEMP 24 ROSLYN ANG  
GAIN 2 P2 81 A

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.8	225.1 MWS
TOLUENE	2	131.5	10.43 PPM
MP XYLENE	3	262.4	2.737 PPM
MP XYLENE	4	291.3	21.82 PPM

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

1	COMPOUND	ID #	R.T.	LIMIT
1	MTBE		42.8	1.000 PPM
2	BENZENE		65.2	1.000 PPM
3	TOLUENE		126.1	1.000 PPM
4	ETHYLBENZENE		247.6	1.000 PPM
5	MP XYLENE		265.5	1.000 PPM
6	OP XYLENE		312.0	1.000 PPM

STOP # 100.0  
SAMPLE LIBRARY 1 APR 22 1994 12:46  
ANALYSIS # 12 J BYRD JR  
INTERNAL TEMP 24 ROSLYN ANG  
GAIN 2 P2 81 A

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.9	3.8 US
TOLUENE	2	132.3	8.245 PPM
MP XYLENE	3	264.5	4.837 PPM
MP XYLENE	4	291.9	13.88 PPM

# PHOTOVAC

APR 23 1994 3:24

FIELD: 30  
POWER: 25

SAMPLE	0.0	10.0
CAL	0.0	0.0
EVENT 3	0.0	100.0
EVENT 4	0.0	0.0
EVENT 5	0.0	0.0
EVENT 6	0.0	0.0
EVENT 7	0.0	0.0
EVENT 8	0.0	0.0

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

NAME	1	45.7	1.000	PPM
BENZENE	2	65.7 <th>1.000</th> <th>PPM</th>	1.000	PPM
TOLUENE	3	134.5 <th>1.000</th> <th>PPM</th>	1.000	PPM
ETHYLBENZENE	4	262.7 <th>1.000</th> <th>PPM</th>	1.000	PPM
MP XYLENE	5	281.6 <th>1.000</th> <th>PPM</th>	1.000	PPM
OP XYLENE	6	330.5 <th>1.000</th> <th>PPM</th>	1.000	PPM

# PHOTOVAC

START


# 2  
# 3  
# 4  
# 5  
# 6

STOP @ 400.0  
SAMPLE LIBRARY 1 APR 23 1994 10:27  
ANALYSIS # 4 J BYRD JR  
INTERNAL TEMP 21 ROSLYN ANG  
GAIN 2 PILE DIRT C

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.2	501.1 mUS
TOLUENE	3	133.3	19.58 PPB
ETHYLBENZENE	4	260.3	23.27 PPB
MP XYLENE	5	279.6	37.36 PPB

# PHOTOVAC

START



STOP @ 400.0  
SAMPLE LIBRARY 1 APR 23 1994 3:53  
ANALYSIS # 1 J BYRD JR  
INTERNAL TEMP 20 ROSLYN ANG  
GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.6	2.8 US
UNKNOWN	2	48.1	372.1 mUS
UNKNOWN	3	73.7	2.5 US
UNKNOWN	4	141.9	1.7 US
UNKNOWN	5	278.3	1.0 US
UNKNOWN	6	298.4	2.2 US
UNKNOWN	7	350.6	661.8 mUS

# PHOTOVAC

CALIBRATED PEAK 3.BENZENE

SAMPLE LIBRARY 1 APR 23 1994 3:53  
ANALYSIS # 2 J BYRD JR  
INTERNAL TEMP 21 ROSLYN ANG  
GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.2	1.9 US
MTBE	2	45.7	1000. PPB
BENZENE	3	65.7	1000. PPB
TOLUENE	4	134.5	1000. PPB
ETHYLBENZENE	5	262.7	1.000 PPM
MP XYLENE	6	281.6	1.000 PPM
OP XYLENE	7	330.5	1000. PPB

# PHOTOVAC

START


# 2  
# 3  
# 4

STOP @ 400.0  
SAMPLE LIBRARY 1 APR 23 1994 10:38  
ANALYSIS # 5 J BYRD JR  
INTERNAL TEMP 21 ROSLYN ANG  
GAIN 2 PILE DIRT D

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.1	2.0 US
TOLUENE	2	132.3	4.313 PPB
MP XYLENE	4	278.3	15.57 PPB

# PHOTOVAC

START




STOP @ 400.0  
SAMPLE LIBRARY 1 APR 23 1994 10:1  
ANALYSIS # 3 J BYRD JR  
INTERNAL TEMP 21 ROSLYN ANG  
GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.4	1.2 US
MTBE	2	45.9	591.1 PPB
BENZENE	3	68.6	638.5 PPB
TOLUENE	4	134.5	732.5 PPB
ETHYLBENZENE	5	263.0	753.3 PPB
MP XYLENE	6	281.5	726.4 PPB
OP XYLENE	7	330.8	733.9 PPB

# PHOTOVAC

START



STOP @ 400.0  
SAMPLE LIBRARY 1 APR 23 1994 3:49  
ANALYSIS # 2 J BYRD JR  
INTERNAL TEMP 21 ROSLYN ANG  
GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.2	1.9 US
UNKNOWN	2	45.7	452.6 mUS
UNKNOWN	3	65.7	2.7 US
UNKNOWN	4	134.5	1.7 US
UNKNOWN	5	262.7	1.1 US
UNKNOWN	6	281.6	2.4 US
UNKNOWN	7	330.5	714.9 mUS

# PHOTOVAC


START

# 2  
# 3  
# 4


STOP @ 400.0  
SAMPLE LIBRARY 1 APR 23 1994 10:48  
ANALYSIS # 6 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG  
GAIN 2 PILE DIRT B

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.6	3.5 US
MP XYLENE	4	280.1	5.331 PPB


# PHOTOVAC




# PHOTOVAC




# PHOTOVAC




# PHOTOVAC




# PHOTOVAC




# PHOTOVAC




# PHOTOVAC



# PHOTOVAC



# PHOTOVAC



# PHOTOVAC

START

STOP # 400.0  
SAMPLE LIBRARY 1 APR 23 1994 14:51  
ANALYSIS # 15 J BYRD JR  
INTERNAL TEMP 24 ROSLYN ANG'S  
GAIN 2 P2-02 60

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	26.7	135.4 $\mu$ S


# PHOTOVAC

START

STOP # 400.0  
SAMPLE LIBRARY 1 APR 23 1994 15:34  
ANALYSIS # 16 J BYRD JR  
INTERNAL TEMP 25 ROSLYN ANG'S  
GAIN 2 P2-02 75

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	26.9	3.6 $\mu$ S


# PHOTOVAC



STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 25 1994 9:45  
 ANALYSIS # 1 J BYRD JR  
 INTERNAL TEMP 23 ROSLYN ANG5  
 GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.5	641.1 mUS
UNKNOWN	2	50.3	625.1 mUS
UNKNOWN	3	77.5	3.4 US
UNKNOWN	4	146.5	2.9 US
UNKNOWN	5	230.9	2.3 US
UNKNOWN	6	312.2	4.6 US


# PHOTOVAC



STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 25 1994 11:16  
 ANALYSIS # 3 J BYRD JR  
 INTERNAL TEMP 20 ROSLYN ANG5  
 GAIN 2 UEG OIL

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.0	144.3 mUS
TOLUENE	2	142.9	6.164 PPB
ETHYLBENZENE	3	281.9	14.56 PPB
MP XYLENE	4	302.6	24.45 PPB
UNKNOWN	5	355.4	7.3 mUS

# PHOTOVAC



STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 25 1994 14:23  
 ANALYSIS # 6 J BYRD JR  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 P2-82 100x

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	27.3	127.8 mUS
MP XYLENE	3	285.2	5.238 PPB


# PHOTOVAC

CALIBRATED PEAK 3, BENZENE

SAMPLE LIBRARY 1 APR 25 1994 9:49  
 ANALYSIS # 1 J BYRD JR  
 INTERNAL TEMP 23 ROSLYN ANG5  
 GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.5	641.1 mUS
MTBE	2	50.3	1.000 PPM
BENZENE	3	77.5	1.000 PPM
TOLUENE	4	146.5	1.000 PPM
ETHYLBENZENE	5	230.9	1.000 PPM
MP XYLENE	6	312.2	1.000 PPM


# PHOTOVAC



STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 25 1994 11:39  
 ANALYSIS # 5 J BYRD JR  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.7	3.5 US
MTBE	2	46.6	1.327 PPM
BENZENE	3	71.1	924.6 PPB
TOLUENE	4	137.5	752.1 PPB
ETHYLBENZENE	5	270.5	645.8 PPB
MP XYLENE	6	290.3	638.0 PPB
O XYLENE	7	341.0	777.6 PPB


# PHOTOVAC



STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 25 1994 10:18  
 ANALYSIS # 7 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.0	90.2 mUS
MTBE	2	44.7	791.0 PPB
BENZENE	3	68.2	919.5 PPB
TOLUENE	4	131.9	899.5 PPB
ETHYLBENZENE	5	258.5	758.8 PPB
MP XYLENE	6	277.1	725.4 PPB
O XYLENE	7	325.7	927.9 PPB

# PHOTOVAC



STOP @ 400.0  
 SAMPLE LIBRARY 1 APR 25 1994 9:58  
 ANALYSIS # 2 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 BTEX


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.7	2.7 US
MTBE	2	50.3	1.185 PPM
BENZENE	3	77.5	1.022 PPM
TOLUENE	4	146.7	881.2 PPB
ETHYLBENZENE	5	232.1	752.5 PPB
MP XYLENE	6	313.7	747.4 PPB

# PHOTOVAC

1 COMPOUND ID # R.T. LIMIT

MTBE	1	46.6	1.000 PPM
BENZENE	2	70.8	1.000 PPM
TOLUENE	3	135.7	1.000 PPM
ETHYLBENZENE	4	285.8	1.000 PPM
MP XYLENE	5	285.2	1.000 PPM
O XYLENE	6	335.8	1.000 PPM

# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.8	1.2 US
UNKNOWN	2	50.6	652.1 MUS
UNKNOWN	3	78.0	3.5 US
UNKNOWN	4	149.7	2.9 US
UNKNOWN	5	294.8	1.9 US
UNKNOWN	6	316.4	3.8 US

# PHOTOVAC

CALIBRATED PEAK 3, BENZENE  
SAMPLE LIBRARY 1 APR 26 1994 8:50  
ANALYSIS # 2 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG  
GAIN 2 CALIBRATION


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.7	2.6 US
MTBE	2	50.5	1000. PPB
BENZENE	3	77.8	1000. PPB
TOLUENE	4	149.7	1000. PPB
ETHYLBENZENE	5	295.1	1000. PPB
MP XYLENE	6	317.0	1.000 PPM
O XLENE	7	373.7	1.000 PPM

# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
---------------	------	------	----------

# PHOTOVAC




COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.8	1.4 US
MTBE	2	50.6	831.2 PPB
BENZENE	3	78.1	858.4 PPB
TOLUENE	4	150.1	840.1 PPB
ETHYLBENZENE	5	296.0	746.1 PPB
MP XYLENE	6	317.6	741.8 PPB
O XLENE	7	374.5	719.8 PPB

# PHOTOVAC



COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.1	48.1 MUS

# PHOTOVAC



COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.7	2.6 US
UNKNOWN	2	50.5	351.1 MUS
UNKNOWN	3	77.8	2.1 US
UNKNOWN	4	149.7	1.3 US
UNKNOWN	5	295.1	919.9 MUS
UNKNOWN	6	317.0	1.9 US
UNKNOWN	7	373.7	594.8 MUS

# PHOTOVAC


CALIBRATED PEAK 3, BENZENE  
SAMPLE LIBRARY 1 APR 26 1994 12:8  
ANALYSIS # 3 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG  
GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.8	1.4 US
MTBE	2	50.6	970.5 PPB
BENZENE	3	78.1	1.000 PPM
TOLUENE	4	150.1	380.9 PPB
ETHYLBENZENE	5	296.0	871.2 PPB
MP XYLENE	6	317.6	806.1 PPB
O XLENE	7	374.5	840.4 PPB

# PHOTOVAC


1	COMPOUND	ID #	R.T.	LIMIT
MTBE	1	50.5	1.000 PPM	
BENZENE	2	77.8	1.000 PPM	
TOLUENE	3	149.7	1.000 PPM	
ETHYLBENZENE	4	295.1	1.000 PPM	
MP XYLENE	5	317.0	1.000 PPM	
O XLENE	6	373.7	1.000 PPM	

# PHOTOVAC



COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.7	3.2 US
UNKNOWN	2	44.5	288.2 MUS
UNKNOWN	3	67.7	314.3 MUS
UNKNOWN	4	132.1	472.6 MUS
UNKNOWN	5	262.4	319.2 MUS

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 15:21  
 ANALYSIS # 9 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.2	830.6 μS
UNKNOWN	2	43.9	331.4 μS
UNKNOWN	3	66.6	1.8 US
UNKNOWN	4	128.9	1.3 US
UNKNOWN	5	257.3	874.0 μS
ETHYLBENZENE	6	276.2	2,321 PPM
MP XYLENE	7	324.8	373.9 PPM


# PHOTOVAC

CALIBRATED PEAK 3, BENZENE

SAMPLE LIBRARY 1 APR 26 1994 15:23  
 ANALYSIS # 9 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.2	830.6 μS
MTBE	2	43.9	1.072 PPM
BENZENE	3	66.6	1000. PPM
TOLUENE	4	128.9	1.166 PPM
ETHYLBENZENE	5	257.3	1.073 PPM
MP XYLENE	6	276.2	1.066 PPM
O XLENE	7	324.8	1.163 PPM


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 15:43  
 ANALYSIS # 11 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 PZ-03 60

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.7	2.6 US
TOLUENE	2	131.3	6.581 PPM
MP XYLENE	4	282.8	4.127 PPM


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 15:32  
 ANALYSIS # 10 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.5	2.4 US
BENZENE	2	66.8	16.12 PPM
TOLUENE	3	138.3	37.17 PPM
ETHYLBENZENE	4	259.1	27.39 PPM
MP XYLENE	5	278.0	44.66 PPM
O XLENE	6	326.9	9.717 PPM


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 17:33  
 ANALYSIS # 1 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.7	5.7 mUS
UNKNOWN	2	47.1	435.7 mUS
UNKNOWN	3	72.3	2.5 US
UNKNOWN	4	139.7	2.1 US
UNKNOWN	5	275.3	1.4 US
UNKNOWN	6	295.4	2.9 US
UNKNOWN	7	347.8	874.5 mUS


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 1000  
 ANALYSIS # 3 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.5	782.8 mUS
MTBE	2	46.2	1.349 PPM
BENZENE	3	70.6	1.328 PPM
TOLUENE	4	130.5	1.584 PPM
ETHYLBENZENE	5	268.7	1.070 PPM
MP XYLENE	6	288.2	1.622 PPM
O XYLENE	7	338.6	1.561 PPM


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 1208  
 ANALYSIS # 5 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 P2-03 105

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.3	49.3 mUS
ETHYLBENZENE	2	255.5	7.667 PPM
ETHYLBENZENE	3	272.6	9.005 PPM


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 0928  
 ANALYSIS # 2 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.4	301.5 mUS
UNKNOWN	2	46.0	318.4 mUS
UNKNOWN	3	70.2	1.8 US
UNKNOWN	4	135.9	1.2 US
UNKNOWN	5	267.2	840.3 mUS
UNKNOWN	6	286.7	1.7 US
UNKNOWN	7	336.8	548.0 mUS


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 1118  
 ANALYSIS # 4 J BYRD JR  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
TOLUENE	2	137.1	13.23 PPM
ETHYLBENZENE	3	270.2	30.02 PPM
MP XYLENE	4	290.3	50.14 PPM
O XYLENE	5	341.0	10.81 PPM

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 APR 26 1994 1120  
 ANALYSIS # 6 J BYRD JR  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 AIR BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	28.5	1.1 US

# PHOTOVAC

CALIBRATED PEAK 3, BENZENE  
 SAMPLE LIBRARY 1 APR 26 1994 0949  
 ANALYSIS # 2 J BYRD JR  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 CALIBRATION

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	29.4	301.5 mUS
MTBE	2	46.0	1.000 PPM
BENZENE	3	70.2	1.000 PPM
TOLUENE	4	135.9	1000. PPM
ETHYLBENZENE	5	267.2	1.000 PPM
MP XYLENE	6	286.7	1.000 PPM
O XYLENE	7	336.8	1.000 PPM



# PHOTOVAC


START

STOP # 450.0  
 SAMPLE LIBRARY 1 APR 27 1994 15:41  
 ANALYSIS # 7 J BYRD JR  
 INTERNAL TEMP 27 ROSLYN ANG5  
 GAIN 2 P2-03 155

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	26.7	66.6 mUS

# PHOTOVAC


START



STOP # 450.0  
 SAMPLE LIBRARY 1 APR 27 1994 15:50  
 ANALYSIS # 8 J BYRD JR  
 INTERNAL TEMP 27 ROSLYN ANG5  
 GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	27.8	996.6 mUS
MTBE	2	42.9	1.170 PPM
BENZENE	3	65.0	982.0 PPB
TOLUENE	4	126.1	929.8 PPB
ETHYLBENZENE	5	246.5	846.6 PPB
ETHYLBENZENE	6	264.5	1.602 PPM
MP XYLENE	7	318.4	261.6 PPB


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 2 1994 13:26  
 ANALYSIS # 4 M HENSON  
 INTERNAL TEMP 23 ROSLYN ANG5  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.3	50.8 µS
UNKNOWN	3	50.5	485.3 µS
UNKNOWN	4	77.6	514.9 µS
UNKNOWN	5	143.7	231.1 µS
UNKNOWN	6	296.3	74.6 µS
ETHYLBENZENE	7	318.2	695.6 PPB
MP XYLENE	8	374.3	104.0 PPB


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 2 1994 13:43  
 ANALYSIS # 5 M HENSON  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 MW-01.0FT BLS

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.2	629.4 µS
UNKNOWN	2	37.2	1.0 µS

# PHOTOVAC




STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 2 1994 16:17  
 ANALYSIS # 7 M HENSON  
 INTERNAL TEMP 23 ROSLYN ANG5  
 GAIN 2 MW-01.75FT BLS

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.3	81.3 µS
UNKNOWN	2	39.2	113.7 µS

# PHOTOVAC

1	COMPOUND	ID #	R.T.	LIMIT
MTBE	1	59.7	1.000 PPM	
BENZENE	2	91.1	1.000 PPM	
TOLUENE	3	176.2	1.000 PPM	
ETHYLBENZENE	4	346.5	1.000 PPM	
MP XYLENE	5	371.3	2.000 PPM	
O XYLENE	6	430.8	1.000 PPM	

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 2 1994 14:50  
 ANALYSIS # 6 M HENSON  
 INTERNAL TEMP 23 ROSLYN ANG5  
 GAIN 2 MW-01.45FT BLS

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.9	56.5 µS
UNKNOWN	2	37.0	177.0 µS


# PHOTOVAC

CALIBRATED PEAK 4, BENZENE

SAMPLE LIBRARY 1 MAY 2 1994 13:28  
 ANALYSIS # 4 M HENSON  
 INTERNAL TEMP 23 ROSLYN ANG5  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.3	50.8 µS
MTBE	3	50.5	5.483 PPM
BENZENE	4	77.5	1.000 PPM
TOLUENE	5	143.7	830.9 PPB
ETHYLBENZENE	6	296.3	316.3 PPB
MP XYLENE	7	318.2	400.3 PPB
O XYLENE	8	374.3	326.1 PPB


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 2 1994 16:27  
 ANALYSIS # 8 M HENSON  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 AIR BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.5	7.5 µS

# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 MAY 3 1994 10:21  
 ANALYSIS # 2 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 5 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.2	6.2 US
UNKNOWN	2	79.4	1.9 US
UNKNOWN	3	105.9	3.4 mUS
UNKNOWN	4	153.3	1.3 US
UNKNOWN	5	304.7	1.2 US
UNKNOWN	6	327.2	2.3 US
UNKNOWN	7	385.7	325.3 mUS


# PHOTOVAC

CALIBRATED PEAK 2, BENZENE

SAMPLE LIBRARY 1 MAY 3 1994 10:25  
 ANALYSIS # 2 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 5 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	32.2	1.000 PPM
BENZENE	2	79.4	1.000 PPM
UNKNOWN	3	105.9	9.4 mUS
TOLUENE	4	153.3	1000. PPM
ETHYLBENZENE	5	304.7	1000. PPM
MP XYLENE	6	327.2	2.000 PPM
OP XYLENE	7	385.7	1000. PPM


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 MAY 3 1994 13:0  
 ANALYSIS # 3 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 5 MW-01 100FT BLS

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	31.7	19.25 PPM
UNKNOWN	2	110.5	23.7 mUS
MP XYLENE	5	326.9	19.99 PPM


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 MAY 3 1994 13:23  
 ANALYSIS # 4 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 5 MW-01 100FT BLS

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	2	30.3	161.0 PPM
UNKNOWN	3	37.7	130.3 mUS
UNKNOWN	4	106.3	11.2 mUS


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 MAY 3 1994 16:10  
 ANALYSIS # 5 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 5 MW-01 100FT BLS

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	13.6	13.5 mUS
MTBE	2	32.8	516.7 PPM
UNKNOWN	3	108.1	16.9 mUS


# PHOTOVAC



STOP # 450.0  
 SAMPLE LIBRARY 1 MAY 3 1994 16:39  
 ANALYSIS # 6 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 5 AIR BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	2	31.3	141.1 PPM
UNKNOWN	3	37.9	335.0 mUS
UNKNOWN	4	105.6	7.3 mUS

PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 4 1994 9:13  
 ANALYSIS # 3 M HENSON  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	34.5	97.9 mUS
UNKNOWN	2	40.8	12.4 mUS
UNKNOWN	3	86.8	4.8 US
UNKNOWN	4	163.3	4.0 US
UNKNOWN	5	322.4	3.1 US
UNKNOWN	6	345.8	7.0 US
UNKNOWN	7	402.3	2.7 US


PHOTOVAC

CALIBRATED PEAK 3,BENZENE

SAMPLE LIBRARY 1 MAY 4 1994 9:17  
 ANALYSIS # 3 M HENSON  
 INTERNAL TEMP 24 ROSLYN ANG5  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	34.5	97.9 mUS
MTBE	2	40.8	1000. PPS
BENZENE	3	86.8	1.000 PPM
TOLUENE	4	163.3	1000. PPS
ETHYLBENZENE	5	322.4	1000. PPS
MP XYLENE	6	345.8	2.000 PPM
O XYLENE	7	402.3	1.000 PPM

PHOTOVAC




STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 4 1994 11:14  
 ANALYSIS # 4 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 01-001M 155FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.4	100.5 mUS

# PHOTOVAC

1	COMPOUND	ID #	R.T.	LIMIT
MTBE	1	40.8	1.000 PPM	
BENZENE	2	86.8	1.000 PPM	
TOLUENE	3	163.3	1.000 PPM	
ETHYLBENZENE	4	322.4	1.000 PPM	
MP XYLENE	5	345.8	2.000 PPM	
OP XYLENE	6	407.3	1.000 PPM	

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 8:58  
 ANALYSIS # 1 M HENSON  
 INTERNAL TEMP 22 ROSLYN ANG5  
 GAIN 2

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.4	182.4 mUS
UNKNOWN	3	81.3	6.4 US
UNKNOWN	4	156.7	4.8 US
UNKNOWN	5	308.3	5.0 US
UNKNOWN	6	332.0	9.0 US


# PHOTOVAC

CALIBRATED PEAK 3, BENZENE

SAMPLE LIBRARY 1 MAY 9 1994 3:8  
 ANALYSIS # 1 M HENSON  
 INTERNAL TEMP 23 ROSLYN ANG5  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.4	182.4 mUS
BENZENE	3	81.3	1.000 PPM
TOLUENE	4	156.7	1.000 PPM
ETHYLBENZENE	5	308.3	1.000 PPM
MP XYLENE	6	332.0	2.000 PPM


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 12:4  
 ANALYSIS # 2 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.5	3.3 US


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 12:43  
 ANALYSIS # 3 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 03-001MU 35FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.5	611.0 mUS

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 14:19  
 ANALYSIS # 4 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.2	1.7 US
UNKNOWN	2	79.2	5.3 US
UNKNOWN	3	152.7	4.4 US
UNKNOWN	4	302.3	4.3 US
UNKNOWN	5	325.1	8.0 US
UNKNOWN	6	383.7	3.6 US


# PHOTOVAC

CALIBRATED PEAK 2, BENZENE

SAMPLE LIBRARY 1 MAY 9 1994 14:21  
 ANALYSIS # 4 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	32.2	1.000 PPM
BENZENE	2	79.2	1.000 PPM
TOLUENE	3	152.7	1.000 PPM
ETHYLBENZENE	4	302.3	1.000 PPM
MP XYLENE	5	325.1	2.000 PPM
OP XYLENE	6	383.7	1.000 PPM

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 14:30  
 ANALYSIS # 5 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 03-001MU 35FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	32.2	26.20 PPM
UNKNOWN	2	40.0	15.5 mUS

PHOTOVAC

START

STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 15:33  
 ANALYSIS # 6 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 03-001MW

COMPOUND NAME PEAK R.T. AREA/PPM  
 MTBE 1 34.5 11.31 PPM

PHOTOVAC

START

STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 15:48  
 ANALYSIS # 7 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 03-001MW 80FT

COMPOUND NAME PEAK R.T. AREA/PPM  
 MTBE 1 31.7 51.13 PPB  
 UNKNOWN 2 37.5 47.3 mUS  
 UNKNOWN 3 269.6 9.3 mUS

PHOTOVAC

START

STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 16:21  
 ANALYSIS # 8 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 03-001MW 100FT

COMPOUND NAME PEAK R.T. AREA/PPM  
 MTBE 1 33.3 23.58 PPB  
 UNKNOWN 2 37.3 23.3 mUS

PHOTOVAC

START

STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 9 1994 16:29  
 ANALYSIS # 9 M HENSON  
 INTERNAL TEMP 26 ROSLYN ANG5  
 GAIN 2 AIR BLANK

COMPOUND NAME PEAK R.T. AREA/PPM  
 MTBE 1 31.8 12.59 PPB  
 UNKNOWN 2 38.2 58.2 mUS

# PHOTOVAC


1	COMPOUND	ID #	R.T.	LIMIT
NTBE	1	32.2	1.000 PPM	
BENZENE	2	73.2	1.000 PPM	
TOLUENE	3	152.7	1.000 PPM	
ETHYLBENZENE	4	302.5	1.000 PPM	
MP XYLENE	5	325.1	2.000 PPM	
O XYLENE	6	363.7	1.000 PPM	

# PHOTOVAC


CALIBRATED PEAK 2, BENZENE  
 SAMPLE LIBRARY 1 MAY 10 1994 10:48  
 ANALYSIS # 2 M HENSON  
 INTERNAL TEMP 23 ROSLYN ANG8  
 GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
NTBE	1	34.5	1000. PPB
BENZENE	2	66.2	1000. PPB
TOLUENE	3	162.1	1.000 PPM
ETHYLBENZENE	4	318.8	1000. PPB
MP XYLENE	5	342.2	2.000 PPM
O XYLENE	6	404.1	1000. PPB


# PHOTOVAC




# PHOTOVAC




# PHOTOVAC



# PHOTOVAC



# PHOTOVAC



STOP @ 500.0  
 SAMPLE LIBRARY 1 MAY 11 1994 15:20  
 ANALYSIS # 1 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	31.6	540.8 PPS
MTBE	2	37.6	423.8 PPS
BENZENE	3	73.4	271.2 PPS
TOLUENE	4	152.3	179.6 PPS
ETHYLBENZENE	5	304.1	852.3 PPS
ETHYLBENZENE	6	326.2	1.884 PPM
O XYLENE	7	384.3	553.1 PPS


# PHOTOVAC

CALIBRATED PEAK 3,BENZENE

SAMPLE LIBRARY 1 MAY 11 1994 15:25  
 ANALYSIS # 1 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.6	55.0 WUS
MTBE	2	37.6	1.000 PPM
BENZENE	3	73.4	1.000 PPM
TOLUENE	4	152.3	1.000 PPM
ETHYLBENZENE	5	304.1	1.000 PPM
MP XYLENE	6	326.2	2.000 PPM
O XYLENE	7	384.3	1.000 PPS


# PHOTOVAC



STOP @ 500.0  
 SAMPLE LIBRARY 1 MAY 11 1994 16:17  
 ANALYSIS # 2 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 02-001M 30FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.5	103.7 WUS

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 MAY 11 1994 16:48  
 ANALYSIS # 3 M HENSON  
 INTERNAL TEMP 25 ROSLYN ANG5  
 GAIN 2 02-001M 50FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.5	3.4 WUS



# PHOTOVAC

MAY 12 1994 8:32

FIELD: 30  
POWER: 25

SAMPLE	8.0	10.0
CAL	0.0	0.0
EVENT 3	0.0	100.0
EVENT 4	0.0	0.0
EVENT 5	0.0	0.0
EVENT 6	0.0	0.0
EVENT 7	0.0	0.0
EVENT 8	0.0	0.0

# PHOTOVAC

CALIBRATED PEAK 2, BENZENE

SAMPLE LIBRARY 1 MAY 12 1994 8:46  
ANALYSIS # 1 M HENSON  
INTERNAL TEMP 23 ROSLYN ANG'S  
GAIN 2 1 PPM BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	35.7	1.000 PPM
BENZENE	2	36.5	1.000 PPM
TOLUENE	3	162.9	1.000 PPM
ETHYLBENZENE	4	321.8	1.000 PPM
PP XYLENE	5	345.2	2.000 PPM


# PHOTOVAC

START

STOP # 450.0  
SAMPLE LIBRARY 1 MAY 12 1994 13: 5  
ANALYSIS # 4 E PARKER  
INTERNAL TEMP 26 ROSLYN ANG'S  
GAIN 2 02-001MW 130FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	32.8	23.22 PPM

# PHOTOVAC



STOP # 450.0  
SAMPLE LIBRARY 1 MAY 12 1994 8:42  
ANALYSIS # 1 M HENSON  
INTERNAL TEMP 23 ROSLYN ANG'S  
GAIN 2 02-001MW 85FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	35.7	11.7 US
UNKNOWN	2	36.5	6.8 US
UNKNOWN	3	162.9	5.1 US
UNKNOWN	4	321.8	5.1 US
UNKNOWN	5	345.2	11.6 US

# PHOTOVAC

START

STOP # 450.0  
SAMPLE LIBRARY 1 MAY 12 1994 10:22  
ANALYSIS # 2 M HENSON  
INTERNAL TEMP 25 ROSLYN ANG'S  
GAIN 2 02-001MW 85FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	32.3	83.7 MUS

# PHOTOVAC

START

STOP # 450.0  
SAMPLE LIBRARY 1 MAY 12 1994 13:15  
ANALYSIS # 5 E PARKER  
INTERNAL TEMP 26 ROSLYN ANG'S  
GAIN 2 AIR BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	32.7	26.42 PPM

# PHOTOVAC

START

STOP # 450.0  
SAMPLE LIBRARY 1 MAY 12 1994 11: 8  
ANALYSIS # 3 M HENSON  
INTERNAL TEMP 25 ROSLYN ANG'S  
GAIN 2 02-001MW 100FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	34.5	234.7 PPM

# PHOTOVAC

CALIBRATED PEAK 2, BENZENE

SAMPLE LIBRARY 1 MAY 12 1994 8:44  
ANALYSIS # 1 M HENSON  
INTERNAL TEMP 23 ROSLYN ANG'S  
GAIN 2 02-001MW 100FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	35.7	1.000 PPM
BENZENE	2	36.5	1.000 PPM
TOLUENE	3	162.9	1.000 PPM
ETHYLBENZENE	4	321.8	1.000 PPM
PP XYLENE	5	345.2	2.000 PPM


# PHOTOVAC

START

STOP # 450.0  
SAMPLE LIBRARY 1 MAY 12 1994 14:01  
ANALYSIS # 6 E PARKER  
INTERNAL TEMP 26 ROSLYN ANG'S  
GAIN 2 02-001MW 145FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.7	153.1 MUS


# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 DAY 12 1994 16:21  
 ANALYSIS # 7 E PARKER  
 INTERNAL TEMP 26 ROSLYN ANG  
 GAIN 2 02-001NW 155FT

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	32.8	2.213 PPS
UNKNOWN	2	41.3	23.8 MVS

# PHOTOVAC



STOP @ 450.0  
 SAMPLE LIBRARY 1 DAY 12 1994 17:28  
 ANALYSIS # 8 E PARKER  
 INTERNAL TEMP 26 ROSLYN ANG  
 GAIN 2 02-001NW AQUIFER

COMPOUND NAME	PEAK	R.T.	AREA/PPM
MTBE	1	35.7	21.62 PPS
UNKNOWN	2	43.4	27.3 MVS


# PHOTOVAC

MAY 17 1994 8:24

FIELD: 38  
POWER: 25

SAMPLE	0.0	10.0
CAL	0.0	0.0
EVENT 3	0.0	100.0
EVENT 4	0.0	0.0
EVENT 5	0.0	0.0
EVENT 6	0.0	0.0
EVENT 7	0.0	0.0
EVENT 8	0.0	0.0

# PHOTOVAC



STOP @ 450.3  
SAMPLE LIBRARY 1 MAY 17 1994 8:49  
ANALYSIS # 1 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG8  
GAIN 2 BTEX

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.3	118.1 μS
UNKNOWN	2	74.2	4.0 US
UNKNOWN	3	140.1	3.4 US
UNKNOWN	4	271.1	3.3 US
UNKNOWN	5	290.9	7.4 US
UNKNOWN	6	341.0	3.7 US

# PHOTOVAC

1	COMPOUND	ID #	R.T.	LIMIT
BENZENE	1	74.2	1.000 PPM	
TOLUENE	2	140.1	1.000 PPM	
ETHYLBENZENE	3	271.1	1.000 PPM	
MP-XYLENE	4	290.9	1.000 PPM	
O-XYLENE	5	341.0	1.000 PPM	
MP XYLENE	6	290.9	1.000 PPM	

# PHOTOVAC

CALIBRATED PEAK 2,TOLUENE

SAMPLE LIBRARY 1 MAY 17 1994 8:59  
ANALYSIS # 1 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG8  
GAIN 2 BTEX

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.3	118.1 μS
TOLUENE	2	74.2	1.000 PPM
ETHYLBENZENE	3	140.1	887.6 PPM
UNKNOWN	4	271.1	3.3 US
UNKNOWN	5	290.9	7.4 US
UNKNOWN	6	341.0	3.7 US


# PHOTOVAC

CALIBRATED PEAK 2,BENZENE

SAMPLE LIBRARY 1 MAY 17 1994 9:1  
ANALYSIS # 1 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG8  
GAIN 2 BTEX

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.3	118.1 μS
BENZENE	2	74.2	1000. PB
TOLUENE	3	140.1	1000. PPM
ETHYLBENZENE	4	271.1	1000. PPM
MP-XYLENE	5	290.9	1000. PPM
O-XYLENE	6	341.0	1000. PPM


# PHOTOVAC



STOP @ 450.3  
SAMPLE LIBRARY 1 MAY 17 1994 9:11  
ANALYSIS # 2 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG8  
GAIN 2 MW-301

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.3	351.3 μS


# PHOTOVAC



STOP @ 450.3  
SAMPLE LIBRARY 1 MAY 17 1994 9:21  
ANALYSIS # 3 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG8  
GAIN 2 MW-002

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.3	1.6 US
ETHYLBENZENE	2	249.8	12.00 PPM


# PHOTOVAC



STOP @ 450.3  
SAMPLE LIBRARY 1 MAY 17 1994 9:31  
ANALYSIS # 4 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG8  
GAIN 2 MW-003

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	30.3	143.3 μS

# PHOTOVAC



STOP @ 450.3  
SAMPLE LIBRARY 1 MAY 17 1994 9:41  
ANALYSIS # 5 J BYRD JR  
INTERNAL TEMP 22 ROSLYN ANG8  
GAIN 2 BTEX STD

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	31.7	128.4 μS
BENZENE	2	77.2	350.7 PPM
TOLUENE	3	145.1	1.046 PPM
ETHYLBENZENE	4	269.1	1.001 PPM
MP-XYLENE	5	290.2	1.005 PPM
O-XYLENE	6	351.9	1.041 PPM

**APPENDIX E**

**AQUIFER SLUG TEST DATA**

**THIS PAGE INTENTIONALLY LEFT BLANK**

## SECTION E.1 INTRODUCTION

Three rising head slug tests were conducted to investigate the hydraulic properties of the Upper Glacial Aquifer underlying the Roslyn ANGWS at Roslyn, New York. The slug test method is a technique used to calculate values of transmissivity (T). In the rising head slug method conducted at monitoring wells installed at the Station, a decontaminated acrylic slug, 2.5" in diameter and 32" in length, was lowered into the water column until completely submerged and the maximum displacement of water had occurred. After the water level rose in response to the slug, the water level in the well was monitored until it returned to the initial static level. The slug was removed from the well after the pre-displacement water level had been reached. The water level initially dropped as the slug was being removed from the water, and then rose back toward the initial static level in the well. The rise in water level was then measured at closely spaced time intervals. A pressure transducer and automatic recorder were used to collect data during testing.

Transmissivities were computed from slug test data using a software program known as STEP-MATCH which has been developed to automate the process of analyzing data from slug tests.

The raw data for each slug test and the curves generated by STEP-MATCH are included in this section.

**THIS PAGE INTENTIONALLY LEFT BLANK**

01-001 MW

SE1000C  
Environmental Logger  
05/17 14:27

Unit# 00601 Test 2

INPUT 1: Level (F) TOC

Reference 100.000  
Linearity 0.030  
Scale factor 20.090  
Offset 0.060  
Delay mSEC 50.000

Step 0 05/17 14:17:15

Elapsed Time INPUT 1

0.0000	100.057
0.0033	100.070
0.0066	101.077
0.0100	100.387
0.0133	101.223
0.0166	100.957
0.0200	100.919
0.0233	100.881
0.0266	100.767
0.0300	100.773
0.0333	100.729
0.0366	100.691
0.0400	100.697
0.0433	100.646
0.0466	100.627
0.0500	100.627
0.0533	100.583
0.0566	100.570
0.0600	100.564
0.0633	100.532
0.0666	100.526
0.0700	100.507
0.0733	100.494
0.0766	100.482
0.0800	100.463
0.0833	100.450
0.0866	100.444
0.0900	100.431
0.0933	100.418
0.0966	100.412
0.1000	100.393
0.1033	100.387
0.1066	100.380
0.1100	100.368
0.1133	100.355
0.1166	100.349
0.1200	100.342
0.1233	100.336
0.1266	100.323
0.1300	100.317
0.1333	100.311
0.1366	100.304
0.1400	100.298
0.1433	100.292
0.1466	100.285
0.1500	100.279
0.1533	100.273
0.1566	100.266
0.1600	100.260
0.1633	100.254
0.1666	100.254
0.1700	100.247
0.1733	100.241
0.1766	100.234
0.1800	100.228
0.1833	100.222
0.1866	100.222
0.1900	100.215

0.1933	100.215
0.1966	100.209
0.2000	100.209
0.2033	100.203
0.2066	100.196
0.2100	100.196
0.2133	100.190
0.2166	100.190
0.2200	100.184
0.2233	100.184
0.2266	100.184
0.2300	100.177
0.2333	100.171
0.2366	100.171
0.2400	100.171
0.2433	100.165
0.2466	100.165
0.2500	100.165
0.2533	100.158
0.2566	100.158
0.2600	100.152
0.2633	100.152
0.2666	100.152
0.2700	100.146
0.2733	100.146
0.2766	100.146
0.2800	100.146
0.2833	100.139
0.2866	100.139
0.2900	100.139
0.2933	100.133
0.2966	100.133
0.3000	100.133
0.3033	100.127
0.3066	100.127
0.3100	100.127
0.3133	100.127
0.3166	100.127
0.3200	100.120
0.3233	100.120
0.3266	100.120
0.3300	100.120
0.3333	100.120
0.3366	100.108
0.3400	100.101
0.3433	100.101
0.3466	100.101
0.3500	100.095
0.3533	100.095
0.3566	100.095
0.3600	100.089
0.3633	100.082
0.3666	100.082
0.3700	100.082
0.3733	100.076
0.3766	100.076
0.3800	100.076
0.3833	100.076
0.3866	100.076
0.3900	100.070
0.3933	100.070
0.3966	100.070
0.4000	100.070
0.4033	100.063
0.4066	100.063
0.4100	100.063
0.4133	100.063
0.4166	100.063
0.4200	100.063
0.4233	100.063
0.4266	100.063
0.4300	100.063
0.4333	100.063
0.4366	100.063
0.4400	100.063
0.4433	100.063
0.4466	100.063
0.4500	100.063
0.4533	100.063
0.4566	100.063
0.4600	100.063
0.4633	100.063
0.4666	100.063
0.4700	100.063
0.4733	100.063
0.4766	100.063
0.4800	100.063
0.4833	100.063
0.4866	100.063
0.4900	100.063
0.4933	100.063
0.4966	100.063
0.5000	100.063


0.9500	100.057
0.9666	100.063
0.9833	100.057
1.0000	100.057
1.2000	100.057
1.4000	100.057
1.6000	100.057
1.8000	100.057
2.0000	100.057
2.2000	100.057
2.4000	100.057
2.6000	100.057
2.8000	100.057
3.0000	100.057
3.2000	100.051
3.4000	100.051
3.6000	100.051
3.8000	100.057
4.0000	100.057
4.2000	100.057
4.4000	100.051
4.6000	100.057
4.8000	100.057
5.0000	100.057
5.2000	100.051
5.4000	100.057
5.6000	100.051
5.8000	100.051
6.0000	100.057
6.2000	100.057
6.4000	100.051
6.6000	100.057
6.8000	100.057
7.0000	100.057
7.2000	100.057
7.4000	100.057
7.6000	100.057
7.8000	100.057
8.0000	100.057
8.2000	100.057
8.4000	100.051
8.6000	100.051
8.8000	100.051
9.0000	100.057
9.2000	100.057
9.4000	100.057
9.6000	100.057
9.8000	100.057
10.0000	100.057

END



# Slug Test on Monitoring Well 01-001MW

STEP (Slug) Test Automated Type-Curve Match (V1.2)



SE1000C  
Environmental Logger  
05/17 15:44  
02-001 MW  
Unit# 00601 Test 4

INPUT 1: Level (F) TOC

Reference 100.000  
Linearity 0.030  
Scale factor 20.090  
Offset 0.060  
Delay mSEC 50.000

Step 0 05/17 15:33:56

Elapsed Time INPUT 1

0.0000	100.146
0.0033	100.805
0.0066	101.166
0.0100	101.299
0.0133	100.964
0.0166	99.448
0.0200	101.033
0.0233	100.888
0.0266	100.780
0.0300	100.666
0.0333	100.653
0.0366	100.666
0.0400	100.571
0.0433	100.571
0.0466	100.558
0.0500	100.513
0.0533	100.488
0.0566	100.463
0.0600	100.437
0.0633	100.425
0.0666	100.412
0.0700	100.399
0.0733	100.380
0.0766	100.361
0.0800	100.349
0.0833	100.330
0.0866	100.317
0.0900	100.311
0.0933	100.298
0.0966	100.292
0.1000	100.285
0.1033	100.273
0.1066	100.266
0.1100	100.254
0.1133	100.247
0.1166	100.228
0.1200	100.222
0.1233	100.216
0.1266	100.209
0.1300	100.203
0.1333	100.203
0.1366	100.197
0.1400	100.190
0.1433	100.190
0.1466	100.184
0.1500	100.178
0.1533	100.171
0.1566	100.165
0.1600	100.159
0.1633	100.152
0.1666	100.152
0.1700	100.152
0.1733	100.146
0.1766	100.140
0.1800	100.140
0.1833	100.133
0.1866	100.133
0.1900	100.127
0.1933	100.127
0.1966	100.127
0.2000	100.120


0.2033	100.120
0.2066	100.114
0.2100	100.114
0.2133	100.108
0.2166	100.108
0.2200	100.108
0.2233	100.101
0.2266	100.101
0.2300	100.095
0.2333	100.101
0.2366	100.101
0.2400	100.095
0.2433	100.095
0.2466	100.095
0.2500	100.089
0.2533	100.089
0.2566	100.089
0.2600	100.089
0.2633	100.082
0.2666	100.082
0.2700	100.082
0.2733	100.076
0.2766	100.076
0.2800	100.076
0.2833	100.076
0.2866	100.076
0.2900	100.076
0.2933	100.070
0.2966	100.070
0.3000	100.070
0.3033	100.070
0.3066	100.063
0.3100	100.063
0.3133	100.063
0.3166	100.063
0.3200	100.063
0.3233	100.057
0.3266	100.057
0.3300	100.057
0.3333	100.051
0.3366	100.051
0.3400	100.044
0.3433	100.044
0.3466	100.038
0.3500	100.038
0.3533	100.032
0.3566	100.032
0.3600	100.032
0.3633	100.025
0.3666	100.025
0.3700	100.025
0.3733	100.019
0.3766	100.019
0.3800	100.019
0.3833	100.013
0.3866	100.013
0.3900	100.013
0.3933	100.013
0.3966	100.013
0.4000	100.013
0.4033	100.013
0.4066	100.013
0.4100	100.013
0.4133	100.013
0.4166	100.013
0.4200	100.013
0.4233	100.013
0.4266	100.013
0.4300	100.013
0.4333	100.013
0.4366	100.013
0.4400	100.013
0.4433	100.013
0.4466	100.013
0.4500	100.013
0.4533	100.013
0.4566	100.013
0.4600	100.013
0.4633	100.013
0.4666	100.013
0.4700	100.013
0.4733	100.013
0.4766	100.013
0.4800	100.013
0.4833	100.013
0.4866	100.013
0.4900	100.013
0.4933	100.013
0.4966	100.013
0.5000	100.013
0.5033	100.013
0.5066	100.013
0.5100	100.013
0.5133	100.013
0.5166	100.013
0.5200	100.013
0.5233	100.013
0.5266	100.013
0.5300	100.013
0.5333	100.013
0.5366	100.013
0.5400	100.013
0.5433	100.013
0.5466	100.013
0.5500	100.013
0.5533	100.013
0.5566	100.013
0.5600	100.013
0.5633	100.013
0.5666	100.013
0.5700	100.013
0.5733	100.013
0.5766	100.013
0.5800	100.013
0.5833	100.013
0.5866	100.013
0.5900	100.013
0.5933	100.013
0.5966	100.013
0.6000	100.013
0.6033	100.013
0.6066	100.013
0.6100	100.013
0.6133	100.013
0.6166	100.013
0.6200	100.013
0.6233	100.013
0.6266	100.013
0.6300	100.013
0.6333	100.013
0.6366	100.013
0.6400	100.013
0.6433	100.013
0.6466	100.013
0.6500	100.013
0.6533	100.013
0.6566	100.013
0.6600	100.013
0.6633	100.013
0.6666	100.013
0.6700	100.013
0.6733	100.013
0.6766	100.013
0.6800	100.013
0.6833	100.013
0.6866	100.013
0.6900	100.013
0.6933	100.013
0.6966	100.013
0.7000	100.013
0.7033	100.013
0.7066	100.013
0.7100	100.013
0.7133	100.013
0.7166	100.013
0.7200	100.013
0.7233	100.013
0.7266	100.013
0.7300	100.013
0.7333	100.013
0.7366	100.013
0.7400	100.013
0.7433	100.013
0.7466	100.013
0.7500	100.013
0.7533	100.013
0.7566	100.013
0.7600	100.013
0.7633	100.013
0.7666	100.013
0.7700	100.013
0.7733	100.013
0.7766	100.013
0.7800	100.013
0.7833	100.013
0.7866	100.013
0.7900	100.013
0.7933	100.013
0.7966	100.013
0.8000	100.013
0.8033	100.013
0.8066	100.013
0.8100	100.013
0.8133	100.013
0.8166	100.013
0.8200	100.013
0.8233	100.013
0.8266	100.013
0.8300	100.013
0.8333	100.013
0.8366	100.013
0.8400	100.013
0.8433	100.013
0.8466	100.013
0.8500	100.013
0.8533	100.013
0.8566	100.013
0.8600	100.013
0.8633	100.013
0.8666	100.013
0.8700	100.013
0.8733	100.013
0.8766	100.013
0.8800	100.013
0.8833	100.013
0.8866	100.013
0.8900	100.013
0.8933	100.013
0.8966	100.013
0.9000	100.013
0.9033	100.013
0.9066	100.013
0.9100	100.013
0.9133	100.013
0.9166	100.013
0.9200	100.013
0.9233	100.013
0.9266	100.013
0.9300	100.013
0.9333	100.013
0.9366	100.013
0.9400	100.013
0.9433	100.013
0.9466	100.013
0.9500	100.013
0.9533	100.013
0.9566	100.013
0.9600	100.013
0.9633	100.013
0.9666	100.013
0.9700	100.013
0.9733	100.013
0.9766	100.013
0.9800	100.013
0.9833	100.013
0.9866	100.013
0.9900	100.013
0.9933	100.013
0.9966	100.013
1.0000	100.013

END

1.0000	100.006
1.2000	100.006
1.4000	100.000
1.6000	100.000
1.8000	100.000
2.0000	100.000
2.2000	100.000
2.4000	100.000
2.6000	100.000
2.8000	100.000
3.0000	100.000
3.2000	100.000
3.4000	100.000
3.6000	100.000
3.8000	100.000
4.0000	100.000
4.2000	100.000
4.4000	100.000
4.6000	100.000
4.8000	100.000
5.0000	100.000
5.2000	100.000
5.4000	100.000
5.6000	100.000
5.8000	100.000
6.0000	100.000
6.2000	100.000
6.4000	100.000
6.6000	100.000
6.8000	100.000
7.0000	100.000
7.2000	100.000
7.4000	100.000
7.6000	100.000
7.8000	100.000
8.0000	100.000
8.2000	100.000
8.4000	100.000
8.6000	100.000
8.8000	100.000
9.0000	100.000
9.2000	100.006
9.4000	100.000
9.6000	100.000
9.8000	100.006
10.0000	100.000

# Slug Test on Monitoring Well 02-001MW

STEP (Slug) Test Automated Type-Curve Match (V1.2)



03-001 MW

SE1000C  
Environmental Logger  
05/17 17:25

Unit# 00601 Test 7

INPUT 1: Level (F) TOC

Reference 100.000  
Linearity 0.030  
Scale factor 20.090  
Offset 0.060  
Delay mSEC 50.000

Step 0 05/17 17:15:26

Elapsed Time INPUT 1


0.0000	100.051
0.0033	100.082
0.0066	100.406
0.0100	100.964
0.0133	101.243
0.0166	100.881
0.0200	100.114
0.0233	100.640
0.0266	101.217
0.0300	100.856
0.0333	100.742
0.0366	100.710
0.0400	100.666
0.0433	100.621
0.0466	100.590
0.0500	100.558
0.0533	100.533
0.0566	100.501
0.0600	100.482
0.0633	100.456
0.0666	100.431
0.0700	100.412
0.0733	100.393
0.0766	100.380
0.0800	100.361
0.0833	100.342
0.0866	100.330
0.0900	100.317
0.0933	100.311
0.0966	100.298
0.1000	100.285
0.1033	100.279
0.1066	100.266
0.1100	100.260
0.1133	100.247
0.1166	100.241
0.1200	100.235
0.1233	100.228
0.1266	100.222
0.1300	100.216
0.1333	100.209
0.1366	100.203
0.1400	100.197
0.1433	100.197
0.1466	100.190
0.1500	100.184
0.1533	100.178
0.1566	100.178
0.1600	100.171
0.1633	100.165
0.1666	100.165
0.1700	100.159
0.1733	100.159
0.1766	100.152
0.1800	100.152
0.1833	100.146
0.1866	100.146
0.1900	100.139

0.1933	100.139
0.1966	100.139
0.2000	100.133
0.2033	100.133
0.2066	100.127
0.2100	100.127
0.2133	100.127
0.2166	100.120
0.2200	100.120
0.2233	100.120
0.2266	100.114
0.2300	100.114
0.2333	100.114
0.2366	100.114
0.2400	100.114
0.2433	100.108
0.2466	100.108
0.2500	100.108
0.2533	100.108
0.2566	100.108
0.2600	100.101
0.2633	100.101
0.2666	100.101
0.2700	100.101
0.2733	100.101
0.2766	100.095
0.2800	100.095
0.2833	100.095
0.2866	100.095
0.2900	100.095
0.2933	100.089
0.2966	100.089
0.3000	100.089
0.3033	100.089
0.3066	100.089
0.3100	100.089
0.3133	100.089
0.3166	100.089
0.3200	100.082
0.3233	100.082
0.3266	100.082
0.3300	100.082
0.3333	100.082
0.3366	100.076
0.3400	100.076
0.3433	100.076
0.3466	100.076
0.3500	100.070
0.3533	100.070
0.3566	100.070
0.3600	100.063
0.3633	100.063
0.3666	100.063
0.3700	100.057
0.3733	100.057
0.3766	100.057
0.3800	100.057
0.3833	100.051
0.3866	100.051
0.3900	100.051
0.3933	100.051
0.3966	100.051
0.4000	100.051
0.4033	100.051
0.4066	100.051
0.4100	100.051
0.4133	100.051
0.4166	100.051
0.4200	100.051
0.4233	100.051
0.4266	100.051
0.4300	100.051
0.4333	100.051
0.4366	100.051
0.4400	100.051
0.4433	100.051
0.4466	100.051
0.4500	100.051
0.4533	100.051
0.4566	100.051
0.4600	100.051
0.4633	100.051
0.4666	100.051
0.4700	100.051
0.4733	100.051
0.4766	100.051
0.4800	100.051
0.4833	100.051
0.4866	100.051
0.4900	100.051
0.4933	100.051
0.4966	100.051
0.5000	100.051
0.5033	100.051
0.5066	100.051
0.5100	100.051
0.5133	100.051
0.5166	100.051
0.5200	100.051
0.5233	100.051
0.5266	100.051
0.5300	100.051
0.5333	100.051
0.5366	100.051
0.5400	100.051
0.5433	100.051
0.5466	100.051
0.5500	100.051
0.5533	100.051
0.5566	100.051
0.5600	100.051
0.5633	100.051
0.5666	100.051
0.5700	100.051
0.5733	100.051
0.5766	100.051
0.5800	100.051
0.5833	100.051
0.5866	100.051
0.5900	100.051
0.5933	100.051
0.5966	100.051
0.6000	100.051
0.6033	100.051
0.6066	100.051
0.6100	100.051
0.6133	100.051
0.6166	100.051
0.6200	100.051
0.6233	100.051
0.6266	100.051
0.6300	100.051
0.6333	100.051
0.6366	100.051
0.6400	100.051
0.6433	100.051
0.6466	100.051
0.6500	100.051
0.6533	100.051
0.6566	100.051
0.6600	100.051
0.6633	100.051
0.6666	100.051
0.6700	100.051
0.6733	100.051
0.6766	100.051
0.6800	100.051
0.6833	100.051
0.6866	100.051
0.6900	100.051
0.6933	100.051
0.6966	100.051
0.7000	100.051
0.7033	100.051
0.7066	100.051
0.7100	100.051
0.7133	100.051
0.7166	100.051
0.7200	100.051
0.7233	100.051
0.7266	100.051
0.7300	100.051
0.7333	100.051
0.7366	100.051
0.7400	100.051
0.7433	100.051
0.7466	100.051
0.7500	100.051
0.7533	100.051
0.7566	100.051
0.7600	100.051
0.7633	100.051
0.7666	100.051
0.7700	100.051
0.7733	100.051
0.7766	100.051
0.7800	100.051
0.7833	100.051
0.7866	100.051
0.7900	100.051
0.7933	100.051
0.7966	100.051
0.8000	100.051
0.8033	100.051
0.8066	100.051
0.8100	100.051
0.8133	100.051
0.8166	100.051
0.8200	100.051
0.8233	100.051
0.8266	100.051
0.8300	100.051
0.8333	100.051
0.8366	100.051
0.8400	100.051
0.8433	100.051
0.8466	100.051
0.8500	100.051
0.8533	100.051
0.8566	100.051
0.8600	100.051
0.8633	100.051
0.8666	100.051
0.8700	100.051
0.8733	100.051
0.8766	100.051
0.8800	100.051
0.8833	100.051
0.8866	100.051
0.8900	100.051
0.8933	100.051
0.8966	100.051
0.9000	100.051
0.9033	100.051
0.9066	100.051
0.9100	100.051
0.9133	100.051
0.9166	100.051
0.9200	100.051
0.9233	100.051
0.9266	100.051
0.9300	100.051
0.9333	100.051
0.9366	100.051
0.9400	100.051
0.9433	100.051
0.9466	100.051
0.9500	100.051
0.9533	100.051
0.9566	100.051
0.9600	100.051
0.9633	100.051
0.9666	100.051
0.9700	100.051
0.9733	100.051
0.9766	100.051
0.9800	100.051
0.9833	100.051
0.9866	100.051
0.9900	100.051
0.9933	100.051
0.9966	100.051
1.0000	100.051

0.9500	100.044
0.9533	100.044
0.9566	100.044
0.9600	100.044
0.9633	100.044
0.9666	100.044
0.9700	100.044
0.9733	100.044
0.9766	100.044
0.9800	100.044
0.9833	100.044
0.9866	100.044
0.9900	100.044
0.9933	100.044
0.9966	100.044
1.0000	100.044
1.0033	100.044
1.0066	100.044
1.0100	100.044
1.0133	100.044
1.0166	100.044
1.0200	100.044
1.0233	100.044
1.0266	100.044
1.0300	100.044
1.0333	100.044
1.0366	100.044
1.0400	100.044
1.0433	100.044
1.0466	100.044
1.0500	100.044
1.0533	100.044
1.0566	100.044
1.0600	100.044
1.0633	100.044
1.0666	100.044
1.0700	100.044
1.0733	100.044
1.0766	100.044
1.0800	100.044
1.0833	100.044
1.0866	100.044
1.0900	100.044
1.0933	100.044
1.0966	100.044
1.1000	100.044
1.1033	100.044
1.1066	100.044
1.1100	100.044
1.1133	100.044
1.1166	100.044
1.1200	100.044
1.1233	100.044
1.1266	100.044
1.1300	100.044
1.1333	100.044
1.1366	100.044
1.1400	100.044
1.1433	100.044
1.1466	100.044
1.1500	100.044
1.1533	100.044
1.1566	100.044
1.1600	100.044
1.1633	100.044
1.1666	100.044
1.1700	100.044
1.1733	100.044
1.1766	100.044
1.1800	100.044
1.1833	100.044
1.1866	100.044
1.1900	100.044
1.1933	100.044
1.1966	100.044
1.2000	100.044
1.2033	100.044
1.2066	100.044
1.2100	100.044
1.2133	100.044
1.2166	100.044
1.2200	100.044
1.2233	100.044
1.2266	100.044
1.2300	100.044
1.2333	100.044
1.2366	100.044
1.2400	100.044
1.2433	100.044
1.2466	100.044
1.2500	100.044
1.2533	100.044
1.2566	100.044
1.2600	100.044
1.2633	100.044
1.2666	100.044
1.2700	100.044
1.2733	100.044
1.2766	100.044
1.2800	100.044
1.2833	100.044
1.2866	100.044
1.2900	100.044
1.2933	100.044
1.2966	100.044
1.3000	100.044
1.3033	100.044
1.3066	100.044
1.3100	100.044
1.3133	100.044
1.3166	100.044
1.3200	100.044
1.3233	100.044
1.3266	100.044
1.3300	100.044
1.3333	100.044
1.3366	100.044
1.3400	100.044
1.3433	100.044
1.3466	100.044
1.3500	100.044
1.3533	100.044
1.3566	100.044

# Slug Test on Monitoring Well 03-001MW

STEP (Slug) Test Automated Type-Curve Match (V1.2)



**APPENDIX F**

**FIELD NOTES**

**THIS PAGE INTENTIONALLY LEFT BLANK**

SUN	MON	TUE	WED	THU	FRI	SAT
12 FRI 9/19/93 • Staked SGS points. - Obtained - digging format.	13 Soil Gas Survey Site 1, 3 23 points surveyed	14 Soil Gas Survey Site 1, 2, 3 24 points surveyed	15 Soil Gas Survey Complete Site No. 2 11 points	16 Meet Drillers Begin on PZ 1.	17 Abandoned PZ 1. Lined up - Soil Sampling for GC Training	18 Preparing Sample Pack Ages
19 Preparing Sample Pack Ages	20 Soil Borings 03-001 BH 03-002 BH 03-003 BH 03-004 BH 03-006 BH	21 Soil Borings 01-001 BH 01-003 BH 01-004 BH 02-001 BH 02-003 BH	22 Great Borings Drive Inventory FB - FB 02-006 BH HRS Walk	23 Great Borings 02-007 BH 02-005 BH 02-004 BH 02-008 BH ES - FB	24 Surveyors Drilling Est's Great Hand Axes Re-Flag location for Surveyors.	25 No. 106 RELATED Achievements
26 Complete Soil Descriptions Kump's GC Data Info Closeout	27 Walk Site w/ Surveyor HRS Info Site Closeout	28 Pack Equip DEPART SITE Return to SA	29	30	1	2
CONTENTS						
DATE						

1

DAY 1 10 SEPTEMBER 1993

0745 Arrive at Roslyn ANG'S. E&A1  
Packer (EP) and Myrna Rodriguez (MR)  
Meet with Capt. Larry Johnson  
Roslyn ANG'S Base Civil Engineer.

Introductions and a general review  
of activities planned for the SI  
Are discussed. Events for the  
Soil Gas survey to begin on Mon.  
(9/13) are discussed.

0810 M.R. and E.P. depart Capt. Johnson's  
office for a walk of the three sites.

\* SITE No. 1 - has a large  
pile of dirt covered w/ visqueen  
from UST removals. Dirt is  
south of Bldg 3C and covers a  
few planned SGS points.

\* SITE No. 2 - has been changed  
alot due to a UST removal. A  
large pile of dirt blocks access  
for SGS and drilling activities.



2

\* Site No. 3 - appears relatively undisturbed. Begins to rain.

WEATHER - Cloudy and Cool  
High: mid 80s. Overcast w/ scattered showers.

0840 MR and EP depart Site.  
Prepare to drive to NEWARK Airport to obtain Cargo Box of supplies.

1330 Arrive at Newark Airport  
American Airlines Cargo Terminal and get box of supplies.

1430 Arrive back at the base and meet w/ Cpt Johnson. Will grid the SGS points. Meet with John Warner, Base plumber to locate underground lines at the sites. Walk all 3 sites.

\* Site No. 1 - locate an old grid of underground utilities. Will locate SGS points to avoid and lay at least 3 feet


3

\* Site No. 2 - locate sewer line parallel to back of Bldg 16.

\* Site No. 3 - no apparent utilities.


1700 M.R. and E.P. finish laying out SGS grid. Grid outlined below:

IRP SITE No. 3




4

IRP SITE No. 1



IRP SITE No. 2

5



1710 E.O. and M.R. depart site for Hotel.

1730 E.O. and M.R. depart Hotel to pick up Jerry Arraga (JA) at Airport.  
Very heavy traffic.

1830 pick up J.A.

1915 Arrive back at Hotel

- Earl Edwards 9/10/93

11 hours


6

DAY 2

SATURDAY

11 Sept 93

No Work Related Activity  
Conducted



Earl E. Pauls

9/11/93

(D.H.S.)

7


DAY 3

SUNDAY

12 Sept 93

No Work Related Activity  
Conducted.

\* Meeting w/ MR and JA for  
tomorrow's activity.



Earl E. Pauls

9/12/93

(D.H.S.)

8

Day 4 Monday 13 SEPT 93

0745 Arrive at Site, EP and MR,  
Meet with Lawrence Schermeyer and  
Robert Burns from Tracer Research Corp.  
Walk through the site.

## 0800 SAFETY BRIEFING

SSO - Earl Parker for Jerry Aring  
Myrna Rodriguez - OPTech  
Lawrence Schermeyer - Tracer  
Robert Burns

- \* Discussed HSP, route to Hospital, Emergency procedures.
- \* Discussed site hazards such as power lines and underground utilities.
- \* Weather concerns. (Heat should not be a significant).
- \* Authorized the SGS Team to stop work immediately if they recognize a hazard.

Weather - Partly Cloudy and breezy.

H's: Mid 80's.  
Ideal Weather!

9

0820 BEGIN SGS at IRP Site No 3.  
All SGS samples are shot twice. (Duplicates).  
\* EP and MR Measure all SGS points  
once drilled to draw a scaled map.

0950 E.P. and M.R. check utilities at Site 1.

1020 J.A. Arrives at the Site. E.P. and

J.A. walk sites.

1035 SGS Team finishes probe work at  
site No 3. Analytical work continues  
while Rob. patches up locations.

1110 SGS Team moves to Site 1. Begin on  
North row from East Side

1130 BREAK for Lunch. SGS Team and  
OPTech depart Site.

1200 RETURN from Lunch. BEGIN SGS  
work at Site 1.

10

1500 Finished SGS Points in North row.  
20 SGS Points completed.  
Begin Center row from the West Side.

1600 Finished SGS points for the day.  
Beginning to patch holes and compile  
Analytical results for the day.

Completed Site No. 3 - 9 points  
Site No. 1 - 14 points

Daily Totals - 23 points

1630 SGS Team gives EP preliminary  
data from today's work. Departs  
Site.

1645 E.P. M.R. and J.A. depart Site

1700 E.P. calculates SGS values for the day.

1830 Complete work for the day

Evelyn #

9/15/93

10.5 hrs

11

DAY 5 TUESDAY 14 SEPT 93

0730 E.P., M.R. and J.A. arrive at the  
Site. SGS Team begins work on  
South line of SGS Points on Site 1.  
Based on yesterday's results at  
Site # 3, two points will be moved  
from the Site 1 grid to attempt  
to delineate small hill in Site 3.

0815 Check water level in observation well (?)  
near fuel pumps in front of Bldg 16.  
Water level = 19.54' Below casing.  
Casing of flush mount - 2' BLS  
 $\therefore$  WL = 19.74' BLS.

0830 E.P. depart site for Hotel.

0900 Phoned Optech. Talked to Debbie  
Zapata. Relayed Mondays SGS information.

0930 Arrived at NYTest. Met with  
Joe Dockery, and Doug Sheeley. Coordinated  
on Analysis plan and schedule. Gave  
them location and types of Analysis  
samples.



12

Doug Sheeley took E.P. on a tour of the NYTEST Lab.  
 Meeting concluded with discussion of Methanol delivery for tomorrow (Wed 9/15) and Meeting on Monday (9/20) to discuss the delivery schedule and volume.

1115 E.P. departs NyTest for Lab Site

1130 E.P. arrives at Site. SGS Team leaves for lunch.

1145 E.P., M.R. and J.A. depart site for lunch.

1215 Return to site from lunch. SGS team continues on Site #1. Driller rep came to base during lunch. Will have to meet with him again.

1250 Talked to Lisa about meeting w/ Lab representative and to Lawrence M. on payment for drums.

1310 J.A. departs site to obtain Zero-Air for the field GC.

13

1330 SGS Team completes SITE No. 1. (minus # 23 and # 29) moves back to SITE No. 3 to sample new point # 10 and # 11.

1410 Complete two SGS points at SITE 3.

1420 Begin SGS work at SITE No. 2. Beginning on East end, moving west.

1510 E.P. departs site to go to Bank to obtain cash for payment to drum merchant.

1540 E.P. returns to site. J.A. back with Zero-Air. Move to measure SGS points on Site No. 1.

1600 SGS Team finishes sampling for the day. Beginning to compile analytical results from the days activity.

Completed 24 SGS points today.


14

1630 SGS Team delivers daily data  
and departs the site.  
Completed 5 out of the 14  
SGS points on the 1RP Site #2.

1635 E.P., J.A. and M.R. depart site.

1700 E.P. calculates AM values for SGS  
points completed for the day.

1855 E.P. finishes work for the day.



E. P. Lark

9/14/93

10 hrs

15

DAY 6

WEDNESDAY

15 SEPT 93

0730 E.P., M.R. and J.A. arrive at the site.

WEATHER: Sunny and warm,  
Breezy, winds from E.  
Hi: Mid 80's

SGS Team continues SGS on Site 2.

0810 E.P., J.A. and M.R. stake out initial  
locations of BH, MW, and PZ at  
Site No 1 and 3.

0845 Take another W.L. in the Test hole  
near the fuel pumps.

19.53 Below Casing

+ .20

19.73 BLS

0910 E.P. and J.A. depart Base to pick up  
Methanol from the Lab.

0935 Return to Base.

1010 E.P. and J.A. & M.R. begin to measure  
borings and SGS points at Site No. 2

16

1110 Measured in boring locations at Site No. 1.

1115 SGS Team completed analysis samples at IRP Site No. 2. 11 Points surveyed today.

1145 SGS Team delivers final analytical results for Site No. 2. Begins to pack up equipment.

1200 SGS TEAM DEPARTS SITE.  
MISSION COMPLETED.

1215 J.A. and M.R. depart site for lunch.

1245 J.A. and M.R. return from lunch.  
EP completes conversion of SGS data from IRP SITE No. 2.  
Completes site diagram and finalizes locations at BH at Site No. 2.

1400 Drum man delivers 35 55-Gallon DOT drums.

17


1410 M.R. departs site for Hotel to obtain HRS information.

1415 Vince Nantista and KEN from Soil Mechanics arrive at Base.  
Go through walk through of sites and ALL BH, MW, and PZ locations.  
& Discuss drilling procedures, clogon site, well construction, other aspects of the drilling operation.

1500 Soil Mechanics departs site.  
EP and J.A. go to Civil Engineering to coordinate w/ CPT Johnson on drilling program to begin tomorrow.

1530 E.P. and J.A. depart site

1700 Conclude work on SGS analysis and BH, MW diagrams



Earl E. Lutz 9/15/93

10 hrs



18 DAY 7 THURSDAY 9/16/93

0815 E.P. and MR. Arrive At Base. J.A. is refueling van and obtaining di-water. Go to civil engineering to FAX time-sheets to S.A.

Walk Piezometer sites. Verify for utilities.

#### WEATHER

Frontal passage Cloudy and Rain all day. Breezy, winds out of the E & West.  
Hi - mid 70's

#### 0940 SAFETY BRIEFING

Drillers Arrive on Site, Orientation

Earl Parker

Jermy Arriaga

Myrna Rodriguez

Robert Rogers

David Vernick

Brett Brenner

OPTECH

Soil Mechanics

Discuss Site and Contaminant History.

19

Environmental Hazards, Overhead power, underground utility.

Emergency procedures to include Ambulance and Route to Hospital.

Talk about SI Sequence and daily objective.

1000 Drillers set up over PZ 01, set up decon area and prepare for drilling. Using CME 75 Drill Rig HSA.

J.A. Sets up field GC for analysis during Piezometer drilling.

1100 Begin drilling at Piezometer (PZ) 1.

0'-5' BCS Sand, silt, gravel. Slightly damp. Brown. Rolls to a loose ball.

5'-10' BCS - Same -

10'-15' BCS - Same -

15'-20' BCS At ~17' BCS becoming very silty. No gravel.

Balls into firm cohesive mass.

20'-25' BCS Silty with large gravel.

Well rounded gravel. Sand

And silt. Beginning to move toward the bottom.

20

25'-30' BLS - Becoming more sandy with fewer and smaller well rounded gravel particles. Brown. Coarse sand. Moist.

30'-35' - SAME -

35'-40' Sandy, Silty, becoming slightly more silty. Gravel to marble size.

1130 At 40' BLS, No water yet. Drilling with 2.25" size Auger.

1145 Drillers break for lunch and must obtain a part for skinn cleaner.

1200 J.A. and M.R. go to lunch.

BTEX standard supplied by Tracer is not good. Seems like pure water. Shot clean in the G.C. Must try to obtain another BTEX standard.

1300 Began drilling again. Drillers returned at 1240.

21

40'-45' BLS Sand, Silt, with increasing large gravel, small cobbles. Well rounded marble and larger sized grains.

45'-50' Particle size becoming smaller. Sand, silt, gravel. Well rounded some large particles. Mostly pea sized grains.

50'-55' - Same -

55'-60' Brown, Sand, Silt, Gravel, more of the same.

60'-65' Becoming more gravelly. Cobble sized particles, well rounded.

65'-70' Continue in gravel. No recovery on the surface.

70'-75' Beginning to get gravel/cobble return at the surface.

Well rounded to subangular cobble up to 2" in diameter.

1330 At 75' bbs. No water yet. Stopped drilling to clean out the hole.

22

1400 Begin drilling again at 75'.

75'-80' recovery consist of very coarse sand and gravel. Descriptions of each 5' interval based on recovery at the surface is no longer very reliable. Will not continue to describe in this manner.

80'-85'  
85'-90'

1430 REACH 90' BLS. Rods show dry hole. Used water probe in HSA and confirmed the bottom is clay. Drilling is concluded for the day. Crew begins to clean hole to leave augers in overnight.

1500 Drillers depart site

SP, MR and JA break down GC. depart site.


1800 JA and SP order a BTEx standard to be delivered to Hotel by FEDEX tomorrow.

23

2115 Contact John Morris in Washington. Relay information on Soil Gas Survey preliminary results. BTEx standard situation from Tracer Research, and the groundwater situation at the Base.

Decided to inform Bill Nealon from the Air National Guard Readiness Center (ANGRC) and let him make the decision as how to proceed with the groundwater investigation.

Soil Sampling will tentatively begin on Monday and should proceed quickly.



Earl E. Pugh

9/16/93

7 hours

24

DAY 8 FRIDAY 17 SEPT 93

0700 E.P., M.R. JA Arrive At the Site.

WEATHER: Raining Heavy At  
some intervals Temp lower 60s.  
Forecast is for Cloudy skys  
with intermittent showers All  
day. Hi's in the lower 70s.

0730 Drillers Arrive. Discussion of  
groundwater situation results in  
a tentative decision to stop  
drilling on PZ 1. The lab is  
not ready to begin soil sampling  
today so we will do no drilling.

0805 E.P. decides to continue drilling on  
PZ 1 As deep as feasible to  
Attempt to locate water in the  
well. Departs drilling location to  
phone Bill Nealon and obtain  
nearby water level information.

0900 Phoned Ken Fischgrum at the

25

Nassau County Public Works dept. to  
obtain recent w.c. information on  
observation well N-11964 completed in  
the upper glacial aquifer. Information  
obtained indicated a Water level  
was taken on Sept 8, 1993:

Water = 56.26' Above MSL

Since our site is 3,500 feet east  
of the well at an elevation of  
200' Above MSL, water was  
likely to occur at 144' below  
land surface at the site.

Cpt Johnson was surprised by this  
information, stating that test  
borings for the dry wells constructed  
near the site indicated water  
to occur ~ 50' below land surface.  
He probably encountered a perched  
water table.

0910 Phoned call to Bill Nealon At  
ANGRC was not in. Left a  
brief message.

26

0915 Called Nytest Lab to change sampling plan to begin on Monday. Doug and Joe are out. Nytest will assign a rep and he will call back.

0920 Called Bill Nealon, Left my phone number to hotel on his service.

0925 Phoned Vince Nantsta w/ Soil Mechanics to update him on the job. Informed him we will be soil sampling on Monday and Tuesday (9-20/21-23).

1015 Received call from Tom Petrella of Nytest will meet with him at 11:00 am to discuss sampling program starting Monday.

1030 Developed sampling program for Monday. Will sample from Site No. 3 first. Then Site No. 1 and 2 on Tuesday. Groundwater program will

27

be carried out last and will await decision by ANGR Project Manager.

1100 Met with J.A. and M.R., went to Nytest and met with Tom Petrella. The decisions are as follows.

Sampling Program  
- Soil -

Monday, 20 Sept.

Soil Samples from IRP Site No. 3

6 borings x 3 intervals = 18 samples  
will obtain: 2 Equipment Blanks  
2 Field Blanks  
2 Field Duplicates  
1 MS/MSD

Total of 25 samples

Tuesday, 21 Sept

Soil Samples from IRP Sites No. 1 and 2.

Site 1 4 borings x 3 intervals = 12 samples

Site 2 3 borings x 3 intervals = 9 samples

5 borings x 2 intervals = 10 samples

Soil Samples = 31 samples



28

will obtain:

- 4 EQUIPMENT BEAKS
- 4 FIELD BEAKS
- 4 FIELD DEPLICATES
- 2 MS/MSD

Total of 45 samples

Further sampling will be developed after consultation with ANGRC.

1215 Lunch

1300 Back at hotel.

- \* Develop sampling details and set aside labels and Chain-of-Custody forms for Monday.
- Develop sleeve count for decon party.

1600 PHONED ANGRC for BILL NEALON.


He is not at his desk.

1700 PHONED JOHN MOERS. DISCUSSED options for drilling program.

29

Decided to drill the boreholes  
And continue with soil sampling.  
He (J.M.) will contact Bill Nealon  
And discuss the groundwater program.

- Continued to work on sampling packages for Soil Sampling Program to begin on Monday (9-20).



Earl Elbert 9-17-93 9 hrs

30


DAY 9 SATURDAY

18 Sept 93

\* Worked in Hotel on the sample packages for Soil Sampling. Mon (9-20)

Wrote out Labels, cut teflon tape squares, Aluminum Foil squares And Labeled Zip-Lock Bags.

Determined when QA/QC samples would integrate into sampling program.



Exp. 9-18-93

9-18-93

4 hrs

31


DAY 10 SUNDAY

19 Sept 93

\* Continued to create the sample packages by working on TUESDAY (9-21) sampling.

Wrote out Labels, cut teflon tape and Aluminum foil squares and Labeled Zip-Lock bags for TUE sampling.

Determined when QA/QC samples would integrate into sampling program.



Exp. 9-19-93

9-19-93

4 hrs

32

DAY 11

MONDAY

20 Sept 93

0700 MR and EP arrive at Site. Set  
up decon area at 1PP Site Va 3

0705 Drillers arrive, begin prep for  
drilling at Site No. 3

0720 J.A. arrives from Lab with  
ICE CHEST and Containers. Returns  
to Hotel for Isobutylene for P10.

0810 SAFETY BRIEFING

Earl Parker

Myrna Rodriguez

Jermy Arisinga

Robert Rodgers

Mark Stimpfle

Steven Mitchell

OPTECA

Soil Mechanics

Review All safety aspects for two  
new field members from Soil Mechanics

Signed Compliance Agreement

WEATHER: CLEAR AND COOL. Sunny  
and breezy Hi: Low 70's

0820 BEGIN DRILLING AT 03-001 BH

SPT Hammer - 140 lbs } Auto Hammer  
30" drop

33

0825 BEGIN DRIVING Sample 03-001/BH #1

03-001 BH #1

Interval 2" - 1.7" BLS

SPT BLOWS 16 0'-1.5"

24 1.5"-1.0'

16 1.0'-1.5'

Headspace = 9.5 PPM

Opening Spoon = 1.2 PPM

- Very dry and hard fill material  
Sandy, Gravelly, Silty.

Interval 5' - 6.5' BLS

SPT BLOWS

3 - 10.0' - 10.5' 5.0'-5.5'

3 - 10.5' - 11.0' 5.5'-6.0'

4 - 11.0' - 11.5' 6.0'-6.5'

Spoon Open = 1.3 PPM

Headspace = 4.1 PPM

- Soft, moist, sandy silt. No  
gravel. Brown. Mostly silt.



34

Interval 10.0' - 11.5' BLS

SPT 10 - 10.0' - 10.5'  
 15 10.5' - 11.0'  
 15 11.0' - 11.5'

Spoon Open : 1.6 PPM  
 Headspace : 2.4 PPM

Sand. Lighter brown fine silty sand. Some coarse sand grains but not common. Mostly fine to very fine sand w/ some silt.

0900 Mon to 03-004 BH

03-004 BH

Interval 0'-1.5' BLS  
 SPT 14 0.0' - 0.5'  
 14 0.5' - 1.0'  
 10 1.0' - 1.5'

Spoon Open : 24.6 PPM  
 Headspace : 42.6 PPM

Slight Odor in spoon

35

Dark brown, moist, unsorted fill.  
 Large gravel, sand, and silt.

Interval 5.0' - 6.5'  
 SPT 5 - 5.0' - 5.5'  
 4 - 5.5' - 6.0'  
 3 - 6.0' - 6.5'

Spoon Open : 6.4 PPM

Headspace : 10.7 PPM

Gravelly, silty, sand, poorly sorted fill material. dark brown, clay. Mostly a medium to fine sand with silt and gravel.

Interval 10.0' - 11.5'  
 SPT 18 - 10.0' - 10.5'  
 25 - 10.5' - 11.0'  
 27 - 11.0' - 11.5'

Spoon Open : 4.2 PPM

Headspace : 11.1 PPM

Very poorly sorted sand. Silty sand, with large, well rounded gravel and cobble sized grains.

Mostly medium to fine sand with little silt. Well rounded gravel and small cobbles.

36

Interval 10.0 - 11.5' FIELD OPLINITE

(Actual) 11.0' - 12.5' BLS

Pushed below the 10.0 - 11.5' Interval

to obtain duplicate sample

STP

14

- 10.0' - 10.5'

15 - 10.50' - 11.0'

12 - 11.00' - 11.5'

Spoon Open : 3.6 PPM

Headspace : 21.6 PPM

Very poorly sorted sand. Mostly a  
fine to medium grained sand with  
little silt. Contains fewer well  
rounded gravel and cobbles.

0945 Complete 03-004 BH

Move to 03-002 BH

1010 BEGIN

03-002 BH

Interval 0.0' - 1.5' BLS

STP

15 - 0.0' - 0.5'

9 - 0.50' - 1.0'

15 - 1.00' - 1.5'

Spoon Open : 0.4 PPM

Headspace : 5.3 PPM

37

Dark brown, clay, very poorly sorted  
sandy and gravel fill material.

Interval : 5.0' - 6.5' BLS

STP

3

5.0 - 5.5

5

5.5 - 6.0

4

6.0 - 6.5

Open Spoon : 0.4 PPM

Headspace : 5.1 PPM

dark brown, very poorly sorted silty sand.

Medium to fine grained sand w/ silt and

well rounded to rounded gravel particles abundant.

Interval : 10.0' - 11.5' BLS

STP

16

10.0 - 10.5

19

10.5 - 11.0

15

11.0 - 11.5

Open Spoon : 0.3 PPM

Headspace : 3.1 PPM

brown, poorly sorted medium to fine grained

silty sand with well rounded medium

to small gravel abundant. Not much silt.

Mostly poorly sorted sand.

1035 Complete Borehole 03-002 BH

Move to 03-006 BH

38

1045 Begin at 03-006 BH

03-006 BH

Interval 0.0' - 1.5' BLS

SPT

11 0.0 - 0.5

9 0.5 - 1.0

8 1.0 - 1.5

Open Spoon 6.7

Headspace : 50.5

Very poorly sorted, dark, sandy fill material with large to medium sized pebbles. Small cobbles present. Much fine sand and silt. No odor present.

Interval 5.0' - 6.5' BLS

SPT

3 5.0 - 5.5

3 5.5 - 6.0

3 6.0 - 6.5

Open Spoon 1.3

Headspace 6.3

Very poorly sorted, brown sand with abundant medium, well rounded gravel. Silty with fine sand. Mostly medium sand and small well rounded gravel.

39

Interval 10.0' - 11.5' BLS

SPT

22 10.0 - 10.5

29 10.5 - 11.0'

27 11.0 - 11.5'

Open Spoon : 2.7 PPM

Headspace : 3.4 PPM

Light brown fine to medium sand with very little silt. Abundant small to medium sized, well rounded gravel. Very few large gravel and small cobble grains. Very poorly sorted sand and gravel.

1125 Finished drilling on 03-006 BH

Drillers break down and go to lunch. EP 5.A take EQUIP BACK and Field Blank #1.

1215 Drillers return from lunch.

Begin to grout holes and

sweep site. Begin to prepare

for Borehole 03-003 B11

1235 Phone John Morris in

San Antonio. Confirmed to

end the drilling program

40

Following the conclusion of soil borings on TUESDAY. Will not drill BG borings or the deep borings at each site.

1300 Prepare to Sample 03-003BH

1315 BEGIN Drilling AT 03-003BH

Interval 0.0' - 1.5'

SPT 8 0.0 - 0.5

9 0.5 - 1.0

9 1.0 - 1.5

Spoon Open: 4.2 PPM

Headspace: 6.3 PPM

Very poorly sorted, dark brown fill material. Sandy with silt and abundant gravel and small cobbles. Dry, mostly a medium to fine grain sand w/ gravel.

Interval 5.0' - 6.5' BLS

SPT 7 5.0 - 5.5

3 5.5 - 6.0

3 6.0 - 6.5

No RECOVERY. Rec of

Wood obstructed sampler. Will move 1' North and re-drill

41

And sample at 5.0'

Interval 10.0' - 11.5' BLS

SPT 17 10.0 - 10.5

28 10.5 - 11.0

29 11.0 - 11.5'

Open Spoon: 5.9 PPM

Headspace: 6.8 PPM

Interval 11.5' - 13.0' BLS

Field Duplicate

M&T MSD Sample

SPT 27 - 11.5 - 12.0

27 12.0 - 12.5

26 12.5 - 13.0

Open Spoon: 4.8 PPM

No headspace or Field GC Sample.

Fine to medium grain sand with some but little silt. Abundant

well rounded to rounded gravel.

Small to large gravel and small

cobble sized particles. Very poorly

sorted sand. Light Brown. Dry.

42

Interval 5.0'-6.5'

SPT

3

5.0'-5.5'

5

5.5'-6.0'

4

6.0'-6.5'

Open Spoon

2.9 PPM

Headspao 5.7 PPM

Very dark, organic rich silty sand.  
Well rounded gravel with abundant  
wood fragments. Leaf and wood  
fragment abundant. Large gravel  
and abundant small, well-rounded  
gravel. Mostly a fine grained silty  
sand matrix. High silt content. Dry.

1415 Conclude drilling at IRP Site No. 3  
by finishing 03-003 BH. Will  
not drill deep boring (03-005 BH)  
at this time. Drillers begin  
to clean up site. Grout holes.

1440 Drillers depart Site

E.P. MR. take Equip Blank and  
Field Blank #2.

43

1500 BEGIN to work on Chain-of-  
Custody documentation and Site  
Clean-up.

1630 Pack up and depart Site for  
LAB. E.P. and J.A. go to  
LAB to turn in samples. M.R.  
departs for Hotel to write  
letters for HRS information.

1640 E.P. and J.A. Arrive at LAB  
and Turn in Samples. Inform  
Davy Shaeley and Joe Dockery  
that Soil Samples will have  
a hold. They will not  
analyze until given the notice  
to proceed by ORTECH.

1700 E.P. and J.A. turn over  
Samples to NY TEST. Obtain  
our copies of the Chain-of-  
Custody and depart LAB.




44

2000 E.P. works on finalizing  
Sampling packages for TUE  
(9-21). Speak w/ John  
Morris. will not hand-Auger  
At this time.

Go up w/ J.A. to see  
how the GC analysis is  
going.

2130 End for the day.



Evel E. Fawcett 9-20-93 (12 hrs)

DAY	12	TUESDAY	21	Sept 1993 <sup>45</sup>
0700	E.P. and M.C. arrive at site.			
0703	Drillers arrive at site. Begin to prepare for drilling. J.A. arrives from LAB w/ sample containers.			
0705	Raining. Setting up tarp to set up decon area and work stations. Raining, cool, H's - lower 60's. Will not start drilling till rain stops.			
0910	BEGIN AT 01-004 BH. Rain stops. Tailgate safety update with all personnel. New drilling member signs Safety Compliance.			
	Borehole 01-004 BH			
	Interval 0.0' - 1.5' BLS			
	15 - 0.0' - 0.5'			
	28 - 0.5' - 1.0'			
	20 - 1.0' - 1.5'			
	Black fill. Appears to contain abundant coal or charcoal. Very poorly sorted medium to fine sandy coal particles. Many large particles of charcoal. Very poor recovery. Will resample.			

Interval 0.0 - 1.5' BLS

SPT - 11 - 0.0 - 0.5

28 - 0.5 - 1.0

29 - 1.0 - 1.5

Open Spoon 6.8 PPM

Headspace 3.5 PPM

Continues to be black with abundant charcoal or coal fill material. No odor. Dry, very poorly sorted material. Mostly very fine grained. Non-cohesive coal sand with abundant large particles.

Interval 5.0 - 6.5' BLS

SPT - 1 - 5.0 - 5.5

3 - 5.5 - 6.0

5 - 6.0 - 6.5

Open Spoon - 7.9 PPM

Headspace - Not obtained (No sample for GC)

Minimal Recovery. One good

brass sleeve.

- Dark, organic rich sand and fill material w/ abundant wood and wood chips. few large coal particles.

Interval 10.0' - 11.5' BLS

SPT 16 - 10.0 - 10.5

30 - 10.5 - 11.0

40 - 11.0 - 11.5

Open Spoon : 4.0 PPM

Headspace : 10.3 PPM

Very poorly sorted sandy silt. Mostly consolidated silt nodules with fine sand. Contains gravel and well rounded small cobble particles. Some medium sand and small gravel. Very poorly sorted.

1045 HOS Complete work on 01-004 BH  
Move to 01-003 BH

1100 BEGW Drilling 01-003 BH

Interval 0.0 - 1.5' BLS

19 - 0.0 - 0.5

20 - 0.5 - 1.0

15 - 1.0 - 1.5

Open Spoon - 8.5 PPM

Headspace - 7.5 PPM

Very poorly sorted, dark brown fill.

48

Medium to fine grain sand with  
Abundant, well rounded gravel  
and small cobble particles. No  
coal or charcoal particles present.  
No odor. Dry.

Interval 5.0' - 6.5' BLS

STP 1 - 5.0 - 5.5

1 - 5.5 - 6.0

1 - 6.0 - 6.5

No recovery - mostly wood chips  
pushing next interval. Organic sand.

Interval 6.5' - 8.0 BLS

STP Push - 6.5 - 7.0

Push - 7.0 - 7.5

2 - 7.5 - 8.0

Open Spoon 15.5 PPM

Headspace 3.5 PPM

Wet, well cohesive silty clay  
with few coarse sand, small  
gravel particles. Mostly silty  
clay. Cohesive and wet.

49

Interval 10.0' - 11.5' BLS

12 - 10.0 - 10.5

15 - 10.5 - 11.0

17 - 11.0 - 11.5

Open Spoon 5.3 PPM

Headspace 3.2 PPM

Brown, dry, sandy silt. Mostly silt  
with fine to coarse sand grains  
and a few gravel particles.

Interval - 10.0 - 11.5 BLS

(Actual 11.5 - 13.0)

FIELD Duplicate / MS/MSD

Same material as previous sample.

PID: Open Spoon 9.8 PPM

10SD HAS Complete work at 01-003 BH

Moving to 01-001 BH

1100 BEGIN drilling at 01-001 BH

Interval 0.0' - 1.5' BLS

STP 7 - 0.0 - 0.5

15 - 0.5 - 1.0

21 - 1.0 - 1.5

Open Spoon 2.1 PPM

Headspace 1.5 PPM



Dry, very poorly sorted silty sand. Mostly fine to medium sand silt and abundant medium to coarse gravel. Very angular gravel. Appears to be fill material. No odor, dry.

Interval 5.0 - 6.5 BLS

~~SPT~~ 27 - 5.0 - 5.5

SPT 34 - 5.5 - 6.0

33 - 6.0 - 6.5

Open Spoon : 0.0 PPM

Headspace : 0.5 PPM

Very poorly sorted coarse to medium silty sand. Mostly sand w/ silt and many small to large well rounded gravel. Some small cobbles present. Dry, no odor.

Interval 10.0 - 11.5 BLS

SPT 9 - 10.0 - 10.5

15 - 10.5 - 11.0

37 - 11.0 - 11.5

Open Spoon 7.3 ppm

Headspace 6.8 ppm

1130 hrs Complete 01-001 BH

Finished sampling at IRP Site 1.

Drillers moving to IRP Site 2.

Set up on 02-001 BH

1135 EQUIPMENT BLANK #3

FIELD Blank #3

1200 BEGIN drilling at 02-001 BH

Interval 0.0 - 1.5' BLS

SPT 5 - 0.0 - 0.5

6 - 0.5 - 1.0

6 - 1.0 - 1.5

Open Spoon 0.0 PPM

Headspace 0.0 PPM

Very dark brown to black, very poorly sorted sand. Contains some silt, medium sand to small, well rounded gravel. Dry.

Interval 5.0 - 6.5' BLS

SPT 18 - 5.0 - 5.5

28 - 5.5 - 6.0

24 - 6.0 - 6.5

Open Spoon : 0.0 PPM

52

Light brown, very poorly sorted sand. Silty with abundant well rounded gravel. Mostly a poorly sorted silty sand with gravel and small cobbles. Dry, No odor.

Interval 10.0 - 11.5 BLS

SPT 82 - 10.0 - 10.5

96 - 10.5 - 11.0

22 - 11.0 - 11.5

No Recovery will push next interval. Very gravelly. Big rocks in sleeves.

Interval 11.5 - 13.0 BLS

SPT 24 - 11.5 - 12.0

22 - 12.0 - 12.5

20 - 12.5 - 13.0

Open Spoon: 0.0 PPM

Headspace: 0.0 PPM

Light to medium brown, very poorly sorted sand. S.H. both medium and coarse sand with well rounded to very angular gravel and cobble.

53

1250 Finish at 02-001 BH. Moving to 02-002 BH.

B2<sup>er</sup>

1310 Phone John Morris. Informed as to

proceed with hand Augering and analytical work. The drillers will be released after this boring is finished but will be returning on Thursday. We will communicate later concerning the continued drilling program.

1320 Begin Drilling at 02-002 BH

Interval #1 0.0 - 1.5 BLS

SPT 4 - 0.0 - 0.5'

5 - 0.5' - 1.0'

5 - 1.0' - 1.5'

Open Spoon: 134 PPM

Headspace: 813 PPM

Odor - petroleum odor at hole and when spoon opens.

Dark brown to black very poorly sorted sand. Some silt, mostly coarse to medium sand with well rounded gravel.

54

1325 - BEGINNING TO DRIZZLE AGAIN.

Interval 5.0' - 6.5' BLS

SPT 13 - 5.0' - 5.5'

14 - 5.5' - 6.0'

13 - 6.0' - 6.5'

Open Spoon: 0.0 PPM

Headspace: 0.0 PPM

Poorly sorted silty sand. Mostly a fine to medium sand w/ alot of silt, fewer gravel particles. Dry. no large particles. Minimum recovery.

Interval 10.0' - 11.5' BLS

SPT 19 - 10.0' - 10.5'

19 - 10.5' - 11.0'

16 - 11.0' - 11.5'

Open Spoon: 0.0 PPM

Headspace: 0.0 PPM

Brown to light brown poorly sorted sand. Silt with fine to medium sand. Contains well rounded small to large gravel particles. Slightly moist. No odor.

55

Interval 11.5 - 13.0 FIELD Duplicate

Open Spoon: 0.0 PPM

Headspace: 0.0 PPM

Pushed from last interval. Lithology is identical. Very poorly sorted sand, silt, and gravel. Mostly sand. Moist. Good recovery. Drizzle stops again. Decan spoon to obtain equipment blank. Finished at 02-003 BH.

1340 Complete drilling. Precipitation begins again. Drillers break down rig.

1350 Drillers depart site. BEGIN to break down decan area.

1400 Obtain Equipment Blank #4. FIELD Blank #4.

1415 Prepare samples for Lab Turn-in. Chain-of-Custody Forms and Seal ice Chests

1435 BEGIN to break down working area - first break down barrier

56

1430 BEGIN final clean-up.

1500 E.P., M.R. and J.A. depart site  
for Lab

1550 DEPART Lab for Hotel


2000 Work on Sample Labels for

Hand Auger sites. Help J.A.

on field GC. Phone John Morris

and discussed investigation status.

2200 Done for the day.



Said Elahde 9/21/93 (11 hours)

57

DAY

13

Wednesday

Sept 22 93

0800

E.P.

Arrives at the

Site.

J.A.

is at hotel running samples

in the field GC.

M.R.

is at the library looking

up HRS information.

WEATHER : Cloudy, foggy. Temp: 59°

Cloudy to partly cloudy with

chance of light showers Hi-70's.

0810

Crew from soil

mechanics

Arrives at the

site to grout holes and more drums.

0840

BEGIN

DRUM

Inventory.

IRP SITE No. 1, 2, 3.

(Drum)

Soil Cuttings

02-001 BH

02 002 BH

(2)

Soil Cuttings

01-001 BH

(3)

Soil Cuttings

01-003 BH

01-004 BH

(14)	Soil Cuttings	03-003 BH
(15)	Soil Cuttings	03-006 BH
		03-002 BH
(16)	Soil Cuttings	03-001 BH
		03-004 BH
(17)	Soil Cuttings	PZ-01
(18)	Soil Cuttings	
(19)	Soil Cuttings	
(20)	Waste Water	Decon Station
(21)	Waste Water	
(22)	Waste Water	
	20 Empty drums in Drum Storage Area.	
(1)	Water Transport Drum	drillers use
(1)	Drum on Drillers Truck	
(1)	Grout Drum	
35	Total	

35	TOTAL
----	-------

1000	Drill crew begins moving drums to storage area
1035	M.R. Arrives at site w/ HRS info. We need to get a disk to put population information on. Goes to Civil Engineering to FAX info to San Antonio office.
1050	M.R. obtained disk for Civil Engineering. Departs site for hotel. Will pick up J.A. and return.
1115	Drill crew completes moving drums. Checks out and departs site.
1130	E.P. departs site for lunch. Meet J.A. and M.R.
1245	Return to base. Preparing to obtain Hand Auger borings.

Return to base. Preparing to obtain Hand Auger borings.

60

1330 Set up clean station and prepare to collect Equipment Blank prior to sampling.

1350 EQUIPMENT BLANK #3  
FIELD Blank #5

1435 Missing soil sample containers. Turn-in by mistake yesterday. M.R. departs for Lab to obtain more containers.

1540 Begin to obtain soil sample at 02-006 BH.

02-006 BH 0.0' - 0.5' BCS Very poorly sorted silty sand with abundant, well-rounded gravel. P10 - 0.0 PPM  
1615 Hit a hard gravel layer at 3.5' BCS. Cannot penetrate with hand auger. Attempting to pound through it with steel probe.

1700 Abandon hole for the day. E.P. M.R. and J.A. depart site for the day (8 hrs)  
5 - 11 AM

61

DAY 14 THURSDAY Sept 23, 93

0800 E.P. to stay at Hotel to obtain estimates for well construction for the groundwater investigation.

J.A. and M.R. go to site to begin obtaining hand augers.

0810 Phone to Sean Walters, Env. Coord at Suffolk ANGB. Give him update on investigation and ask about GW well installation. Suggested to talk to NYSDEC personnel on well installation.

0830 Phone to John Swartwout at NYSDEC. referred me to Dan Eaton - NYSDEC Geologist. He said we could use Wet Relying with Bentonite Mud, or Cable Tool rig technique only. Cannot use percussion rig. Will pass this information to driller.

0900 Phoned drillers for estimates on drilling 3 Piezometers, & Monitoring wells. Soil Mechanics - Vince Nantaska  
R&L Drilling - Lou Zackman  
Aqua-Tech Drilling - Ron Smoles



62

0930

Arrive at Site. J.A. and M.R.  
 working on Hand Augers  
 Moved off of 02-006 BH.  
 Completed 02-007 BH Internals  
 1 and 2. ~~Int 1 0.0-0.5' BLS 5.5 PPM~~  
 02-006 BH 0.0-0.5' BLS - Obtained 5.5 PPM  
 02-007 BH 0.0'-0.5' BLS - 1.2 PPM  
 Black, charcoal fill very unsorted.  
 02-007 BH 5.0'-5.5' BLS - 6.5 PPM  
 Moist, brown silty sand. Poorly sorted.  
 0950 BEGIN 02-005 BH  
 Digging into hard gravel interval  
 At 3' BLS. Moving on. Will return.  
 02-005 BH - 0.0'-0.5' BLS 1.8 PPM  
 Dark brown to black poorly sorted  
 silty sand with charcoal fill fragments.  
 1035 BEGIN on 02-004 BH.  
 02-004 BH 0.0'-0.5' BLS 40.8 PPM - Odor  
 Dark brown, very poorly sorted sand.  
 Silty sand with angular gravel.  
 Complete 02-004 BH ~~Int 1 5.0-5.5' BLS~~  
 Moist, very poorly sorted sandy silt. Odor.  
 1120 More back to 02-006 BH with  
 post-hole digger to enlarge  
 hole to get around large rock.  
 02-006 BH 10-05' BLS 5.5 PPM

63

we are able to bypass rock and  
 drill down to our target  
 interval.  
 02-006 BH 5.0-5.5' BLS 2.3 PPM  
 Dark brown, very poorly sorted silty sand  
 w/ abundant well-sorted gravel. No odor.  
 1350 Complete 02-006 BH 2nd Interval.  
 1415 Move back to 02-005 BH  
 and post-hole to 3' to attempt  
 to penetrate gravel interval  
 1435 BEGIN on 02-008 BH.  
 02-008 BH 0.0'-0.5' BLS 20 PPM  
 Dark brown to black very poorly sorted  
 silty sand with charcoal fill particles.  
 02-008 BH 5.0'-5.5' BLS 48 PPM  
 Dark brown to black, very poorly sorted  
 silty sand with few gravel. No charcoal fill.  
 1550 Abandon present hole at 02-005 BH  
 cannot penetrate gravel interval.  
 Moving 1.5' north and east.

64

1610. Penetrate to 5.0' much easier.  
 02-005 BH - 5.0'-5.5' BIS 457 PPM  
 Strong odor. Dark brown, very moist and  
 cohesive sandy-silt with clay. Some  
 small pebbles.

1635 Prepare to obtain Equipment Blank.

1650 Obtain EQUIPMENT BLANK #6  
 FIELD BLANK #6

1715 Prepare Chain-of-Custody for  
 samples. Begin site clean-up

1745 Depart Site for CAB.

1810 Depart CAB. E.P. J.A. and M.R.  
 go to Hotel.

2115 Phone w/ John Morris. Will close  
 down at Roslyn and prepare to  
 move to Worcester if plans unfold  
 with Washington.

(Carl E. Stachert 9/23/93 (9.5 km))

DAY 15

FRIDAY

SEPT 24, 93

65

0800 E.P. remains at Hotel to contact  
 Surveyor and Drillers for cost  
 estimate. J.A. and M.R. depart  
 for site to watch Grout team  
 from Soil Mechanics grout Hand  
 Augers.

0815 Contact Surveyor (Mr. Pratap Narsh).  
 He is not in the office. Left a message.

0830 Contact Edward Palma and Joke at  
 Big Apple Drilling for cost proposal  
 on drilling work.

0900 E.P. Arrives at Site. Grout team is  
 finished and J.A. and M.R. have  
 packet and inventoried the supplies.  
 At present, they are re-staking  
 all the points for the surveyor.  
 E.P. goes to Hardware store for  
 nails and paint.

0945. Continue to re-stake points.



1100 Staking out points at IEP Site No. #3.

1130 Complete Site clean-up and restaking  
All points. Going to Civil Engineering  
to talk to Spt. Johnson.

Not in - out to lunch.

1145 E.P. M.R. and J.A. depart site for  
lunch.

1230 Return to base after lunch. Return  
to Civil Engineering. Cpt Johnson is  
out of the office for the afternoon.

Talked to Maintenance Coordinator.  
Mr. Al Arens. We will store the  
big box in their warehouse when  
we go to Worcester.

Will return to base morning to  
(Monday)  
give Cpt Johnson a final briefing  
and Fax information to John  
Morris in San Antonio.

1240 Depart Site for Hohl.

M.R. goes to library for HRS  
information.

E.P. in room compiling information.  
J.A. is compiling GC information  
and finishing ~~hand~~ hand Auger  
GC shots.

1530 Received phone call from  
Surveyor (Mr. Narsu) Will  
meet with him at 8:30 AM  
Monday morning to walk  
the sites.

1630 Working on Maps to fax to  
John Morris on Monday. Compiling  
Soil Gas info and PID info.

1800 Compiling GC info on maps.


1930 Finished working on Site related  
information.

End of Shift

9/24/93 (10.5 hrs)

DAY 16 SATURDAY 25 Sept 93

- No JOB RELATED ACTIVITY -



DAY 17 SUNDAY 26 SEPT 93

1300 Finish Soil descriptions,  
to Compiling information for  
2200 Site Closeout.

Y. O. G. P. H. 25 Sept 93 (6 hrs)

Day 18 Monday 27 SEPT 93

0800 Check out of Hotel. Go to base to FAX info to San Antonio and meet with Surgeon (Mr. Narsen).

0830 Mr. Narsen arrives at site. Make copies of sites for him, then walk the three sites to identify all points to be located.

0910 Complete walking the site. Fill in soil on graded hard auger locations and secure our cones.

0920 Go to Civil Engineering and FAX maps to John Morris.

Call Lab - Speak w/ Doug Shuley and inform him of the end of Phase I investigation.

Call Driller - Leave message for Vince that we are ending.

Phase I investigation. Will call him when we are ready to schedule the next work.

0930 Then John Morris in San Antonio. He wants us to wait until a last-minute hotel is secured in Worcester before we drive there. Will call him back at 1300.

0945 Go to Roslyn Library to work on Worcester Sampling and Drilling Plan and to work on GC info and for M.R. and J.D. to review Worcester Work Plan.

1100 Phoned John Morris. Problem in Worcester will not be worked out quickly enough for us to go. Will check back in to Hotel. Will see if situation in Worcester will be worked out for tomorrow.

1300 Review data and compile info from Roslyn Field work. Begin to pack up info.

M.R. and J.P. return to Site to inventory and pack supplies to await future work.

DAY 19 TUESDAY 28 SEPT 93

0830 Speak w/ John Morris. Will depart Roslyn AHS today. Will need to make a Scope change to complete work at Roslyn.

J.A. and M.R. go to Roslyn AHS to seal and store Equipment until we return.

1000 Go to Station to brief Cpt Johnson on situation and insure supplies are stored OK.

1100 Depart Roslyn, New York for Airport. Turn in vehicles and proceed to Airport.

2230 Arrive in S.A. - Roslyn Phase I over.

~~Paul E. Pugh~~ 4/27/93 (3 hrs)

~~Paul E. Pugh~~ 4/28/93

# PHASE II FIELD WORK

Roslyn ANG-S

BEGIN: 6 April 1994

END:

Crew: EARL E Parker II  
MARIC Escobar  
JOE Byrd.

## OBJECTIVES:

- Remobilize Equip and Subcontractors
- Complete Soil Sampling
- Install Piezometers (3)
- Complete deep soil borings (3)
- Install Monitoring Wells (3)
- Obtain Water samples (2 rounds)

## Subcontractors:

Soil Mechanics - Soil Drilling  
Big Apple Testing - Well Drilling  
NYTEST - Analytical Laboratory  
Pratap NARSU - Surveyor

SUN	MON	TUE	WED	THU	FRI	SAT
3	4	5	6	7	8	9
~	~	TRAVEL TO New York	Report to State Inventory Equipment Check drilling locations.	Drilling Soil Samples 01-002 BH 02-003 BH 03-005 BH BG-001 BH	Complete analytical data	Job rehab Local Piezometers Meet Big Apple Drilling Schedules
10	11	12	13	14	15	16
Survey PZ locations.	Prepare for drilling work	Drill core annulus Deposit Supplies Begin PZ-1 (to 70' BLS)	Drill PZ 1 3 Attempts. PZ 2 - 65' BLS PZ 3 - 65' BLS PZ 4 - 85' BLS	Recon again for O-DEX drilling Obtain Equip	Job rehab Organize and Obtain Equip	Job rehab Organize and Obtain Equip
17	18	19	20	21	22	23
Activity Meet w/ Jeff from BK APPLE	Continue Prep for O-DEX drill. PZ-1	Drill PZ-1 SS - 100'	Drill PZ-1 to 160'	Complete at PZ-1 Clean site at PZ-2	Complete at PZ-1 Clean site at PZ-2	Complete at PZ-1 Clean site at PZ-2



WEDNESDAY DAY 1 10 April 94

0815 Arrive at Roslyn ANG-S.  
Check in and brief Cpt Larry  
Johnson on investigative program.

Obtain equipment and inventory  
box.

0945 Walk the sites. Check drilling  
locations for obstructions.  
Restate locations for Soil Sampling.

01-002 BH

02-003 BH

03-005 BH

BG-001 BH

1030 Brief Cpt Johnson on investigation  
plan. Will sample 4 boreholes tomorrow  
and finish on Friday if necessary.  
Will begin drilling piezometers  
Monday (11 Apr 94).

1100 Receive a call from Lee Perry  
(ANGRC-CEUR/PM). Briefed him

on the progress of the investigation  
and about the sampling plan for tomorrow.  
Mr. Perry requested preliminary data,  
soil gas survey results and field screening  
results from previous activities.

Faxed Soil Gas Survey and PID readings  
from previous investigations.

1130 Called John Morris to inform him  
of phone conversation with Lee Perry.

1145 Depart Station to go to NYTEST  
to meet with Joe Dockery to coordinate  
sampling and pick up sampling kit.

1155 Arrive at NYTEST. Coordinated sampling  
plan for SI. Discussed analytical  
needs. Joe Byrd and Mark Escobar-  
tour the lab. Pick up sampling  
kit for tomorrow's sampling.

1400 Go to Air-Wald to pick up Ultra-Air  
then to Store for Equipment.

1730 Return to Hotel. ~~End of Day~~

8 hrs

16 April

Thursday Day 2 7 April 98

0730 Depart hotel for Station.

0740 Arrive at Station. Prepare for drilling activities.

Mark Escobar sets up GC in room provided by the Station.

Joe Byrd begins to clean sleeves and end caps.

0830 Soil Mechanics drillers arrive at the site. Robert Rogers is the driller again. Same crew from soil mechanics.

Walk the site with drillers.

0915 Drillers move to 02-003 BH

Safety Meeting: Enol Parker

Joe Byrd } optech

Mark Escobar

Robert Rogers } Soil Mech.

1000 Begin Drilling at 02-003 BH  
WEATHER: Cloudy, Drizzle, Windy.

Temp: 48° High up to 55°

Calibrate PID: 100 PPM Isobutylene

1015 02-003 BH, Int 1

0.5'-2.0' BLS

STP 5 - 0.5'-1.0' BLS

4 1.0'-1.5' BLS

5 1.5'-2.0' BLS

PID opening: 0.0 PPM

ATHA: 0.0 PPM

Fill material Pack brown to black

charcoal grains Sand, silty sand,

silt w/ large angular gravel. Some

clay particles. Poorly Sorted.

% Recovery: 70%

1025 Interval 2 5.0'-6.5' BLS

SPT 6 - 5.0'-5.5' BLS

7 - 5.5'-6.0' BLS

7 - 6.0'-6.5' BLS

PID opening: 1.7 PPM

ATHA: 3.3 PPM

Slight odor during drilling.

PID at Drill hole at 10.5 PPM

Brown Silty sand and silt. Moderately cohesive with only little clay. Gravel.  
% Recovery: 60

1030 Interval 3 - 10.0' - 11.5' BLS  
SPT - 19 - 10.0 - 10.5'  
24 - 10.5 - 11.0'  
19 - 11.0 - 11.5'

P10 Opening: 1.6 PPM  
ATHA: 2.5 PPM

Brown to black silty sand. Mostly a fine sand with little clay. Angular gravels.  
% Recovery: 80%

1040 Complete drilling and sampling at 02-003 BH. Move to 01-002 BH

1055 SET up on 01-002 BH

1100 01-002 BH, Interval 1  
0.5' - 2.0' Feet BLS

SPT - 15 0.5 - 1.0' BLS  
- 12 1.0' - 1.5' BLS  
- 17 1.5 - 2.0' BLS

P10 Opening: 0.0 PPM  
ATHA: 0.0 PPM

Fill material. Brown sandy silt, clay with gravel particles. Poorly sorted sand.  
% Recovery: 90%

1110 Interval 2 5.0 - 6.5' BLS  
SPT - 3 - 5.0 - 5.5' BLS  
- 9 5.5 - 6.0' BLS  
- 13 6.0 - 6.5' BLS

P10 Opening: 0.0 PPM  
ATHA: 0.0 PPM

Brown sand, silty sand and gravel. Very poorly sorted sand with very little clay.  
% Recovery: 80%

1125 Interval 3 10.0 - 11.5' BLS  
SPT - 26 - 10.0 - 10.5' BLS  
- 37 - 10.5 - 11.0' BLS  
- 43 - 11.0' - 11.5' BLS

P10 Opening: 0.0 PPM  
ATHA: 0.0 PPM

Brown to black silty sand, sand with large gravel particles. Very little clay. Very poorly sorted sand.  
% Recovery: 70%



Recalibrate PIP: 100 ppm Isobutylene  
Weather: Clearing, No Rain Temp 58°

1140 Interval 3, DUPLICATE

11.5-13.0' BLS

SPT 25 - 11.5'-12.0' BLS

27 - 12.0'-12.5' BLS

25 - 12.5'-13.0' BLS

PID: 0.0 PPM

ATHA: 0.0 PPM

Sand. Brown sandy gravel. More rounded  
gravel. Some silt. Very little clay.  
Very poorly sorted sand.  
% Recovery: 90%

1150 Complete Drilling At 01-002 BH.  
Drillers will Decan Aggers before  
proceeding.

1210 Drillers complete Decan. Move  
to 03-005 BH

Set up over 03-005 BH

Recalibrate PID: 100 PPM Isobutylene

1210

Interval 1

0.5-2.0' BLS

SPT

- 7 -0.5-1.0' BLS

- 10 1.0-1.5' BLS

- 14 1.5'-2.0' BLS

PID Opening: 0.0 PPM

ATHA: 0.0 PPM

Lt. Brown sand Silty sand with  
some clay particles. Very poorly  
sorted sand with small angular  
gravel and larger rounded gravel particles  
% Recovery: 80%

1220

Interval 2

5.0'-6.5' BLS

SPT

- 3 5.0'-5.5'

- 6 5.5'-6.0'

- 7 6.0'-6.5'

PID Opening: 0.5 PPM

ATHA: 0.0 PPM

Lt. Brown very poorly sorted sand,  
silty sand and clayey silt. Abundant  
gravel and clay.  
% Recovery: 70%

Weather

turning cloudy again

Temp: 60° More windy

1240 Interval 3, 10.0-11.5' BLS  
SPT - 15 - 10.0 - 10.5' BLS  
- 21 10.5 - 11.0' BLS  
- 14 11.0 - 11.5' BLS  
Pio Opening: 0.0 PPM

ATHA: 0.0 PPM  
Lt. Brown sandy silt, silt, slightly  
cohesive sand with fewer gravel  
particles. Very poorly sorted silty  
clay w/ sand.  
% Recovery: 100 %

1250 Interval 3, 11.5-13.0' BLS  
MS/MSD

SPT - 9 - 11.5 - 12.0' BLS  
- 11 - 12.0' - 12.5' BLS  
- 10 - 12.5 - 13.0' BLS  
Pio Opening: 0.0 PPM  
ATHA: 0.0 PPM  
% Recovery: 100 %

1300 Complete drilling at 03-005 BH  
Moving to BG-001 BH.  
Recalibrate Pio: 100 PPM Isobutylene

1320 BG-001 BH, Interval 1  
0.5' - 2.0' BLS  
SPT - 2 - 0.5 - 1.0' BLS  
- 2 - 1.0 - 1.5' BLS  
- 4 - 1.5 - 2.0' BLS  
% Pio Opening: 0.0 PPM  
ATHA: 0.0 PPM  
No Asphalt cover, Dark, organic rich  
sand, silty sand and gravel with  
some clay. Very gravelly sandy loam.  
% Recovery: 70 %

1330 Interval 2 5.0' - 6.5' BLS  
SPT 8 - 5.0 - 5.5' BLS  
11 - 5.5 - 6.0' BLS  
16 - 6.0 - 6.5' BLS  
Pio Opening: 0.0 PPM  
ATHA: 0.0 PPM  
Lt. Brown sand mostly sand with  
some silt and gravel patches.  
little clay.  
% Recovery: 80 %

1340 Interval 3, 10.0' - 11.5' BLS  
 SPT - 11' - 10.0 - 10.5' BLS  
 - 12 - 10.5 - 11.0' BLS  
 - 9 - 11.0 - 11.5' BLS  
 PIO Opening: 0.0 PPM  
 ATHA, 0.0 PPM  
 Lt. Brown sand, silty sand w/ gravel  
 Saturated sand with very little clay  
 % Recovery: 70 %

1350 Finish drilling at BG-001 BH  
 Drillers prepare to Gout holes.  
 Drillers clean equipment.

1400 E.P. and J.B. prepare to obtain  
 Field Blank #7

1430 E.P. and J.B. prepare to obtain  
 Equipment Blank #7

1435 Drillers move drums to drum  
 Area. Drillers finish work  
 and depart Site.

4 Drums added 02-003 BH, 01-002 BH  
 03-005 BH, BG-001 BH.

1500 E.P. and J.B. conduct Site Cleanup  
 E.P. prepares chain-of-custody form  
 for samples.  
 Joe Byrd secures boreholes.

1600 Earl and Joe complete site clean  
 up and samples are ready to  
 go to the lab.

Mark Escobar continues to Analyze  
 samples with the GC.

1605 Earl Parker and Joe Byrd depart  
 station to go to lab to drop  
 off samples.

Mark Escobar remains at Station  
 to complete GC analysis.


1610 Arrive at Lab.  
 Inventory samples and sign over  
 custody of samples to NYTEST.

1630 Depart Lab for Hbkl.

1640 Arrive at Hotel. Mark Escobar has not yet arrived.

1650 Mark Escobar calls. He has returned to Hotel.

Complete work related activities for the day. Prepare to eat a late lunch.



E. J. Escobar 4/7/94 (P.H.S.)

FRIDAY

DAY 3

April 8 '94

0800

Arrive at the Station.

E.P. begins to prepare daily report to ANGRC summarizing yesterday's activities. Fax to PM.

M.E. summarizes the analytical information on last years activities to FAX to Project Manager (Mused)

J.B. Inspects site it insure clean and abandoned holes are closed safely.

0845

E.P. and J.B. go to site to measure in locations of boring locations to put on site map for ANGRC.

Locate Piezometer locations. Mark on the ground for inspection.

0930

FAX locations and field screening results at yesterday's activities and summarized information on last years analytical results to ANGRC / CEUR PM (Leo Perry).

1040 Walk Piezometer locations with  
Cpt Larry Johnson (Station Civil  
Engineer) Tentative approval on  
site is obtained.

All locations are as shown on  
work plan. PZ 3 is moved  
30 feet west to put it on the  
asphalt away from overhead  
obstructions from nearby trees.

1100 Big Apple drillers arrive at the  
site. Ed Palma and John Barnes  
arrive to inspect the drilling  
sites and discuss the drilling  
program.

Walk the 3 Piezometer sites.  
All are fine with the drillers.

Inform us of a delay in  
his mobilization to the site.  
They are delayed on a project  
and will not be able to get

to Roslyn until Wednesday.  
This will require a two day  
delay in the drilling at the  
piezometers.

1215 Big Apple drillers take a  
California-style split spoon  
samples to check its fit on  
their equipment and depart  
the site.

Try to call John Morris - Optech,  
Lee Perry - ANGEL/CEUR and Bill  
Hedberg - HAZWARR to inform  
them of the delay. Everyone  
is out of the office.

1230 Depart Site for lunch

1315 Arrive at the Station. Call  
John Morris and inform him of  
the delay. Will use the time to  
prepare for drilling, organize previous  
data and survey in the



piezometer locations for groundwater flow direction determination.

Call Lee Perry. Inform him of the delay. He will postpone his arrival to Roslyn.

1410 Reach Bill Hedberg at HAZWARR.

Discuss delay in drilling program. He will postpone his arrival to Mon (18 Apr). Discuss aspects of the investigation. i.e. rationale for deep borings, Groundwater flow direction.

1430 Discuss drilling procedures w/ Cpt Johnson, specifically, disposition of clean soil cuttings during the drilling of piezometers and monitoring wells.


Soil Cuttings that do not register contamination during field screening (ie P10 and field GC) will be

placed on the soil spill piles to be used to backfill Station Activities. All contaminated soil during drilling will be drummed and stored.

1540 Prepare to close activities for the weekend. Station has a drill weekend scheduled. Insure equipment is secure and site is clean.

1550 Depart site.  
S.P. and M.E. go to FED-EX drop for package to the office.

1615 Arrive at hotel.  
End of the days activities



Ead Elshout

4/8/94

7.5 NO

SATURDAY

DAY 4


9 April 94

✓

✓

✓

No SITE RELATED ACTIVITIES



Seal El Sub 4/7/94 01x

SUNDAY

DAY 5


10 April 94

✓

✓

✓

No SITE RELATED ACTIVITIES





Seal El Sub 4/10/94 0.0 hrs

Monday DAY 6 11 April 94

0830 Depart Hotel to go to Station.  
E.P. J.B. and M.E. check site  
after a drill weekend. All  
boring locations are secure.

0900 Talk to Cpt Johnson. Obtain  
a transit and stadia rod  
to shot elevations of Perimeter  
locations. Using benchmarks  
from previous work to shot  
elevations.

Set up transit at Road by  
IRP Side No. 3.



Station 1

Shot BM N.E. Foundation bolt  
SE Corner Post 202.07'

BM 202.07' Rod: 4.48'  
INST. HEIGHT: 206.55'

PZ1 Rod: 4.69 ∴ PZ1 = 201.86'

PZ2 Rod: 0.80 ∴ PZ2 = 205.75'

Station 2

Shot BM & Catch Basin Run  
Side No. 1 201.57'

BM 201.57 Rod: 7.38  
INST. HEIGHT: 208.95

PZ3 Rod: 11.86 ∴ PZ3 = 197.09  
01-004BH Rod: 6.56 ∴ 004BH = 202.39  
Surv = 202.45



1130 Call Bill Loder concerning Worcester ANG's SI. Tried to reach John Richardson at Barnes but he was not in. left a message.

1200 Called Lee Perry but he was not in.

1215 DEPART SITE for lunch.

1330 Returned to Hotel to phone Ed Apple. No response from Ed Palma. Will call again at 4:00 pm to check status on drilling.

1400 Depart for Station.

1410 Arrive at Station. Continue Analytical Analysis of drums.

1535 Call Bill John Richardson at Barnes ANG's, Mass and discuss issues concerning Worcester ANG's.


1600 Call Ed Palma with Big Apple Testing. He said they will be ready to begin drilling on Wednesday (4/13). Will be on site at 0800 that day.

1630 Begin to pack up for the day at the station. All items are ready for drilling to begin.

1645 Depart Station

1655 Return to Hotel.

1900 Compile Analytical data on Soil stored in drums.



LEE LUTHER 4/11/68 8 hrs

TUESDAY DAY 7

12 April 94

No major activities at the station.

Drilling of Piezometers to begin tomorrow.

Complete preparations for drilling.

- Maint/Cleaning of P10

- All valves for field GC are

decontaminated and cleaned.

- Systems check on LEL / oil water interface probe.

Appraisal of PZ1 drilling location for tomorrow activities.

Called Lee Peim (ANGS/CEUR PM) on status report, drilling schedule and projected activities over the next few weeks.

Preparation of Worcester ANGS activities for Bill Loder.

Sam E. D. L. H. 4/12/94 (8 hrs)

WEDNESDAY DAY 8

13 April 94

0730 Depart H41 for Station

0740 Arrive at station

Prepare for drilling.

Set up field GC

0840

Big Apple drillers arrive.

WALK through the site. Show the

drilling locations and talk

about the contaminants found.

0900

Supply truck arrives with drillers

supplies. PVC, grout, sand, ect.

Begin to unload supplies

M.E. Van, get the field GC setup.

Begins to calibrate.

J.B. obtains a composite sample

from the three drums of soil

cuttings from the piezometer

drilled last phase. We will

Analyse the soil for BTEX for

disposal disposition.

0930 Drillers continue to unload equipment and set up a dewatering system to clean augers.

M.E. begins to analyze composite sample from soil cuttings from PZ1 location.

WEATHER: Foggy, damp, and cool. Temp: 45°, very foggy. No wind. Expect rain later in the day. Hi - mid 50's.

1015 Drillers move to dewater area and begin to clean augers.

1130 Drillers continuing to clean augers. GC analysis of soil from previous drilling indicates clean soil. No BTEX or any peaks on GC. Will dispose of soil in drums at the backfill pile as requested by COT Johnson.

1150 Complete cleaning augers. Break for lunch.

1215 Move to PZ1.

Safety Briefing  
Earl Parker } OPTech  
Joe Byrd }

John Barnes }  
John Barnes II } BIG APPLE  
William Figueroa }

Review site history and possible contaminants (hydrocarbons). Possible site hazards, emergency procedures, hospital route, eye wash station, phone location.

Weather hazards.

WEATHER: Overcast and drizzle.

Winds are very light out of the east. Drizzle. Temp: 45°

1230 Begin to drill at PZ1.

Calibrate P10: 100 PPM Isobutylene

1250 Drilling to 20' BLS

Sand and silt. No odor. P10 reads

0.0 PPM. No evidence of contamination

1320 Drill to 60' BLS. 50' BLS  
 Return cuttings indicate sand and silt with some clay layers. No moisture, no odor. P10 = 0.0 PPM.  
 Drizzle begins to increase to a light rain. Drilling beginning to go slower. Encountering rocks and cobbles in the surface return.

1400 Drill to 68' BLS 57' BLS  
 Drilling becoming more difficult as more cobbles are encountered. Return indicates rounded cobbles and gravel in a sandy-silly matrix with clay.

Drillers are pulling out auger flights to check the lead auger.

Lead auger lost its "door" that prevents cuttings from moving up the auger. Door was wood and they will need a steel door to prevent

cuttings from moving up the augers.

1415 Drillers do not have a steel door. DW will have to be fabricated. They can proceed no further today. Drillers depart site.

1430 Soil from previous P2 location is dumped on the cuttings pile. Three drums of cuttings were produced so far today.

ME is analyzing soil for BTEX. Soil had no P10 readings or odors.

1430 Analysis of Soil in Drum A  
 Strait line - no peaks.

1435 Analysis of Soil in Drum B  
 Strait line - no peaks.

1400 Analysis of Soil in Drum C  
 Strait line - no peaks

1450 Begin to deposit PZ1 soil cuttings  
in the backfill pile.

1530 Complete soil transfer. ME begin  
to pack up field GC station.


EP and JB cover soil at drill  
rig and prepare to close site  
for the day. Rain continues.

1630 Site cleanup complete. Prepare  
to depart the Station.

1645 Return to Hotel. Call Ed Palma  
w/ Big Apple to discuss today's  
progress. He said he will be  
at the site tomorrow to see how  
the drilling will continue. Drilling  
options (O-DEX) may be necessary  
due to the boulders being encountered.

1650 Call Lee Perry (ANGRC/CEUR PM)  
and inform him of the days  
progress.

1800 Call John Morris in Hawaii to  
inform him of the days progress.  
He is not in. Left a message  
for him to call me back.



Ed Elmer  
4/18/94 8 hrs



THURSDAY DAY 9

14 April 94

0730 Depart Hotel for Station.

0740 Arrive at Station. Prepare for daily drilling at PZ-1.

ME sets up field G.C.

0835 John Barnes (Driller) arrives at the site. Says the crew is still fabricating the steel door and will be out soon.

1000 John Barnes Jr. arrives at the site and starts the rig. Crew arrives with welded steel door and attaches to the rig. Preparing to begin drilling.

Safety Meeting:

Earl Parker

John Barnes Jr.

Ben William Figo

Discuss today's drilling. Review hazards at the site.

Weather: Clear, Sunny and Mild.  
Temp: 65 Hi today low 70's  
Winds out of the SW. very slight now but will increase throughout afternoon.

1005 Begin to Assemble Auger Flights in the hole.

Drill down to previous days depth 57' BLS (NOT 70' BLS). Drill an additional 2 feet. Very difficult, then no progress. On a boulder.

1040 Retrieve Auger Flight.  
Lead Auger sheared a tooth.  
Cannot penetrate and deeper at this location. Must move to attempt another drill.

Moving 10' East to Attempt again

1100 Begin to drill another hole for PZ-1.

1108 At 40' BLS Attaching next 20' length of Augers.

Soil is a poorly sorted sandy silt with clay lenses and abundant gravel and cobbles. No odor or no PID readings from soil or drilling location.

1130 Encounter 57' BLS interval and encounter boulders again. Drilling very difficult.

1135 No progress. Drilling halted at this location.

Moving back to near original location to attempt to drill using small (3 1/4) inch augers.

1200 Set up over 3rd location to drill PZ1 using 3 1/4 inch augers. Changing drilling equipment to hold new auger size.

1210 Drillers take a short lunch break at the site.

E.P. calls Matt Alexander and explains the present situation at PZ drilling.

Calls John Morris but he is not in.

1230 Begin to drill again at PZ1 (third location) with 3 1/4 ID augers. 20' string to begin.

1300 Adding 15' of drill pipe. (Augers)

1320 Adding 20' of Auger.

1351 Adding 20' of Auger.

1432 Drilling going very slow and difficult. Hydraulic pop-off valve leak on the drill rig.

1530 Complete pulling and stacking augers 10' of the third attempt 85' BLS. Begin site clean-up activities.

Drillers will return tomorrow to begin  
O-DEX drilling at PZ-1.

1545 Drillers depart site.

1610 EP J.B. M.E. Complete site cleanup  
for the day - Break down field DC.  
Depart Site.

1630 Phone Leo Perry. He is not in.  
Left a brief message on today's  
results and will call him in  
the morning.

1635 Call Bill Hedberg. (HAZWRAP) he  
is not in. Left message and  
will call in the morning.

1640 Call John Swartwout (NYSDEC)  
to ask about deep boring requirements  
during SI at N.Y. Explained  
the O-DEX requirements at the  
site and about the proximity of  
the MW's in relation to the sites

And if deep soil borings would  
be necessary. After a review of  
the situation at the Roslyn SI,  
he said a continuous description  
of the subsurface soils during the  
installation of the MW's would  
satisfy NYSDEC requirements and  
the deep borings are not necessary.


1530 Dan Eaton (NYSDEC) called. (I  
was not in). Message said he  
will call me back.

1910 Receive a call from John Morris.  
Discuss situation at the station. Since  
O-DEX will be required and based on  
the information from the NYSDEC,  
we will propose to ANGRC that  
the deep soil borings be eliminated  
and use the information obtained  
from the installation of the MW's.

2030 Receive a call from Dan Eaton (NYSDEC)  
concerning O-DEX drilling procedures.



He was concerned with the 5-foot split spoon sampling with the O-DEX rig. He stated it was very time consuming and unnecessary for geologic classification. Geologic descriptions can be made from the surface return. He stated field screening was not possible. But NYSDOC would not require 5-foot or continuous split spoon sampling. Descriptions from surface return are acceptable.



East of 4/14/94

FRIDAY	DAY 10	April 15, 94
0730	Depart Hotel for the Site	
0740	Arrive at Station - Prepare for the days activities. M.E and J.B. Set up and calibrate field GC.	
0755	Call Leo Aray (ANGRC/CEUR PM). Inform him of the overall situation and conversations with John Swartwout and Dan Eaton (NYSDOC). Based on the concurrence of the State, the deep borings are eliminated from the field investigation.	
	5-foot interval sampling during the installation of the MW's will not be conducted with the split spoon. Geologic descriptions will be obtained from surface return during O-DEX drilling. If surface return shows contamination during field screening up with the PID or field GC, then	

drilling will stop to obtain a split-spoon sample for closer study and analysis using the field GC.

0830 Call Ed Palma w/ Big Apple. Drillers are obtaining equipment for O-DEX drilling. Will not be able to begin today. Will begin drilling on Monday. He will come out to the site this afternoon for status meeting.

1000 Begin to compile analytical data from previous investigation.

ME and J.B. are working with the field GC.

1100 Sean Walters (env Manager 106A PG) came by. Will be briefed on Boston investigation.

1130 Meeting with Sean Walters. Discuss last September's investigation and

analytical results. Discuss this investigation and the well drilling and sampling.

1400 John Barnes and drillers arrive at site to deposit drill rods and set up the rig for O-DEX drilling.

Will arrange for drill casing to be delivered on Monday to begin. Will expect drilling to take two weeks.

1440 Ed Palma from Big Apple will not be able to make it to the field.

1525 Drillers complete re-configuring drilling rig for O-DEX drilling. Begin to clean-up and service equipment for the weekend.

1545 Drillers depart the site.

1600 Call Lee Perry (ANGRC/CEUR PM). He is not in.

1610 Call Bill Hedberg (HAZWRAP), Inform him of the progress of drilling And give him a proposed work schedule. He may postpone trip till Monitor Wells are being drilled.

1630 Secure equipment and depart Station.

SOT

DAY 11

16 Apr 94

No work related activities

Bill Hedberg 4/16/94 8h

Bill Hedberg 4/16/94

20 h

Sun Day 12 Apr. 17, 94

No Work Related Activities

- Paperwork on Roslyn work

Mon Day 13 Apr. 18, 94

0800 E.P. and J.B. arrive at the Site. Mark Escobar returned to San Antonio yesterday 4/17/94. Begin to set up for work. ~~Call~~ Trouble with the Field GC. Air Flow knob is frozen closed. Waiting for driller to arrive at site. 0930 Call for Ed Palma at Big Apple. He is not in. Leave message for him to call me. Call Norma at office about contract. 0950 Contact Lee Perry. Talk to him about Friday and the conversation with Sam Walters (Sullfolk Engr. Co.). 1030 John Barnes is at the Site waiting for the delivery of the drill casing. 1040 Call Big Apple. Ed Palma is not in. Talk to Jeff Affarpour (president). He was not completely familiar with the situation. He will come out today.

Earl S. Lantz 4/17/94 (as hrs)



1115 John Barnes Jr. and crew arrive at the site. Begin to prepare for drilling.

1130 E.P. and J.B. depart site to go to FED-EX to send back field GC.

Eat Lunch

1300 Return to Site. Drillers inventorying drill casing, welding casing and lining up drill pipe in preparation for drilling.

1315 Call JEFF or Ed at Big Apple. Ed is not in and Jeff is unavailable. Jeff will be coming to the site this afternoon.

Drillers continue to weld casing and prepare drill pipe.

1500 Drillers complete preparations. The air compressor has not arrived. It is the last piece of equipment we are waiting on.

1520 Drillers depart the site. E.P. and J.B. wait for Jeff from Big Apple.

1530 Jeff Antkowiak from Big Apple arrives at the site.

Discuss the drilling program and cost and time. Jeff does not know all the details of the Agreement. Will have to discuss the situation with Ed Palma and John Barnes. E.P. lets him know Optech's position.

Will call him tomorrow (Tues) at 11:00 AM to insure all parties are in agreement as to the work to be performed.

1630 Discussion ends. Jeff departs the site. E.P. and J.B. depart the site.

*Wendy Edwards* 4/18/91 P.5  
hs

TUESDAY DAY 14 April 19, 94

0800 E.P. and J.B. arrive at the Station.

E.P. is left at the site to await drillers and J.B. goes to FEB-EX to insure field GC is sent back to HAZCO.

Now GC will arrive at Hotel this morning.

1 0845 John Jr. and helper (Bill) arrive at the site. Once the air compressor arrives, drilling can begin.

0900 Turn on the rig, making final preparations to begin drilling.

0910 J.B. arrives at the site. Field GC is off.

0915 Air compressor arrives at the site. offload and prepare for drilling.

0920 Safety Meeting  
Eael Paeke  
Joe Byrd  
John Barnes  
Bill Figueroa

Talk about O-DEX drilling system. John explains the process. identify hazards.

Weather: Sunny to partly cloudy and mild Temp: 60's high for today in the mid 70's. Sunny to P.C. chance (slight) of afternoon showers. Wind out of the south east at 10 mph.

0940 Begin to drill at PZ1

Casing	Feet BL	DESCRIPTION
0-10	0 - 5	Sand and gravel, small gravel with silt. Silty sand.
	5 - 10	Medium to coarse sand, very poorly sorted with silt and pebbles.
10-25	10 - 15	Silt, clayey silt. fewer gravel And fine sand to silt.

15-20 Clay, Silty clay with some fine and medium sand. few gravel.

1050 Compressor is stopping. Drilling is going very slow in the clay.

1100 Begin drilling at  $\approx 20'$  BLS  
Compressor quits again. Drilling halted so drillers can call for service

1115 E.P. goes to call Jeff at Big Apple.  
Says he has not been able to look into the drilling contract but will do so in the early afternoon.  
Asks if I can call back at 4:00 pm.

1135 Return to drilling location.  
Compressor is running so we begin to drill again.

20-25 Compressor out again.

Break for lunch so service man can fix compressor

1230 Service men arrive and begin to fix compressor

1330 Compressor back in operation.  
Begin to drill again

1340 20-25 Clay - silt and fine sand.  
Mostly clay and silt.  
Drilling progresses slowly.

1410 Stop to attach next casing.  
Casing interval 25-40' BLS  
Begin to drill

25-40 25-30' Silty clay, clayey silt w/ fine sand and gravel.  
30-35' Silty sand, some medium sand w/ pebbles. Intervals of clayey silt.  
35-40 Clay - silty clay. Very slow progress.

1550 Drilling for 30 minutes w/ no real progress in the clay.

1605 Drillers stop drilling. Prepare to remove hammer from the hole.

Having problems removing the air hammer. Cannot break drill pipe sections loose w/ O-DEX casing.

1615 Call Big Apple - Talk to Ed Palma. He is back in the office and will return the signed contract to Norma today.

Informed him of the difficulty we are having w/ O-DEX and the clay. Says he will talk to John Barnes about the situation.

I will talk to John Morris and Lee Perry tomorrow and we will discuss how to proceed.

1700 Drillers are still attempting to remove air hammer. A drill pipe joint has

frozen and they are trying to break it free.

1730 Pipe broken free. Continuing to retrieve air hammer.

1815 Remove air hammer for inspection. Air jets on the bottom of the hammer were clogged with clay preventing air from lifting cuttings from the bottom of the hole. May account for the slow rate of drilling.

Air hammer cleaned out. Appears to be working properly once cleaned out.

1830 Begin to re-assemble drill string.

1900 Drill string is reassembled and drilling continues.

35'-40' Continue in clay changing to a sandy silty clay.



1905 Stop to attach next casing.  
Casing interval 40' - 55' BLS

1928 BEGIN next 15' Interval (40'-55')  
40-45' Sandy - clayey silt. silt with  
medium to coarse sand and small  
gravel. More gravel to bottom.  
45-50' Sand, medium to fine sand with  
silt and small gravel. Silty  
sand near bottom. Gravel  
throughout.

50'-55' Fine sand and silt. Small rounded  
gravel. Sandy silt. Sand, fine  
to medium w/ silt. fewer gravel.

1940 Complete 15' interval  
Pack up for the day

1950 Prepare to depart site

2000 Return to Hotel.

~~\_\_\_\_\_~~

Earl E. Fawcett 9/19/94 (115 hrs)

WEDNESDAY

DAY 15

APRIL 20, 94

0800 Arrive at the Station.

Prepare and file progress report to

Lee Perry.

J.C. Set up and calibrates field

GC.

0835 Drillers arrive at the site and set  
up for drilling.

Safety Meeting =

Earl Parker

John Barnes

Bill Fogaro

Review drilling and safety considerations  
at this site.

WEATHER: Sunny, clear and mild.

Temp 60°, Hi: Low 70's. Clear

to only Partly Cloudy and winds

out of the southeast/southwest

at 5-10 mph in afternoon.

0850 Drillers attach the next 15'  
of well pipe and casing.

0945 Begin to drill next 15' Interval  
Interval 55' to 70' BLS

55'-60' Drilling proceeding very very  
slowly. Air hammer seems  
to be plugged with clay  
once again

1000 Drilling stopped.

Pulling up drill pipe to look at Air  
hammer.

1035 Air hammer is clogged with clay.  
Will clean it out again.

1110 Phoned Matt Alexander in office to  
give status.

1130 Air hammer clean and re-assembled.  
Drill stem lowered into hole and  
begin welding casing to continue  
drilling.

1210 Complete welding drill casing.  
Prepare to drill 55'-70' BLS Interval

1215 55'-60' Sandy, silty, gravelly w/  
some clay. Mostly silty sand.  
60'-65' Clayey, sandy silt w/ gravel.  
Small rounded gravel. Sand and  
clay.

65-70' Silt, clayey, sandy silt w/ small  
gravel.

1235 Stop drilling to add next 15' of  
casing and drill pipe.

1240 Call Matt Alexander and John Morris  
Explain progress. Decide to continue  
as is.

1250 Drillers attaching next drill pipe.

1310 Break for lunch. Drillers welding casing.

1330 Complete welding casing.  
Prepare to drill interval 70'-85' BLS

1340 70-75 Silt, clay and sand w/ gravel.  
Mostly silty fine sand.

75'-80' Silty sand. Fine to medium sand with silt and gravel.

80'-85' Sand, Medium to coarse sand. Very little clay and silt. Larger pebbles (fragments) near the bottom.

1400 Complete drilling interval. Break to attach next 15' casing interval.

1410 Pulling air hammer for inspection

1435 Air hammer is fine. Air jets are unclogged. Will re-construct drill string and prepare for the next interval.

1510 Complete welding drill casing. Begin next interval 85'-100'

85'-90' Medium to fine silty sand. Little clay and fine gravel. More coarse near bottom with more gravel fragments.

90'-95' Medium sand with increasing rock fragments. To gravel interval. Grading to more medium and fine sand near the bottom.

95'-100' Sandy to sandy silt. Becoming more silty w/ clay and gravel fragments. Fine sand, silt and clay.

1545 Complete 15' interval. Drilling began to slow near the bottom of the interval.

Drilling is becoming slow due to the fact that the air pressure to lift the cuttings is becoming low.

Since air jets are plugged to increase the pressure on the bottom jets to prevent them from clogging, the hammer cannot cut and lift at the same time. The driller cuts several inches, then lifts the hammer to blow out the cuttings. Drilling is very slow.

The Drillers have a larger compressor coming tomorrow to solve this problem.

FRIDAY

DAY 17

April 22, 94

0800

E.P. and J.B. Arrive at the Site.  
E.P. prepares daily progress report and sends to ANSAC/CECE  
J.B. sets up the Field GC.

0845

Drillers Arrive at the Site. Site clean-up at PZ-1.

Weather: Sunny and cool. Hi-mid 60's.  
Sunny all day and breezy. Temp: 55°

1000

Continuing site clean-up. Air hammer is out. Must get a new one prior to continuing drilling.

WL at PZ-1

WL = 141.92' below MP  
- 1.20 MP  
140.72' BLS

1030

Begin to move equipment to PZ-2.  
Moving soil in dunes to fill pile.

1215

John Barnes and Ed Palma come to the Site. Bring lunch and talk with John Barnes, Jr. Will call them later.

1430

Take WL at PZ-1.  
WL = 141.86' below MP  
- 1.20 MP  
140.66' BLS

PZ-1 location is clean.

1500

Talk to John Barnes Sr. Air hammer will be in on Sat at 8:00 am. We will drill tomorrow.

1530

Drillers continue to prepare for drilling at PZ-2. Prepare air hammer for repair.

1615

Drillers go as far as they can today. Prepare to secure the rig for the night. J.B. breaks down field GC.

1630

Depart Site for the day.

Ed. E. Lark 4/22/94  
8.5 hrs

145-150' Air pump blows water and mud out of hole.

Sand and gravel. Sand is wet. Medium to fine sand.

150-155 Sand and small rounded gravel. gravel increasing with depth.

155-160 Sand and gravel. Coarse to

Medium sand with rounded gravel. Lt. Brown clay and silt at 156'. Saturated clay with angular pebbles. Gravel to sand at 158'. Sand and Gravel at bottom

1600 Complete 15' Interval. Reached target depth of 160'. Actual = 158.5' BLS.  
WL.  $\approx$  148' BLS


1615 Air hammer retrieved and is broken. Will have to obtain another Air hammer prior to beginning work at P22. Begin to secure site for the day.

1635 Drillers depart site. Will construct the well tomorrow and move drilling operation to P22.

1700 J.B. secures field GC and EP completes site cleanup for the day. Depart Site.

Call Matt Alexander and inform him of the days progress.

2130 Call John Morris and inform him of status of drilling program.



Earl E. Pugh

4/21/91

8.5 hrs



110-115 Coarse sand and gravel. Some silt and fine sand.

1108 Complete 15' interval. Begin to attach the next 15' interval.

1130 John Barnes Sr. arrives at the site. Brings back for crew.

1145 John Barnes departs site

1155 Begin next 15' Interval.  
Drilling 115' - 130' BCS  
115'-120' Sand. Medium to fine sand and silt w/ gravel and rock fragments. Turning to sand and rounded gravel near bottom.

120'-125' Sand, silt, and abundant quartz rock fragments.  
Drilling going slow. Sandy silt and gravel near bottom.

125'-130' Fine sand, silt, and clay.  
Mostly silty clay. Very clay. Medium to coarse sand w/ gravel and rock fragments w/ silt.

1240 Complete next 15' interval.

1250 Break for lunch

1320 Return to station. Begin to attach next 15' interval and weld casing.

1415 Complete welding next 15' interval  
Drilling 130' - 145' BCS

130'-135' Fine sand and silt. Some but few rock fragments and gravel. Some clay. Drilling is slow.

135'-140' Medium to coarse sand and gravel. Rock fragments.

Tending to get mix sand rich sand, coarse to medium sand with few gravel. Sham


beginning to come from hole.  
1440 Attach next 15' casing on to hole

1520 Begin to drill next 15' Interval  
Interval is 145' - 160'

1600 Drillers begin to break down for the day to obtain the larger compressor.

J.B. breaks down field G.C.

1630 Drillers depart the site. E.P. and J.B. depart the site.



See E. F. 10

8 hrs

THURSDAY

DAY 16

21 Apr 94

0800

Arrive at the Site.  
E.P. prepares and sends daily progress report for yesterday.  
J.B. sets up and carries up the field G.C.

0900

Drillers arrive at site. Begin to pull drill string to prepare air hammer.

0930

Air Hammer prepared. New air compressor arrives at the site.

0945

Begin to reconstruct drill string.

1000

Add next 15' extension casing. Will weld it into place.

1045

Begin to drill next 15' interval

Drilling

100'-115' B.C.S

100'-105'

Case sand and gravel.

some medium to fine sand with little silt.

105'-110'

Medium to fine sand and

silt w/ gravel throughout. More gravelly near bottom.

SATURDAY

DAY 18

23 Apr 94

0900

Arrive at Station

Go to PZ1 for W.C.

VL = 141.84 below MP

- 1.20 MP

140.64 below L.S.

J.B. Sets up the field GC.

0910

Drillers Arrive at the site. John Barnes Jr. is with them.

Safety Briefing:

Earl Parker

John Barnes, Sr.

John Barnes Jr.

Bill Figero

Discuss new drilling location hazards and safety considerations.

Weather: Sunny and mild. Winds out of the south east at 5 mph.

Temp: 49° High lower 60's.

0930

Welding on shoe to lead casing. Prepare for drilling. Attach Air hammer to drill rod.

1100

Begin to drill at PZ-2

Interval 0'-10' BLS

0'-5' Lt. Brown sand. Medium

sand w/ small gravel. Very little silt. Black specks (Fill)

5-10' Brown sand. Coarse to medium

sand w/ small gravel. Little

Silt. Poorly sorted sand.

1107

Stop at 10' BLS. Prepare to attach next 15' interval.

1132

Begin to drill next 15' Interval.

Interval 10'-25' BLS

10-15' Sand. Poorly sorted sand with

abundant rounded gravel at 11' BLS

becoming more sandy and silty.

15'-20' Poorly sorted medium sand and

gravel. Granite gravel fragments

Sand and abundant rock fragments



20'-25' More sandy with gravel. Medium silty sand with gravel. Sand and some silt with rounded gravel.

1148 Complete next 15' interval.

Begin to add next 15' casing.

1200 Break for lunch

1230 Return from lunch. Drilling continuing next 15' casing.

1245 Begin to drill next 15' interval  
Interval 25'-40' BLS

25'-30' Brown sand and gravel  
Poorly sorted silty sand  
with rounded gravel. Very little clay and little silt.

30'-35' Poorly sorted sand and gravel  
Silty sand and well rounded gravel. Silty, gravelly sand.

35'-40' Brown, slightly silty sand.  
Medium sand w/ gravel. Rounded gravel. Few rock fragments.

1254 Complete next 15' interval.  
Begin to add next 15' to casing

1345 Begin to drill next 15' interval  
Interval 40'-55' BLS  
40'-45' Sand and silt with abundant gravel and quartz rock fragments. Mostly sand, silty sand and gravel.

45'-50' Sandy silty gravel. Abundant gravel w/ rock fragments. Sandy and silty sand near bottom.

50'-55' Sand. Coarse to medium sand w/ gravel, becoming more fine sand and less gravel.  
Medium to fine sand w/ gravel

1400 Complete 15' interval. Begin to add next 15' casing.

1435 Begin to drill next 15' interval  
Interval 55'-70' BLS  
55'-60' Poorly sorted medium and fine sand w/ abundant gravel.

60'-65' Medium sand and gravel. Rounded to subangular gravel. Some but few angular fragments. Clayey silt at 63' BCS. Clay and silt w/ rock fragments and gravel. S.H. sandy silt and clay w/ fewer gravel. Silty clay and clay. Silty sand to fine sand and gravel at bottom.

65'-70'

1442 Complete 15' Interval. Begin to attach next 15' interval.

1313 Begin to drill next 15' interval.

Interval 70'-85' BCS

70'-75' Fine sand and silt w/ gravel. Few rock fragments.

75'-80' Fine to medium sand w/ silt

and rounded gravel. Silty

sand w/ some clay. Mostly

sand, silt and gravel.

80'-85' Sand, silt, few gravel.

Mostly medium to fine silty sand. Silty sand and gravel.

1330 Complete 15' interval. Begin to attach the next 15' interval.

1605

Begin to drill the next 15' interval

Interval 85'-100' BCS

85'-90' Sand and silt. Medium

to fine sand. Fine sand

and silt. Very little gravel

near bottom.

90'-95' Fine sand, silt and clay.

Some rock fragments. Mostly

fine sand, silt and clay (clay).

Fine sand and silt becoming

more coarse sand, gravel, and

rock fragments near bottom.

95'-100' Medium to coarse sand and

silt with abundant rock

fragments. Very poorly sorted

sand, coarse to fine w/ silt.

rock fragments.

1650

Complete 15' interval. Slow, return

to the surface was weak. Pulling


drill string to inspect air hammer.

1700 Hammer is fine. Will not pull  
drill string. Begin to secure  
site for the day.

1715 Site is secure. Drillers  
depart site.

1720 E.R. and J.B. depart site.

Call MAH Alexander with  
summary of daily activities



Carol E. Doherty 4/23/94

7.5 hrs

drill rig - Gus Rock - Brent Z28

CONTENTS		
PAGE NO.	REFERENCE	DATE
	BIG Apple Testing (718) 767-2900 Ed Palma	
	Hofel-Radlyn (516) 625-2700	
	ANACAC/GAR Leo Perry 1-800-237-9744 FAX (AVL) 8-0-858-8121 Conn (301) 981-8121	
	OPTech Calling Card: 1-800-950-1111-0-(AC)-Num-532-731- 2951-9181	
	John Morris 698-0388	
	FED-EX: 1342-6486-1	

SUN	MON	TUE	WED	THU	FRI	SAT
24 No Work Relax Activities	25 Complete P22. Move to P23	26 Drilling at P23 0'-70' BLS	27 Complete drilling at P23 Survey Set Wells and Set Screens at PS 5 and PS2	28 Survey Set Wells and Set Screens at PS 5 and PS2	29 Pull casing at PS2	30 Pull casing Set Screens and Grout at PS 1, PS2, PS3
1 No Work w/ Drills Well Levels	2 Drill at NW 01 to BLS BLS	3 Drill at to 135' BLS	4 Complete drilling to 155' Set Casing. Problems. Attempt to pull	5 Complete drilling to 155' Set Casing. Problems. Attempt to pull	6 Complete to Set PVC at 01-001 mud 03-001 mud Move to	7 No work Relax Activities
8 No Work Relax Activities	9	10	11	12	13	14
15	16	17	18	19	20	21

Sunday

DAY 19



4/24/94

/

|

/

No Work Related Activities



Earl E. Park

4/24/94



Monday

DAY 20

4/25/94

0800

E.P. and J.B. arrive at the site

J.B. Sats up field GC

E.P. prepares and fixes daily

progress report for Saturday and

prepares for today's activities

0845

Drillers arrive at the site

J.B. supervising the movement of clean

soil cuttings to the fill pile.

Drillers begin to pull drill stem to

inspect the Air hammer.

0918

Air hammer is exposed. Looks good.

Air was blown through and at

air jets were clean

0920

Begin to re-assemble drill stem.

J.B. calls insitu to delay

arrival of the Hermit.

0933

Drilling assembled. Adding next

15' casing. welding onto casing string.

1005

Begin next 15' Interval.

Interval

100-115' BLS

100-105' Very poorly sorted sand. Coarse to

fine sand w/ some silt. No gravel.

Few rock fragments. Becoming

more gravelly near bottom.

105-110' Very poorly sorted sand, silt and

gravel. Medium to fine sand

w/ silt and gravel.

110-115' Very poorly sorted sand and

gravel. Sand, silty sand, coarse

sand and gravel. Few rock fragments.

1028

Complete

15' interval. Attach next

15' casing and drill rod.

1106

Complete

next 15' Attachment. Begin to

drill 115'-130' BLS Interval.

115-120' Very poorly sorted sand and

gravel. Sand, silt and gravel

120-125' Sand and gravel. Medium

sand w/ gravel and a few

rock fragments. Some silt.

125-130'

Sand. Fine to medium sand w/

silt and gravel. Some rock fragments.

Mostly a very poorly sorted medium.

Sand

1130 Complete 15' interval. Attach the next 15' casing and drill pipe.

1205 Complete attaching next 15' interval  
Drill Interval 130'-145' BLS

130-135' Sand silt, and gravel with some dry clay.

135-140 Fine to medium silty sand w/ little dry clay. Few gravels and rock fragments. Medium sand w/ some silt and gravel near bottom.

140-145' Medium sandy w/ some fine sand, silt, and gravel.

1240 Completed next 15' interval. Break for lunch.

1315 Return to site. Drillers welding next interval to casing.

CPT Johnson brings Mr Ford, Station Supervisor on tour of work.

1340 Complete welding next 15' section

of casing. Begin to drill.

Interval 145'-160' BLS interval

145-150 Sand. Medium to fine

sand with gravel. Steam

and wet sand present.

150-155 Sand. Medium to fine sand w/

few gravel. No rock fragments.

155-160 Sand. Medium to fine sand w/

few gravel. Sand and gravel.

Concre to medium and fine

sand.

1605 Complete 15' interval. Reached target depth of 160' BLS. Actual depth is approx 159' BLS.

Drillers begin to pull drill pipe.

14-20 Call Optech. Talked to Matt

Alexander. Gave him a situation report.

1600 Moved rig and drill equipment to PZ 3 location.

1630 Began to secure site for the day.

1640 Obtained WL from P22  
WL = 144.46 above MP  
- 0.70 MP  
143.76' BLS

1650 Depart site for FEO-EX station to mail package.

1700 Return to Hotel.

1930 Call from Bill Hedberg (HAZWRAP).  
Informed him of our progress  
and of our tentative drilling schedule.

Says he will fly back to Tennessee  
and keep in touch w/ progress. Will  
plan to visit when MW drilling  
is almost finished to see well  
construction, testing, and sanding.

~~Earl E. Smith~~ 4/25/94

8.5 hrs

TUESDAY

DAY 20

4/26/94

0800 EP & JB arrive at the station.  
EP prepares daily progress report  
and FAX to ANGRC/CEVR.

Calls Lee Perry but he is not in.

JB sets up field GC.

EP prepares graphic log of P21  
and P22.

0915 Drillers arrive at site and prepare  
for drilling at P23.

0950 FAX P2 logs to Matt Alexander.

1000 Drillers having trouble with the  
AIR HAMMER. Performing maintenance.

1115 Complete maintenance. Sand inside  
hammer did not allow it to close  
properly. It was cleaned out  
and works.



# Safety Meeting

Earl Parker

John Barnes

Bill Fajiro

Discussed site 3 (P23) situation.

Weather: Cloudy and cold. Temp 45°  
It is mid 60's. Supposed to get  
partly cloudy. Mist in Am.

1130 Prepare to drill initial 10' interval

0'-5' Brown organic rich soil. Mud  
sand and silt w/ gravel and

rock fragments. Cobbles and gravel

5'-10' Gravel, cobble and rock fragments.

Becoming sandy and gravelly

to a very poorly sorted, mostly

medium sand and gravel at bottom

1138 Complete initial 10' interval.

Begin to attach next 15' interval.

1150 Call Matt Alexander to check in and  
give status report.

1220 Prepare to drill next 15' interval

Interval 10'-25' BLS

10'-15' VPS Sand, silt, and gravel.

Much gravel and rock fragments

15'-20' Sand, silt, gravel and rock

fragments. Rounded to subangular

gravel, cobbles and rock and

quartz fragments.

20'-25' Sand, silt and gravel. Gravel

and rock fragments. Steam

from perched water. A good

bit of steam. No water.

Wet sand and gravel.

1235 Complete 15' Interval. Preparing next  
15' interval.

1330 Break for lunch.

1330 Return from lunch. Drillers welding

next casing interval in place.

1350 Prepared to drill next 15' Interval  
Interval 25'-40' BLS

25'-30' Sand, silt, and gravel.  
 UPS sand and gravel.  
 30'-35' Sand, silt and gravel.  
 Some (few) rock fragments.  
 No evidence of water or  
 steam. Sand and gravel.  
 35'-40' Sand, silt, and gravel. Some  
 rock fragments. Mostly  
 a VPS sand and gravel.

1400 Completed 15' interval. Drilling  
 went very fast on this last interval.  
 Begin to attach next 15' interval.

1435 Complete attaching next 15' interval  
 Begin to drill 40'-55' interval  
 40'-45' VPS sand and gravel. Small  
 rounded gravel and rock fragments.  
 Sandy w/ rock fragments and  
 gravel near bottom.  
 45'-50' Coarse sand and gravel. Gravel  
 and rock fragments. Becoming  
 a bit more sandy near the bottom.  
 Coarse sand and gravel

50'-55' Sand and gravel. Rock fragments  
 becoming more sandy. Bottom  
 is a medium sand and silt  
 Mostly a medium sand with  
 rounded gravel.

1453 Complete 15' interval.  
 Preparing to attach next 15' interval.

1525 Begin to drill the next 15' interval  
 Interval 55'-70' BLS  
 55'-60' Sand and gravel. Rock fragments.  
 Fine to coarse sand and larger  
 sub rounded to subangular pebbles  
 and cobbles and rock fragments.  
 More sand. Fine to med sand.

60'-65' VPS sand, gravel and rock  
 fragments. Coarse, fine sand  
 and silt w/ gravel.

65'-70' Mostly VPS sand and gravel.  
 fewer rock fragments. Sand  
 coarse to medium, and silt  
 w/ gravel.

1543 Complete 15' interval.

Drillers break down and secure the site for the day.

1600 Drillers depart site for the day

E.P. and J.B. take water levels from P21 and P22

WL at P21

$$\begin{array}{r} \text{WL} = 141.66 \text{ Above MP} \\ - 1.20 \text{ MP} \\ \hline 140.46 \text{ ' BLS} \end{array}$$


$$\begin{array}{r} \text{Elevation LS} = 201.86 \\ - 140.46 \\ \hline 61.40 \text{ ' AMSL} \end{array}$$

WL at P22

$$\begin{array}{r} \text{WL} = 144.25 \text{ Above MP} \\ - 0.70 \text{ MP} \\ \hline 143.55 \text{ ' BLS} \end{array}$$

$$\begin{array}{r} \text{Elevation LS} = 265.75 \\ - 143.55 \\ \hline 62.20 \text{ ' AMSL} \end{array}$$

1630 E.P. and J.B. depart site.



Paul E. Fakh 4/26/94 8 hrs

WEDNESDAY DAY 21

4/27/94

0800 E.P. and J.B. Arrive at the station.  
EP prepares and sends daily progress report.

J.B. sets up and calibrates field GC.

0900 Drillers arrive at the site.

Manhanna and prepare for drilling at PZ 3.

Safety Briefing:

Eael Parker

John Barnes

Bill Figuero

Review safety issues.

Weather: Partly cloudy and breezy

Temp: 58° High: Mid 70's.

PC to chance at T-Storms late this afternoon. Winds from the Southeast at 5-10 mph.

0945 Begin to work next 15' Interval to casing.

1012

Begin to drill next 15' interval

Interval 70'-85' BLS

70'-75' VPS Sand and silt w/

some gravel.

75'-80' VPS Sand, silt, and gravel.

Few rock fragments. Mostly a

VPS sand and silt.

80'-85' Fine sand, silt and clay becoming

a clayey, silty sand w/ few

gravels. At 84' becoming a

fine to medium sand w/

some gravel.

1026

Complete 15' interval. Prepare to attach next 15' interval.

1107

Begin to drill next 15' interval

Interval 85'-100' BLS

85'-90' Fine to medium sand and

gravel. Some silt. Mostly

fine to medium sand and silt.

90'-95' Fine to medium sand and

gravel. Some silt.

95'-100' Fine to medium sand and silt

with rounded small gravel.



1123 Complete Drilling 15' interval.  
Begin to attach next 15' interval.

1155 Prepare to drill next 15' interval  
Interval 100'-115' BLS  
100'-105' Fine to medium sand and  
silt w/ gravel and few  
rock fragments.

105'-110' Fine to medium sand and silt  
w/ fewer small gravel. Mostly  
As silty fine and medium sand.  
110'-115' Fine to medium sand and silt  
w/ gravel and few rock fragments.  
Silty fine sand and gravel

1212 Complete the 15' interval  
Beginning to attach next 15' interval.

1220 Break for lunch

1250 Return to site. Begin to assemble  
next 15' interval.

1330 Prepare to drill next 15' interval  
Interval 115'-130' BLS  
115'-120' Fine to medium sand, silt,  
with gravel. Some rock  
fragments.  
120'-125' Fine to medium sand, silt, and  
gravel. Silty sand and gravel  
w/ rock fragments.  
125'-130' Fine to medium sand, silt, and  
gravel w/ fewer rock fragments.  
Mostly a gravelly, silty sand.

1350 Complete 15' interval. Begin to  
attach next 15' interval.

1420 Prepare to drill next 15' interval.  
Interval 130'-145' BLS  
130'-135' Fine to medium silty sand  
and gravel. Few rock fragments.  
135'-140' Sand and gravel. Fine to medium  
sand and gravel. Becoming  
more sand.

140-145' Medium sand and gravel  
mostly sand. Becoming wet  
At ~ 143' BLS. Medium sand  
w/ some small gravel. Steam.

1437 Complete drilling, 10' interval.  
Beginning to attach next 15' interval.


1508 Begin to drill next 15' interval.  
Interval 145'-160' BLS.  
145'-150' Medium sand and gravel.  
Some fine sand. Steam.  
Mostly a med. sand and gravel.  
150'-155' Medium sand w/ some fine sand and few gravel.  
155'-160' Medium to fine sand. Mostly medium sand. Few gravel.  
Mostly medium sand

1530 Complete 15' interval.  
Reached target depth of 160' BLS.  
Actual drill depth = 159' BLS

Drillers begin to pull drill rods and air hammer out of the hole.

1615 Drillers complete removing air hammer.  
Begin site clean-up.

1620 E.P. and J.B. Survey in the three piezometers.



STATION 1

IRP Site No. 3

BM: NE Foundation Bolt

SE Corner Post 202.07 AMSL

BM: 202.07

Rod: 4.27

∴ Inst Height = 206.34' AMSL

Top PZ1 Casing: 3.00 = 203.34' AMSL

Ground at PZ1: 4.45 = 201.89' AMSL

STATION 2

IRP Site No. 1

BM: Catch Basin Rim = 201.57

BM = 201.57 Rod = 6.10

$\therefore$  INST HEIGHT = 207.67

Top of Casing at P22 : 0.98 = 206.69' AMSL

Ground Surface at P22 : 1.67 = 206.00' AMSL

### STATION 3

BM & Catch Basin at 180 S.W. No. 1.

BM: 201.57 ~~Inst Rod: 12.52~~

INST HEIGHT ~~214.09~~

~~Top of Casing at P23 : 5.90 = 208.19' AMSL~~

~~Ground Surface at P23 : 6.52 = 207.57' AMSL~~

1650 Obtain water levels from P2's

P21 = 141.65' below Casing

$\therefore$  203.34 - 141.65 = 61.69' AMSL


P22 = 144.18' below Casing

$\therefore$  206.69 - 144.18 = 62.51' AMSL

P23 Water level could not be obtained. Still agitated from drilling. Will obtain the WL in the morning.

1715 E.P. and J.B. depart the Site.

1800 Call John Morris and inform him of the daily progress



End of Day 4/26/94 8.7 hrs

THURSDAY

ULY 22.

4/28/94

0800 E.P. and J.B. Arrive at the Site

Obtain Water Level Information

P21 141.65

P22 144.20

P23 139.33

Error was determined in yesterday's elevations to P23.

0900 Drive J.B. back to Hotel for departure from New York.

0915 EP return to the Site.

Drillers at site preparing to clean and set walls

Resurvey P23

BM E Catch Basin Rim at

IRP Site No 1. Elev 201.57

Elev. 201.57 Rod: 8.78

∴ Inst Height: 210.35

P23 Top Casing = 6.42 = 203.93'

Ground = 7.00 = 203.35'

Groundwater Elevations

MP

P21 141.65 (203.34) = 61.69'

P22 144.20 (206.69) = 62.49'

P23 139.33 (203.93) = 64.60'

1015 Drillers do not have the tool they need to pull the casing to expose the screen. It was shipped to the wrong location. They hope to extractor will be in tomorrow.

Begin to jet the well at P23. Sand heaved in the well and it will be jetted out w/ air in order to set the screen.

1100 Attached the dull stem at P23 to jet the sand out of the hole.




1140 Complete jetting sand from the hole. Beginning to pull drill rods to set screen. Add potable water to well to put head pressure.

1205 Begin to set the PVC screen at PZ 3

Attach 10' screen .010 w/ end cap  
Attach 15, 10' PVC sections

Total length of PVC well = 160'

PVC screen well extends 0.50' above land surface



1350 Complete setting screen. Set one bag (100 lbs) of sand pack in well to stabilize piezometer base.

Begin to move equipment to set piezometer PZ 2

1415 Begin to move 7 drums of soil to fill pile from PZ 3 drilling and jetting.

1440 Set up over PZ 2. Begin to jet sand out to bottom of O-DEX casing at 160 BUS.

1455 Complete air jetting. Begin to pull drill pipe to set PVC casing. Add potable water to put head pressure of boring sands.


1525 Complete pulling drill pipe. Begin to set the PVC screen at PZ 2

Attach 10' screen .010 w/ end cap  
Attach 15, 10' PVC sections.

Total length of PVC in well = 160'

Casing extends 2.25' above land surface

∴ Total depth of well is 157.75' BGS



1610 Complete setting casing at P22. Add one bag (100 lbs) of sand pack to stabilize bottom of well.

Prepare to clean up at P22.


Drillers securing site for the day

1645 Drillers depart Station.

E.P. does clean-up work at P23

and P22.

1730 E.P. departs station.



End of shift

4/28/94

9 hrs

FRIDAY

DAY 23

4/21/94

0800 E.P. arrives at the site. Prepares daily progress report and sends to AUGER/CEUR.

0840 Obtain work levels from Piezometers

	BWP	MP	ANISC
P21	141.65	(203.34)	61.67
P22	144.20	(206.67)	62.47
P23	142.25	(203.43)	61.68

0915 Call Optech for Mark Hansen's info and talk to Debbie Zapala.

0930 Begin to summarize progress to report to John Morris. Complete well log on P23

Weather: Partly cloudy and slightly overcast. Temp: 49°. Light winds from the southwest. Hi: low 60's w/ increasing chance of showers in the late afternoon

1040 Continue to summarize drilling history in a Memo to John Morris


1230 Call Ed Palma (Big Apple) to find out when drillers are. They received their extractor and will arrive at the site soon. We will work tomorrow to complete setting the piezometers.

1400 Drillers arrive at the site with the casing extractor. It will take an hour to prepare the equipment.

1515 Drillers watching extractor to bottom of O-DEX casing at PS 2.

1535 John Barnes Sr. arrives at the site. Begin to hammer the O-DEX casing up to expose the screen. Adding #2 washed Gravel and Filler pack as casing is being lifted. Vibration of hammer settles sand and seals as casing is removed.

PS 2



1635 Complete lifting casing.  
Casing lifted and cut at 10.50'  
∴ 10.25' of casing lifted from  
the total depth.

Unable to lift any more due to  
restriction on the drilling rig.  
Drillers will remove a 5' joint on  
the rig to allow for more casing  
to be pulled on future holes.

1710 Screen and gravel pack set. Drillers  
begin to remove 5' joint above  
extractor.

1740 Operations are complete. Begin to  
pack up site. Move drilling  
to PS 1 for tomorrow.

1805 Drillers depart the site.  
E.P. clean-up around PS 2

1815 E.P. departs the site.  
Calls John Mann at OFFCCU

*Paul E. Egan*  
10.25 hrs  
4/28/94

Saturday

DAY 24

4/30/94


0800

Arrive at Site w/ chislers

Begin to mix PVC casing to PZ1 to set casing. Soundings indicate hole is deep enough to set casing.

0830

Begin to set casing in PS1



Attach 10' screen w/ Bottom Cap.

Attach 14 10' PVC casing

Total length of PVC in well = 160'

PVC Screen Flush w/ land surface

PVC Casing is 1.8' above land surface

0840

Begin to weld extender to O-DEX casing.

To expose the screen, 20' of ODEX casing will be lifted.

0940

Begin to air hammer O-DEX casing out of the hole.

1045

10.3' of casing pulled.

160' original casing

- 10.3' Cut Casing

149.7

- 1.4' Casing above land surface

148.3' ODEX casing below land surface

53.55'

Elevation bottom O-DEX casing


Sand Pack : 140.5' below land surface

61.39' Elevation top of sand pack

59.4' Grout seal.

Damage PVC casing while cutting ODEX casing. No access to well

PS1



1200 Move to PS 3 location

Bottom of Screen 43.85'

Top of Screen 53.85'

Bottom of O-DEX casing 43.95' AMSL

Will lift 10' of O-DEX casing to expose the screen.

1220 Move rig over PS3. Begin to weld onto O-DEX casing.

1300 Begin to exhibit O-DEX casing.

1325 Complete pulling O-DEX casing.

11.3' of O-DEX casing removed.

Sand pack to 146.72' BLS. (56.63' AMSL)


∴ Sand is 2.78' above bottom of O-DEX casing.

Put bentonite Slurry seal.

1415 Move to P21 to grout




PS 3



1515	Mix grout and grout PS1 to the surface. 2 grout iterations 4 bags of grout.
	Grout Seal Begins at Site 3 03-005 BH.
1610	Moving to Grout PS2
1625	Begin to mix grout at PS2. Grout PS2 to the surface. 2 Grout iterations; 4.5 bags of grout.
	Grout Seal Begins at Site 1 and 2. 02-003 BH and 01-002 BH
1710	Moving to PS 3
1718	Cut casing and prepare to Grout PS 3
1750	Complete Grouting PS 3 to the surface. 2 iterations using 4.5 bags of grout.

1800 Begin to secure the site for the day.

1810 Drillers depart the site  
E.P. departs the site.



E.O. E. L. Jr. 4/30/94 (10 hrs)

Sunday DAY 25 1 May

Called John Means for status report at his residence to inform him of current situation.

Purchase a saw to cut damaged casing at PSI to obtain water level.

1410 Arrive at station to collect water levels.

PS3 WL = 142.74

MP = 1.45

= 141.29' BLS

PS3 at 203.35 - 141.29 = 62.06' AMSL

PS 2 WL = 144.54

MP = 1.00

143.54' BLS

PS2 at 206.00 - 143.54 = 62.46' AMSL



Cut casing at PSI.


PSI was damaged during installation of the PVC casing. When the hole was grouted, grout got into the PVC casing and the well collapsed. It is completely grouted up.

Additional water levels will not be possible from this piezometer.

1440 Depart Station

Return to Hotel to call John Morris about PSI.

Will inform Bill Lee Perry (MURAC) and will use previous water levels for flow direction at the Station.



Saeed El Fakhri 5/1/94 (3.5 hrs)


Monday

DAY 26

2 May 94

0800 Arrive at the station w/ Mark Hanson from Optech.

Set up to survey in the piezometers to check elevations again



Station 1

BM 202.07' Rod 4.58' IH: 206.65' Anisc

PS1 Rod: 4.80 El = 201.85 <201.89>

PS2 Rod: 0.69 El = 205.96 <206.00>

MW01 Rod: 1.49 El = 204.47

Station 2 PS2: 205.96 Rod 2.02 IH: 207.98

BM = Rod: 6.38 El = 201.60 <201.57>

PS3 = Rod: 4.65 El = 203.33 <203.35>

- All elevations are close enough to use original measurements

Weather: Clear and mild. Temp: 55°  
Winds out of the southwest.  
The today was 70. Windy, mild.

Prepare to collect water levels at PS2 & PS3.

0830 Drillers are at the site moving equipment for MWOL drilling.

0850 Obtain water levels from PS2 and PS3. (cont) (mpt)

PS2 144.96 - 1.00 = 143.96 = 62.04' mwe

PS3 143.15 - 1.00 = 141.75 = 61.60

Call ANGRC/CEUR for Lee Perry but he is not in.

0900 Drillers begin to set up at MWOL.  
MWOL is moved to the north east side of IRP Site No 1 to place it upgradient of the sites.

Safety meeting: Enel Proker

John Barnes

Bill Fagnie

Review of safety concerns during drilling.

1030

Begin to set up on MWOL

Call into Optech to inform John Morris on status. Fax gradient map with location of MWOL. Gradient of groundwater is to the west; northwest at approx 285°

Try to call Lee Perry at ANGRC/CEUR but he is not in.

1100

Begin to drill at MWOL

Interval 0'-10' BGS

0'-5' Sandy fill. Sand and gravel.

wt some fill material.

5'-10' Sand, medium to fine sand,

silt, and gravel.

1118 Complete drilling.

Begin to attach next 15' Interval.

Drillers take lunch.

1150

Bill Hedberg (HINZWRAP) arrives

at the site. Brief him on the

situation and objectives of the SI

1210	Complete attaching next 15' interval	
	Begin 10'-25' BCS Interval	
	10'-15' Sandy, silty, gravel. Mostly sand and gravel w/ silt.	
	15'-20' Sand, silt and gravel. Mostly a fine sand and silt w/ abundant gravel.	
	20'-25' Silty sand and gravel. Less sand. Mostly gravel.	
1240	Complete 15' Interval. Begin to assemble next 15' Interval.	
1315	Begin to drill next 15' Interval. Interval 25'-40' BCS	
	25'-30' Fine sand, gravel and abundant large rock fragments. Drilling through large boulders. Very slow drilling.	
	30'-35' Fine sand, gravel and rock fragments. Coarse gravel and abundant rock fragments with some sand and silt.	
	35'-40' Gravel becoming more sandy. Medium sand w/ some fine sand, silt, and gravel.	

1355	Complete drilling 15' interval. Preparing to attach next 15' interval.	
1475	Begin next 15' interval. Interval 40'-55' BCS	
	40'-45' Sandy, silty, gravel and sand mostly fine sand, gravel and rock fragments.	
	45'-50' Fine sand and gravel w/ abundant rock fragments. Mostly fine sand and gravel.	
	50'-55' Fine to medium sand, gravel and abundant rock fragments. Larger gravel and slightly more sandy near the bottom.	
1437	Completed 15' Interval. Preparing next 15' Interval for drilling.	
1508	Begin the next 15' interval. Interval 55'-70' BCS	
	55'-60' Coarse sand and gravel. Mostly small gravel, coarse sand and few rock fragments.	

60'-65' Abundant gravel and rock fragments.  
Large boulders drilling going slower.  
Some fine sand. Mostly gravel and  
rock fragments. Becoming more  
medium sand at bottom.

65'-70' VPS Sand, silt, clay and gravel.  
Soil is slightly moist and may  
indicate perched water. Slight  
skew was noted. Mostly a  
very fairly sorted medium sand  
and gravel w/ silt and clay.

1528 Complete drilling 15' interval  
Begin to abate next 15' interval.

1554 Begin to drill next 15' interval.  
Interval 70'-85' 285

70'-75' VPS sand and gravel and  
silt. Slight skew. Some  
gravel and rock fragments. Becoming  
more silty near the bottom.

75'-80' VPS Silty sand. Sand, silt, and  
clay w/ some well rounded gravel.  
Very moist silty sand w/ the skew-

80'-85' VPS Sand, silt, and clay w/  
gravel and few rock fragments.  
Becoming a medium sand and  
gravel well rounded gravel and  
sand. Moist.


1610 Complete drilling 15' interval

Begin to secure site for the day.

1630 Driller's report the site

EP and M.H. secure the MWO  
location

1645 EP, M.H. and Bill Helberg depart  
the site



East of Lake 5/2/74

8.75 15

TUESDAY

DAY 27

3 MAY 94

0800

Arrive at the S.K. Enel Packer, Mark  
Hanson, Bill Hildberg

E.P. prepares daily progress report and  
sends it to Lee Perry (AUGRC/CEUE).

0900

Call Lee Perry (AUGRC/CEUE). Talk

about progress of the investigation.

Inform him of the new location

of 01-001 MW due to groundwater

flow direction. Talk about the

drawdowns of 02-001 MW and

03-001 MW.

03-001 MW will be placed down

in the parking lot as near as

possible to remain out of the way

of flooding during rains. These two

dry wells overflow during periods

of medium to heavy rains.

02-001 MW will be placed on the

edge of the pavement down gradient

from the two dry wells at Bldg 16 and 9

0940


Drillers arrive at the site. Begin to  
prepare for drilling.

1030

E.P. and M.H. walk to 02-001 MW and  
03-001 MW locations.

Drillers are moving augers to a  
central location.

IRP Site No. 3 - 03-001 MW



Bldg 36

1115 Safety Meeting w/ drillers. Weather is  
Sunny and mild. Hi - mid 60's

1135 Driller's begin to work on next 15' interval.

1150 Driller's begin to drill next 15' interval  
Interval 85'-100' BLS

85'-90' Very coarse sand and gravel w/  
abundant rock fragments, mostly  
coarse sand.

90'-95' Fine to medium sand mostly  
medium sandy gravel and some  
rock fragments. Abundant gravel  
w/ fine to medium sand. Beginning  
more sandy near the bottom.

95'-100' Fine to medium sand with gravel.  
Mostly medium and fine sand.  
Few small well rounded gravel.  
Mostly fine sand, gravelly medium  
sand.

1210 Complete drilling 15' interval

1240 Attach next 15' interval. Begin to drill

Interval 100'-115' BLS.

100'-105' Medium to fine sand and gravel.  
Few rock fragments. Mostly a  
fine, to medium grained sand.

105'-110' Mostly medium sand w/ fine sand  
and gravel. Few rock fragments.  
Medium sand.

110'-115' Mostly medium sand with some  
fine sand and gravel. Mostly  
A medium to fine gravel sand.  
Below medium sand near bottom.

1305 Complete 15' Interval  
Break for lunch after reaching next  
15' interval to drilling.

1433 Complete Attaching next 15' interval  
Begin to drill 115'-130' BLS interval  
115'-120' Sand, medium to fine sand,  
gravel and rock fragments. Coarse  
to medium sand w/ gravel.

120'-125' Mostly medium to fine sand, gravel  
and abundant rock fragments.

Fine to medium gravelly  
sand and rock fragments.

125'-130' Medium to fine sand and gravel.  
Mostly medium and fine sand w/  
gravel. Very few rock fragments.



1458 Complete drilling on 15' interval

Water at 01-001 MW is estimated to be @ 62.0' AMSL

01-001 MW 204.47' AMSL  
- 62.00

142.47' Below land surface

by 15' Screen. we want 10' in water and 5' above water.

Screened interval of

137.5' BS (67.00' AMSL)

142.5' BS (62.00' AMSL)

152.5' BS (52.0' AMSL)

Will drill ODEX casing to 155.00' BS

Will set screen bottom at 152.5' BS

1532 Begin to drill next 15' Interval

Interval 130'-145' BLS

130'-135' Fine to medium sand, gravel, silt, and few rock fragments.

Mostly a fine to medium sand.

135'-140' Fine to medium sand. Gravel and sand. Mostly a medium to fine sand and gravel.

140'-145' Medium sand and gravel. Some fine sand and gravel. Mostly a medium sand. Skew present at 143' BLS. Sand and some gravel.

1553 Complete 15' Interval

Begin to secure the site for the day

Will drill last interval and screen

Prepare to concrete cap boreholes and other abandoned piezometer well


Incisions Bill Hedberg deposits site.

1630 More over to PS1 area to concrete the holes in the asphalt.

1740 Move over to boreholes at  
IPP Site. Use 1 and 2 and cement  
cap boreholes.

1805 Complete cement work. Pick up  
equipment and secure site.

1815 Depart Site. Drillers depart  
and EP and MH depart site.



End of shift 9/3/74 (9.3 hrs)

WEDNESDAY DAY 28 4 May 74

0800 EMI Parker, Mark Hanson, Bill Hocking  
Arrive at the station

EP prepares mud sands Optech daily  
p. report

M.H. sets up and calibrates  
field GC.

0900 Drillers arrive at the site. Prep for  
operations. Discuss safety considerations  
for ODEX extraction procedures.  
Get the sampling hammer and split spacers  
prepared. Prep for finish drilling and  
get down area ready.

0953 Begin to drill last interval  
Interval 145-155' BLS  
145'-150' Medium to fine sand and  
gravel. Mostly medium sand  
Fewer small gravel. Steam  
and wet sand.



150-155 Medium sand. Some fine sand and gravel mostly medium sand.

1005 Complete drilling 2.3' of casing at the surface. Hole drilled to 155.7' BLS.

1018 Blow cut hole w/ air to clean out casing as much as possible. Beginning to pull drill string to remove hammer.

Measure screens

PVC Section	1	2	3	4	5	6	7	Screen Section	Screen w/ End Cap
	19.96'	20.00'	19.97'	20.00'	20.00'	19.97'	20.00'	10.02'	6.10'
									156.02'

1100 Obtain split spoon sample from upper marker.

P10 opening 0.0 PPM

Obtain sample for GC analysis.

1103 Begin to assemble and run screen down casing.


1115 Complete running screen in the well. Assembled 5' screens, end cap, 10' screen, the PVC sections 1 to 7.

PVC Section 7 ended up 7.8' above land surface. (It off 5.36')

∴ Bottom of well casing is 148.22'

BLS, MP = 2.3' casing above land surface.

Initial water level	@ 1130 hrs
148.76' below MP	148.69'
2.30' MP	2.30'
146.46' BLS	146.39'



Cut from PVC casing 5.36'

Total length PUC =  $156.02 - 5.36 = 150.66$

Bottom of O-DEX Casing : 155.7' BLS

Bottom of Screen : 148.22' BLS

Top of Screen : 133.22' BLS

Pull O-DEX Casing to : 133.0' BLS

Must remove 22.7' ODEX Casing.

1230 Cut off first O-DEX section of

9.40' w/ O-DEX MP of 1.0' above land.

Bottom of O-DEX Casing : 149.6' BLS

Casing MP is now 2.0' Above land surface

∴ Casing settled 0.3' down

Bottom of Casing PUC Screen : 148.66

1303 Water level 145.74

- 2.00 MP

143.74' BLS

1350 Begin to LA O-DEX casing again.  
Add 1/2 bag #2.W.G.

Begin to pull up well casing and well  
are coming up together.

Well has risen 1.4' up since we  
began. Stopped lifting casing to  
attempt to stabilize well.

Bottom of casing and PVC screen: 147.26

1510 Unable to prevent well from rising  
with O-DEX casing. The PVC well is  
firmly adhered to the O-DEX casing  
by the gravel pack.

It is determined to pull the well and  
drill and reinstall the well. This  
time, the well will have a 10' screen  
as started in the work plan and  
the well will be immediately hydrated  
with water in order to minimize  
sand bearing within the well.

Both of these factors should minimize  
the distance the O-DEX casing  
should need to be raised to  
expose the screen.

1520 Attempt to remove PVC well  
from O-DEX casing. Well breaks  
at the 2<sup>nd</sup> PVC section from  
the bottom. 40' of PVC casing  
plus 15' of slotted screen  
remains in the hole.

1610 Drillers will discuss options to  
remove remaining well and  
re-drill O-DEX casing to attempt  
to set the well again.

O-DEX casing cut 4' below  
the 145' joint. There is now  
141.0' of O-DEX casing in the  
hole.


1620 Drillers begin to secure the site  
for the day.

1630 Drillers depart the site.  
Bill Hedberg departs the site.

S.L. and M.H. perform silk clean-up and secure equipment.


1691 3P and 111 deg. 110 side

2030 Preparing plan to re-drill well for tomorrow.



### Current Situation:


63.65' Anise Bottom of 9 Deck  
57.21' Anise Bottom of Screen



Must drill with O-PÈX an additional

10.31 BLS.

W.11 pull ODEX casing up 14.0'



✓	5.5 hrs	6/6/99	✓
---	---------	--------	---

Thursday DAY 29

5 May 94

0815 Arrive at the Station

E.D. prepares daily progress report and reviews calculations for the re-attached to install O-DEX/MW

MH warms up and calibrates field GC and prepares PID.

0910

Dallies arrive at the site. They will use an air hammer to break up and remove old casing from well.

Begin to attach air hammer and drill string.

1010

Begin to hammer on PVC casing. Hammer encounters casing at  $\approx 95'$  BLS.

PVC collings rise to the surface as the drill.

1100

At approx 125' BLS. O-DEX casing begins to go into the ground. Stop drilling.

in order to attach 10' section to O-DEX casing.

1148

Complete attaching 10' casing onto O-DEX casing. Beginning to drill again. Encountering the well screen.

1300

Attach next 15' interval and ready to drill. Break for lunch.

This next 15' interval will intersect the bottom of the O-DEX casing at 6'. The air hammer will not fit past the shoe on the lead casing so it will only be drilled 6'. We will then be at  $\approx 141'$  BLS.

1409

Drill to the O-DEX shoe with the air hammer. Now at 144' BLS. Blow air and clean out hole. Prepare to extend the air hammer to replace w/ O-DEX hammer to continue hole.

1520 Removed air hammer. Large pieces of PVC screen are removed. Drillers begin to re-assemble drill string with O-DEX hammer.

1600 O-DEX hammer and drill string are in the hole. We will proceed with the final drilling and setting the new well tomorrow.

Bill Kellogg informs me this will be his last afternoon in the field. Gives informal debriefing on his observations in the field.

1610 Drillers depart site.

1620 E.P. and M.H. secure the site and depart the station.

2130 John Morris calls and I inform him of the situation at the site.

Errol E. Lash 5/5/94 8 hrs

Friday


DAY 30

6 May 94

0815 E.P. and M.H. arrive at the site. E.P. prepares daily field report and faxes to Leo Perry (ANSARC/CEUZ).

Attempts calls at 0830 and 0900 but he is not in. Left a message.

0915 Drillers arrive at the site. Prepare for drilling. Attach O-DEX casing to drill last interval.





Attaching 9.3' length of O-DEX casing  
to O-DEX string 146.1'

∴ O-DEX string casing is 155.4'

For O-DEX to go 152.5' BLS  
we need to stop drilling at  
2.9' of O-DEX above land surface.

1040 Begin to drill last 10'. Some casing blows  
out but mostly wet sand. Near bottom of  
casing. Just sand. Lay out PVC sections  
for entry into well.

PVC Section 1	19.97	* Optional
2	20.00	
3	20.00	
4	19.98	
5	20.00	
6	20.00	
7	20.00	
8	20.00	
PVC 10' Screen	10.30	
	150.28	
End cap	+ 0.35	
Total		= 150.63

1120 Shutoff drilling, Air out hole

1122 Begin to add water to well

Pull out drill rods.

O-DEX casing is 2.8' Above land

Surface - ODEX end is at 152.6' BLS

1137 Complete adding water to well

Continue to pull out drill rods.

1155 Complete pulling out drill rods.

Pulling Air hammer.

Preparing to set PVC Screen.

Mark Hansen Attaches endcap

to 4" PVC screen (.010 slotted,  
10' in length).

Begin to run screen down

the hole EP and MH


Attach screen and 1st PVC

interval using Clean gloves.

Drillers continue to install

PVC casing in the well.

01-001 MW



1210 Complete Assembling the well.  
Complete Attaching all sections  
and it extends 6.5' Above  
the land surface.

∴ Bottom of screen is at  
144.13' feet BLS.

We had 8.5' of sand here in  
the well even with the water.

Measure water flow into well.  
water at 1 gallon per 28 seconds.  
Water flowed for 15 minutes.  
Therefore 32.15 gallons was added  
to the well.

1235 Drillers break for lunch. We will  
air jet the bottom of the well  
using an air hose to settle  
the well deeper.

1250 Begin to lower air hose in  
the well. Attach to small



Air compressor on the rig.

1310 Begin to Air Jet the well. Well falls down into well approx 7.0 feet to 0.5' BLS.

Bottom of PVC casing is now 151.1' BLS. Complete Air Jetting and remove Air hose from the well.

1325. Begin to attach O-DEX extensor to casing to lift O-DEX casing to expose the PVC Screen.

Bottom of O-DEX casing, 152.6' BLS  
Bottom of PVC screen 151.1' BLS  
Top of PVC Screen 140.8' BLS

Will pull O-DEX casing to 140' BLS  
∴ Need to lift casing 11.8'  
Will lift casing 12.0'.

1410 Extractor is Attached. Begin to pull O-DEX casing.

Placing gravel pack as well is extracted. Using #2 washed gravel as sand pack.

1435 Completed pulling O-DEX casing 12.8'. Added 1 bag (100 lb) and 3/4 of a second bag of Sand Pack.

Bottom of O-DEX casing. At 139.8' BLS

PVC casing settled to 0.7' BLS. Screen interval is

Top: 140.7' BLS  
Bottom: 151.0' BLS

Top of Sand Pack is measured at 136.08' BLS.

Place Bentonite pellets and measure the top of the seal at 132.7'. Hydrate the bentonite seal w/ 10 gal.

1510 Complete setting 01-001 MW. Drillers begin to pick up around the site.

Begin to cut O-DEX casing at the land surface.


Attach flat air hammer on O-DEX casing and hammer casing to 0.3' below land surface to set the flash mount cover over the well.

Drillers will spot hole and complete surface cover at a later time. Cut PVC casing to 0.5' above land surface. Cap well.

1600 Drillers continue to clean up at the site and move equipment to 03-001 MW location.

1730 Drillers moving Air Compressor and Drill pipe to 03-001 MW.

E.P. and M.H. prepare to survey the next drilling location



Benchmark: 202.07'

Red: 5.04 Ins Height: 207.11'

Dry well (North) 6.78 200.33' AMSL

Dry well (South) 6.56 200.55' AMSL

High Water Mark 5.86 201.25' AMSL

03-001 MW 5.77 201.34' AMSL

1810 Drillers moved all equipment and are send to clean drill stems to drill on Monday. Begin to secure the site for the weekend.

1815 Drillers report the site.


1815 E.P. and M.H. obtain w/c from  
01-001 MW.

WL = 141.48

MP =  $\frac{0.30}{141.18' \text{ BLS}}$

OR 63.29' AFS AMSL

1820 E.P. and M.H. Depent the site.



End of Day 31 5/6/94 9.5 hrs

Saturday

DAY 31

5/7/94

No Work Related Activities

End of Day 31

5/7/94

00 hrs

Sunday Day 32 5/8/94

No work related activities

*Eddie Fackler* 5/8/94 0.0 h-s

Monday DAY 33 5/9/94

0810 E.P. and M.H. move at the Station.  
E.P. calls Lee Perry (ADDER/LEUR PM)  
Informs him of completing 01-001 MW and  
beginning of 03 001 MW. He asks again  
if the well will also be down-gradient  
of the IRP Site U3. It will not  
IRP Site No 3 and the dry wells are  
across gradient from each other and  
the scope of the work plan states the  
Monitor wells are installed specifically to  
investigate the dry wells. Therefore the  
MW's are placed for that purpose.

M.H. warns up the field GC.

0850 Drillers move at the site.  
Dean drill pipe, prepare land-ODEX pipe  
with drill shoe and land drill pipe in  
O-DEX casing.

1015 Safety briefing.  
Ernie Proke John Brown  
Mark Hanson Bill Feggo  
Discuss usual safety considerations and  
new site hazards. Discuss special concerns

of being down gradient of our first set of dry wells and possible contaminants are very important. Emphasize the importance of shielding drill cuttings.

1030 Prepare rods and banners to drill the first 10' interval. 03-001 MW

1045 Begin to drill interval 10' interval  
0'-5' Blacktop some road base material and fill. VPS sand, silt, and gravel. Mostly sand and gravel.  
5'-10' Sand, silt and gravel. Mostly sand and fine to medium sand and gravel. Angular gravel and rubble.

1055 Complete 10' interval. Add next 15' interval

Weather: Clear to Partly Cloudy and mild. Temp: 61 Hi: low 70's  
Clear to PC w/ light winds from the southwest. Turn more cloudy late in the afternoon.

1140 Begin to drill next 15' interval  
Interval 10'-25' BCS  
10'-15' Sand, silt, and gravel. wet zone of silty and clayey, silty sand at 12' BCS. becoming quickly a clay silty sand w/ gravel.  
15'-20' Sand, silt, and gravel. Medium sand with gravel and silt.  
20'-25' Sand, silt, and gravel. rounded gravel. Mostly a silty fine to medium sand.

1150 Complete drilling 15' interval. Begin to attach next 15' interval.

1223 Begin to drill next 15' interval  
Interval 25'-40' BCS  
25'-30' Sand, silt, and gravel. Some rock fragments locally. Mostly a very poorly sorted sand, silt and gravel.  
30'-35' Fine to medium sand and gravel. VPS sand, silt, and gravel. Few rock fragments.

35'-40' UPS sand, and to fine sand, and gravel to abundant rock fragments at 38' BLS. Mostly rock fragments and fine to medium sand. Abundant gravel.

1235 Complete drilling 15' interval.  
Break for lunch

Dillers begin to prepare next 15' interval for installation.

1352 Ready to drill next 15' interval.

Interval 40-55' BLS

40'-45' Fine sand, clay and rock fragments and gravel. Mostly gravelly rock fragments and fine sand.

45'-50' Rock fragments, gravel, and fine sand. Becoming a medium sand and gravel at 47' BLS. Mostly a medium sand with fine sand and gravel.

50'-55' Fine to medium sand and gravel. Mostly fine and medium sand. Well rounded small gravel. No rock fragments.

1404 Complete drilling 15' interval

1435 Complete welding next interval. Begin to drill 55'-70' BLS interval.  
55'-60' Medium sand, silt, and gravel.  
60'-65' Medium to fine sand and gravel. Becoming more medium sand and gravel. Few rock fragments.  
65'-70' Medium to fine sand and gravel. Becoming more dark and silty.  
UPS sand, silt and gravel.

1448 Complete drilling the next 15' interval.  
Begin to attach next 15' interval.

1510 Begin to drill next 15' interval.

Interval 70'-85' BLS

70'-75' UPS sand, silt, and gravel, some larger gravel.

75'-80' UPS sand, silt, and gravel. Dark brown and slightly moist. Mostly a sand, silt, and gravel.

80'-85' UPS sand, silt, and clay becoming more sandy with bottom w/ some rock fragments. Sand and gravel.

1522 Complete 15' interval. Begin to attach next 15' interval.



1550 Begin to drill next 15' interval.  
 Interval 85'-100' BLS  
 85'-90' medium to fine sand and gravel.  
 Few rock fragments. Mostly sand and gravel.  
 90'-95' Medium to fine sand, gravel and  
 rock fragments. Gravelly sand w/ fragments.  
 Mostly coarse sand to silt and gravel.  
 95'-100' Sand, silt, and gravel UPS sand  
 and silt w/ gravel and few angular  
 large gravel and rock fragments.

1603 Complete 15' interval. Complete drilling  
 for the day. Drilling begins to break down  
 - and stop equipment for the day.  
 Drillers begin to attach the next 15'  
 interval.

1627 Begin to drill next 15' interval  
 Interval 100'-115' BLS  
 100'-105' UPS sand, silt and gravel.  
 Mostly sand and gravel.  
 105'-110' Medium sand. Mostly medium sand  
 w/ some fine sand and gravel.  
 Mostly medium sand w/ silt  
 evident at 110' BLS

110'-115' Fine to medium sand and  
 gravel. Mostly medium sand with  
 rounded gravel. No evidence of silt  
 or water.

1642 Complete drilling 15' interval. Complete  
 drilling for the day. Drillers begin to  
 break down and stop equipment for the day.

1655 E.P. and M.H. obtain water level from  
 01-001 MW  
 WL = 142.33  
 - 0.10 MP  
 142.23 BLS

1655 Drillers depart the site.  
 E.P. and M.H. depart the site.

Earl Edwards 5/9/94 8.5 hrs

TUESDAY DAY 34 10 May 94

0810 E.P. and M.H. arrive at the site.  
 E.P. prepares daily status report and sends it to Lew Perry (ANZDEC/CCW PM).  
 0850 Drillers arrive at the site. Begin to prepare for drilling.  
 Safety Briefing:  
 Earl Carter  
 Mark Hansen  
 John Brown  
 Bill Fyfe  
 Safety Review  
 Weather: Clear to Partly Cloudy and Mild. Temp 64° F. - Mid 70's. Clear to P.C. w/ light winds from the SE at 5 to 10 mph. Annular Eclipse at 1350 today.  
 0915 Drillers begin to weld on next pipe interval to drill string and M.H. Moves drill cuttings to the cuttings stockpile. will be determining aquifer cuttings to store in cuttings area to await analytical analysis on water.

0940	BEGIN TO DRILL	NEXT 15' Interval
	Interval 115'-130' BLS	
	115'-120'	Fine to medium sand, moist and gravelly. Mostly a fine and medium sand. No steam.
	120'-125'	Medium sand w/ fine sand and gravel.
	125'-130'	Medium sand with fine sand and gravel. Slightly more gravelly near the bottom
0957	Complete drilling 15' interval.	Adding next 15' interval.
1030	Begin to drill next 15' interval	
	Interval 130'-145' BLS	
	130'-135'	Medium sand, fine and gravel. Mostly a moist medium sand and fine sand w/ gravel.
	135'-140'	Medium sand w/ fine sand and some gravel. Some steam evident.
	140'-145'	Mostly a medium to fine sand and gravel. Moist sand and steam.
1055	End 15' interval.	



Begin to attach next interval.

WL at PZ1 measured at 61.69' msl


on 4/28/93  $\therefore$  at 139.65' BLS at

03-001 MW.

Assume WL at 03-001 MW = 139.5' BLS

Screened interval from 136.5' - 146.5'

Planned Settings



Measured Screen and Casings

Screen 10.02

PVC Section 1 19.98

" 2 20.04

" 3 20.02

" 4 20.02

" 5 20.02

" 6 20.01

" 7 20.01

End Cap - 1.08

151.20' Total Length

Total length from bottom of the screen

is (Tot) - (End Cap) =

or 151.20 - 1.08 = 150.1

Bottom of Screen at 146.5

Screen & PVC is 150.1

We want 3.6' of Screen Above land surface.

Begin to drill next 10' interval.

Will only drill 8 feet.


1135

145-150 Water extremely thin a wet to moist medium sand, fine sand and gravel. Mostly a medium sand

150-153 Medium sand, fine sand and gravel. Mostly a medium sand w/ some fine sand and rounded small gravel. Stern.

1143 Complete drilling 8' interval

Adding additional screen due to the effects of the slowly recharging well near by. 10.02'



Well will have a 20' screened interval.

1150 Turn off air after blowing out hole for 5 minutes. Begin to add water to well to put positive head in well.

Begin to pull out drill rods.

1213 Complete pulling out drill rods. Turn water out of well.

Water on for 23 minutes at 1 gallon per 45 seconds is approx 31 gallons in the well.

1220 Run split spoon sampler down the hole to obtain a sample from the aquifer material for field screening. P.O. 0.0 PPM

Soil is a medium sand w/ some fine sand and few gravel.

1230 Begin to assemble and run PUC in the hole. EP and will set PUC screens and end caps w/ Nitril Gloves.

Drillers using Nylon Glovers begin to assemble the PVC casings and run them down the hole.

1248 Complete running PVC screens and casing down the hole. Total casing set in the hole is 161.22'. End cap is 1.03' and 12.9' of casing above land surface.

∴ Bottom of screen is 147.24' BLS

Drillers break for lunch.

1335 Pullers begin to attach O-DEX extractor to casing.

Bottom of O-DEX casing = 153.0

Bottom of PVC Screen = 147.2'

Top of PVC Screen = 127.2

Must extract O-DEX casing to

approx 127' therefore we must extract approximately 26' of O-DEX casing.

1410 Begin to extract O-DEX casing.


1417 Weld breaks on O-DEX casing and Air hammer after approximately 9 feet of extraction. Decide to cut the casing here and re-weld the extractor back on the O-DEX casing. Added 1/2 bag of #2 W.G. sand pack down well extraction. Cut off 9.82' of O-DEX casing. Then line 153.0  
- 9.2  
143.8' with 1.0' above LS

∴ Bottom of O-DEX casing = 142.8' BLS

1423 Begin to re-weld extractor to O-DEX casing to continue to pull the casing to expose the screen.

1515 Complete welding and preparing to extract the O-DEX casing. Need to continue to lift O-DEX casing approx 16 feet.

03-001 MW



1530 Begin to extract O-DEX casing. Measuring the top of the sand pack during extraction. Adding #2 W.G. as O-DEX is being lifted to insure the well is not locking up with the O-DEX casing as it is being extracted.

1620 Complete lifting O-DEX casing A total of approx 16 feet.

Cul O-DEX casing 17.8' removed  
147.8  
- 14.8

128.0' with 2.9' above land surface  
Bottom of O-DEX casing = 125.1' BLS

PVC casing now measures 13.2' above land surface after O-DEX extraction is complete. Therefore

160.14  
- 13.20

146.94' BLS - Bottom of PVC Screen.

Sand pack top was measured at 121.0' BLS (80.34' AMSL)

Buttbank seal chips placed in the well and hydrated with 10 gallons of water. Top of the Buttbank seal was measured at 116.70' BLS (80.60' AMSL)

1655 Complete setting well. Begin to clean up equipment around the site.

1710 Drillers have secured the site preparing to depart.

E.P. and M.H. Sent two 55-gallon DOT drums with all soil collings from 03-001 MW 130' BLS to TD (153.0' BLS). Drums of soil material from the upper will be stored with other soil collings to await groundwater analytical analysis. Drums will be labeled and moved in the morning.


1715 Drillers depart the site.

1715 E.P. and M.H. obtain groundwater levels.  
03-001 MW  
WL = 139.99  
0.40 MP  
139.59' BLS  
139.59' (201.34) 61.75' AMSL

01-001 MW  
WL = 142.47  
0.30  
142.17

142.17 (204.47) 62.30' AMSL

1730 E.P. and M.H. depart the site



Ed E. Lach

5/10/94

9 hrs



40'-45' VPS sand, silt, and gravel. Mostly a sandy gravel and few rock fragments.

45'-50' Medium to fine sandy gravel and rock fragments. Mostly large gravel and fragments.

50'-55' Mostly a dry fine sand w/ gravel

1648 Complete Drilling 15' interval. Drillers begin to track next 15' interval.

1702 Begin to drill next 15' interval.

Interval 55'-70' BLS

55'-60' Fine sand to sand, gravel and

abundant rock fragments. Becoming more generally with rock fragments near the bottom.

60'-65' VPS sand, silt, and gravel with

larger gravel and rock fragments. Becoming more sandy near bottom.

65'-70' Medium to fine sand and gravel

Medium sand and gravel with some

fine sands and few rock fragments

VPS sand and gravel

Complete drilling 15' interval

Drillers begin to secure the site for the day.

1730 Drillers depart the site  
EP and MH obtain water levels

PS 3 142.80

1.50 MP

141.30' BLS (62.05)

PS 2 144.58

1.00 MP

143.58' BLS (62.42)

01-001 MW

142.25

~~EL 142.25~~ MP 0.20 MP

142.05' BLS (62.42)

03-001 MW

139.82

0.40 MP

139.42' BLS (61.92)

1750 EP and MH. Report the site.

Earl Edwards

5/11/94

9 hrs

1258 Complete drilling the initial 10' interval.

Drillers organizing the ODEX casing and drill pipe in a better position to feed it up into the hole.

Drillers performing additional work on the drill rig.

1438 Drillers prepare the next 15' interval for drilling. Welding next O-DEX interval in place.

1455 Drillers begin to drill next 15' interval. Interval 10' - 25' BLS.

10' - 15' Mostly gravel and rock fragments. Breaking through large rocks. Some fine to coarse sand. Mostly gravel and rock fragments.

15' - 20' Sandy gravel and rock fragments. Mostly gravel and rock fragments becoming more sand near the bottom. Very coarse sand with silt and abundant gravel and rock fragments.

20 - 25' Medium to coarse sand and gravel some silt, gravel, and rock fragments. Mostly a medium sand w/ gravel.

1518 Complete drilling 15' interval. Begin to attach next 15' interval.

1545 Begin to drill next 15' interval.

Interval 25 - 40' BLS. Medium to fine sand and gravel. Mostly a medium sand and gravel.

30' - 35' Medium to fine sand with abundant gravel and few rock fragments.

35' - 40' VPS sand, silt, and gravel with larger gravel and few rock fragments. Mostly a coarse sandy gravel and sand.

1555 Complete 15' interval. Beginning to add next 15' of drill pipe and ODEX casing.

1624 Complete attaching 15' interval. Begin to drill 40' - 55' BLS interval.



WEDNESDAY

DAY 35

11 May 94

0810 Arrive at the Station.


E.P. prepare daily progress report and send it to Lee Perry (ANGRE/CIUE PM).

0850 Drillers arrive at the site. Begin to prepare to move equipment to 02-001 MW.

E.P. and M.H. move drums of aquifer material to claim storage area north of the parking lot. We have 2 drums of aquifer material from 03-001 MW.

1025 Drillers begin to organize equipment around 02-001 MW. Delivery of drill pipe and PVC casing for monitor well are delivered.

E.P. and M.H. survey in the new monitor well drilling location.



Benchmark Marked corner of 12P Site No 1.  
Elevation 201.57 Rod 8.79

Instrument Height: 210.36'

Recoil PS 3 Rod 7.03 203.33' < 203.35 >

02-001 MW Rod 6.68 203.68'

1205 Call Joe Byrd At Optech to return call. Arrange for him to come out on Sunday to complete the project.

1215 Break for lunch

1240 Return to site. Drillers are preparing to drill initial 10' interval.

1245 Begin to drill initial 10' interval  
Interval 0-10' BLS

0'-5' Mash an unsorted fill material  
And road base. Very poorly sorted

Sand, silt, and angular gravel.

5'-10' UPS sand, silt, and gravel with large angular rock fragments.

THURSDAY

DAY 36

12 May 94

0810

E.P. and M.H. Arrive at the Station.

E.P. prepares and sends Daily progress report to Lee Remy (ANGEL/CEUR PW).

M.H. prepares bell QC for operation.

0900

Drillers arrive at the site. Begin to prepare for the days operations. Discuss Safety issues with chance of rain this morning. Then E.P. and M.H. move drums of cuttings to the Station to dispose of.

0915

Drillers begin to attach next 15' interval to drill string.

0945

Begin to drill next 15' interval.

Interval 70-85' BCS

70-75' VPS sand, silt, and larger gravel. Few rock fragments.

75-80'

VPS Sand, silt, and gravel. Medium to fine sand and larger gravel. Becoming more silty w/ clay, silt and fine sand.

80-85'

VPS sand, silt and gravel w/ some clay and slight moisture to a more medium sand and gravel.

1005

Complete 15' interval. Begin to attach next 15' interval to drill string.

1034

Begin to drill next 15' interval.

Interval 85-100' BCS

85-90' Fine to medium sand and gravel. Mostly sand w/ gravel and few rock fragments.

90-95'

Fine to medium sand, gravel and some rock fragments. Mostly And sand and gravel.

95-100'

Medium sand w/ gravel and few rock fragments. Mostly a sand medium to fine w/ gravel and some rock fragments.

1052

Complete drilling 15' interval. Prepare to attach next 15' interval.

WEATHER

: Cloudy, mild w/ chance of rain today. Hi - 69° and drizzle. winds out of the south from 5-15 mph.

Screen	10.05
PVC - Section 1	10.03
" 2	10.05
" 3	10.05
" 4	10.05
" 5	10.05
" 6	10.03
" 7	10.05
" 8	10.05
" 9	10.05
" 10	10.03
" 11	10.03
" 12	10.05
" 13	10.05
" 14	10.05
" 15	10.05

End Cap 0.50

1133 Begin to drill next 15' interval

Interval 100' - 115' BCS

100' - 105' Fine to medium sand, silt. w/

some gravel, few rock fragments.

105' - 110' Fine to medium sand, gravel and

rock fragments. Abundant gravel

and rock fragments w/ fine sand.

Coarse sand to medium sand, gravel

and rock fragments

110' - 115' Medium to fine sand w/ some coarse sand, gravel and few rock fragments. Mostly coarse sand to medium sand and gravel.

1150 Complete drilling 15' interval. Drillers preparing next 15' interval for drilling.

EP takes M.H. to hotel to deposit. Reclaim.

EP calculates target depth for PVC well and screens.

203.68' Amse

138.60'

141.60' BCS

148.60'

154.63' TD

Total length of 10' screen plus all  
15 sections of 4" PVC is 160.72'

There fore for bottom of screen to be  
at 149.63' BLS, there will be 11.1'  
above land surface.

1220 Drillers complete Attaching next 15' interval

Begin to drill Interval 115'-130' BLS

115'-120' Sand, silt, and gravel. Mostly  
a fine to medium sand and silt  
w/ gravel and few rock fragments

120'-125' Sand, silt and gravel. Medium to  
fine sand w/ gravel and few rock  
fragments.

125'-130' Medium sand w/ fine sand and

gravel. Mostly a medium sand  
and gravel

1243 Complete drilling 15' interval

Drillers break for lunch.

1320 Drillers begin to weld next 15' section  
onto drill string.

E.P. runs field CC Analysis on soil  
from 130' BLS interval.

Begin drilling next 15' interval

Interval 130'-145' BLS

130'-135' Medium to fine sand w/ silt  
and gravel. Mostly medium sand  
and rounded gravel

135'-140' Medium to fine sand and  
gravel

140'-145' Medium sand and gravel. Some  
fine sand, mostly medium sand w/  
some small rounded gravel. Sand  
becoming moist with some steam  
near very bottom.

1418 Complete 15' interval. Drillers attaching

last interval and will drill it 10' BLS  
for a total depth of 155' BLS.

Skies becoming very dark. Thunder  
storms may be moving into the  
area soon.

1420 EP takes 145' BLS sample and  
conducts field GC analysis. Moving  
in second sealable drum for cuttings  
from 02-001 MW. Drilling seal from  
130' BLS to TD for drum storage  
area awaiting analytical results.

1430 Wind kicks up big and thunder and  
lightning in the area. Stop work  
and move away from the rig to  
see if rain will blow over.

1515 Rain is over and drillers go back  
to the rig and begin to work test  
interval on the drill string.

1535 Begin to drill test 10' interval.

Interval 145' - 155' BLS

145-150 Medium sand, fine sand and

gravel. Mostly a medium sand

and gravel, wet sand and silt.

150-155 Sand, medium sand and some

fine sand and gravel. Most

sand and silt.

And clay at the bottom.

1548 Complete drilling. TO at 155' BLS.

Obtain sample for field GC analysis from  
cuttings from 155' BLS.

Drillers blow out the hole. Fine sandy  
mud with gray clay coming from  
hole. Into the top of a silty clay.

1555 Drillers add water to hole as they shut  
the air off. Since we are in clay,  
we do not expect a lot of sand here  
at the hole so we will minimize  
the amount of water added to the  
hole.

Drillers begin to pull out drill  
string.

1603 Stop adding water. water flow at  
1 gal / 36 seconds i.e. 14 gallons  
added to the well.

Drillers continue to extract drill pipe.



1615 Complete by pulling air hammer.  
Prepare to run split screen sampler  
to obtain aquifer material sample.

1623 Run down spec. Obtain aquifer material.  
Mostly a fine sand, silt and clay  
with light gray clay and brown sand  
and silt.

Pip (spec. opening) 0.010 in.  
Collected a sample for field GC.

1628 Begin to assemble PVC well.  
EP and B.II don latex gloves and  
assemble end cap and 10' screen  
(4" ID, Schedule 40, 0.010 slotted).

Will add 15 additional sections at  
approx 10' lengths (measured previously)  
for a total PVC well string of 161.22'.

Subtract the end cap and the bottom  
of the well screen is at 160.72'.

Will set the well at 148.6 to 138.6'  
BGS for the screened interval.

Therefore, we will set the screen and  
PVC casing with 12.1' remaining above  
the land surface.

1642 Complete setting the well. It hangs  
at 12.1' above land surface. Sounding  
the total depth, there is 4.8' below  
the bottom of the screen. The  
clay prevented much sand from in  
the well. Cut 6.1' from PVC well.

Drillers are adding #2 washed gravel  
sand pack to seal the bottom of the  
well. Add 2.5 bags of (100lb)  
sand pack.

1655 Begin to attach O-DEX extractor  
to O-DEX casing to begin the  
process of extracting the O-DEX  
casing.

Bottom of O-DEX casing 155'  
Bottom of PVC Screen 148.6'  
Top of PVC Screen 138.6'  
Must extract O-DEX casing 18'.

1735 Complete welding Extractor to O-DEX casing  
Begin to extract the casing.

PVC well begins to settle, falling 2.2' with the begin of the extraction.  
Start Turn off air hammer and attach a line to the well to return it to optimum settings.

1745 Attach a line to the well and re-engage the O-DEX extractor and lift the well back to original elevations.

Adding #2 W.G. sand pack to stabilize the bottom of the well. Add  $\frac{1}{2}$  bag of gravel and well stabilizes.

Continuing to extract O-DEX casing.

Add 1 bag of #2 W.G. as O-DEX is being extracted.

1838 Lift O-DEX casing to 14.8'. Must stop to cut casing and re-attach.

extractor.

1848 Remove 13.8' of O-DEX casing with a surface MP of 1.0'. Therefore

$159' - 13.8' = 145.2' - 1.0' = 144.2'$   
Bottom of O-DEX casing at 144.2' BLS

PVC MP is 5.90  $\therefore$  with a PVC string of 154.62 - 5.90, screen interval is 148.7 - 138.7' BLS

Gravel pack is sounded to be at 138' BLS. Will not need to add gravel during final O-DEX casing lifting.


Will lift casing an additional 7.5'.

1910 Complete attaching the O-DEX extractor to the casing to complete extraction.  
Begin to pull casing.

1930 Complete pulling O-DEX casing



02-001 MW




Approximately 7.5'

Drillers decide to bring out a steel saw to cut casing in the morning. We will quit for the day and cut O-DEX casing in the morning.

Drillers begin to secure the site for the day

1948 Drillers and E.R. depart the site



Evel E. Lark 5/12/94

10.3 hrs

FRIDAY

DAY 37

13 May 94

0800 E.O. arrives at the site. Sends daily progress report to Lee Perry (ANCC/CWR).

0900 Drillers arrive at the site.  
Discuss daily activities. Make them aware of increased activity around the station today in preparation for the Station's drill weekend coming up.

Weather: Sunny and mild. Temp 61°  
11: Mid 70's. Sunny and breezy with "South winds from 10-15 mph.

0915 Drillers begin to cut O-DEX casing to remove Extractor and complete activities at 02-001 MW.

0940 O-DEX extractor is removed. Measure current PVC MP.  
PVC MP is 4.2' above land surface.  
Therefore: PVC total length 154.62'

Bottom of Screen. 150.42'

Screened interval is

150.42' BLS TO 140.42' BLS  
OR

53.3' AMSL TO 63.3' AMSL

Cut 7.5' from O-DEX casing  
Top of O-DEX casing pushed to 0.3' BLS. Bottom of O-DEX casing at 137.7' BLS or at 65.98' AMSL.

Adding 3/4 bag of #2 W.G. to sand pack. Sand top of sand pack at 135.7' BLS or at 67.98' AMSL.

Add Bentonite pellets 1/2 (100 lbs) Ad hydrate w/ water. Top of Bentonite seal is 133.8' BLS or 69.90' AMSL.

1035 Complete well setting at 02-001 MW.  
Begin to mix grout to grout well to surface.

1110 Mixing Bentonite grout to be mixed into the well. Mix 2 Bags of grout in mix tub and add to well.

1130 Mix another 2 bags of Bentonite grout and add to 02-001 MW.

Well takes  $\frac{1}{2}$  of the tub. Grouted to the surface. Looks like the well was successfully grouted.

Putting  $\frac{1}{2}$  tub of grout on a pallet to get Station personnel to get a Forklift and move the tub to the next MW to grout (01-001 MW).

1145 Forklift operator at lunch. Drillers take lunch.

Begin to clean up at 02-001 MW. Driller cut PVC casing below land surface and place vault box by well for

installation. Vault boxes will be installed and cemented at all wells on Monday after the grout has a chance to set up.

1240 Forklift operator moves grout to 01-001 MW. Drillers move rig and equipment to 01-001 MW to grout the well.

1255 Drillers remove  $\frac{1}{2}$  tub of grout (1 Bag) into well. Begin to mix an additional bag.

1315 Begin to mix and grout 1 bag (2 bags) of grout to complete 01-001 MW.

Pour grout to just below surface. Grout to about 3' BUS. Will move to grout 03-001 MW.

1330 Drillers moving rig and equipment to 03-001 MW to grout the well.

John Barnes (Jr) prepares to cut PUC casing at 01-001 MW below land surface while others move equipment to 03-001 MW and begin to mix grout.

Clean up around 01-001 MW as drillers move off.

1350 Drillers mix grout at 03-001 MW.

John Barnes cuts PUC at PS 2 below the land surface.

EP cleans up Area Around PS 2 and 01-001 MW.

1420 Drillers tremie 1 tub (2 bags) of benchmark grout in 03-001 MW.

Begin to mix A-Second tub Mixing 1 Bag of grout (1/2 tub).

1455 Begin to tremie grout into 03-001 MW.

Fill the hole to the surface. Have some gravel left over. EP and Bill take grout to 01-001 MW and PS 2 location to fill level of grout to the surface in these locations.

1515 Drillers begin Maintenance on rig and consolidate equipment.

EP moving empty sealable drums to the Monitor well locations to be used to drum development water for well development on Monday.

Continue to clean-up At MW locations.

1610 Drillers complete cleaning up and securing equipment for the weekend. Drillers will complete surface completion (Valve box and Cementing) on Monday as well as well.

development. Drillers prepare to depart the site.

1620 Drillers depart the site.  
E.P. finishes clean-up at the sites and securing the well heads for the weekend. Preparing to obtain water levels.

1630 Obtain water levels from all wells.

02-001 MW    WL = 141.36  
MP = + 0.20  
141.56    (62.12)

PS 3.    WL = 141.33  
+ 0.20  
141.53    (61.82)

1642 Attempt to obtain WL from 03-001 MW.  
Drillers cut the PUC casing below land surface and apparently allowed some grout to get inside the PUC casing.

unable to determine how much.  
Cannot look into well to see.  
Grout coats the side of the casing and makes probe stick trying to go down.

1655 After many attempts and cleaning the probe. Obtain a good water level. Does not appear grout is at the water. Probe is dirty from 25' BLS to 50' BLS approximately.

03-001 MW    WL = 139.43  
MP + 0.20  
139.63    (61.71)

1703 01-001 MW    WL = 141.84  
+ 0.40  
142.24    (62.23)

1708 Attempt to obtain WL from PS2.  
Grout in the PUC well at a 20' BLS with not permit probe to go down.




1720 Clean out van and pack equipment.

Went to pay-phone to call John Morris (Optech) to inform him of grout situation in 03-001 MW and PS2.

1745 Departed the site to go to hotel to phone drillers concerning grout in the wells.

1800 Call Walter Reservoir. No one in so I leave a message concerning the grout in the wells.

1815 Phone John Morris (Optech). He states he will be stopping by Reservoir on Monday to meet with drillers concerning the grout in the wells.



Earl E. Felt 5/13/94 (9.7 hrs)

Saturday DAY 38 5/14/94

0810 Receive a call from John Brown Sr of Walter Reservoir. He received my message and returned my call.

Discussed the grout situation at the wells.

I believe grout got into 03-001 MW when the driller cut the PVC casing below the land surface ~~at~~ which was below the level of the grout. Once the cut was made, an undetermined amount of grout flowed down the inside of the casing.

PS2 grout got inside the well when the driller was cutting that PVC below the land surface. I believe he attempted to break the uppermost PVC interval above the grout level (unscrew the upper section)

to cut it and replace it. However, he unscrewed an internal below the grout level. Once that seal was broken, some grout sprayed into the PVC casing before he screwed it back.

This grout is at an undetermined interval inside the casing but somewhere in the 25' BGS interval.

I informed John Barros of our concerns that the wells may be damaged beyond repair and that

John Morris would be at the site Monday afternoon and to should be there.

I will call Ed Palma at Big Apple Teching and inform him of the situation and he should also be at the site on Monday afternoon.


Pat Narsu (Land Surveyor) was not at

the site on Friday so he will be out Monday or Tuesday to be lined out in survey requirements.

MyTest (Laboratory) will have round 2 water sample kits ready for Monday.

Hermit, water tests (Slug test) equipment arrived today at the hotel for Tuesday (as scheduled) slug tests.

Spending the afternoon preparing paper work and reconciling my expenses so far for this trip.




Seal E. Lantz 5/14/94 (6 hrs)



Sunday Day 39 5/15/94

Pick up Joe Byrd at  
LA Guardia Airport at 05:30pm  
to assist at the Reslyn SI



See E. L. 5/15/94

Monday Day 40 5/16/94

CRCO E.P. And Joe Byrd (JB) go to NY Test  
And pick up sample kit for water  
samples. Obtain 7 bottle sets for  
water samples.  
1) 01-001 MW  
2) 02-001 MW  
3) 03-001 MW  
4) Base Water Sample  
5) Equipment Blank  
6) WMS  
7) WMSD

CEIS Obtain ice for sample preservation.

CE30 Arrive at the Site. Inspect well locations.  
All looks fine.  
Attempt to obtain water level at  
03-001 MW.

Tape spools down with absolutely no  
problem. Obtain good water level  
and tape comes up clean.

WL = 139.05 + 0.20 MP  
139.35' as (61.99')  
rmsc

Trying to obtain water level at PS 2.

Tape goes down with absolutely no problem. Gives up clean. No grout.

PS 2  
WL 143.83 (+0.00 MP) (62.57')<sup>AMSC</sup>

Illness to 01-001 MW

WL 141.65 + 0.30 = 141.95 (62.52')

Move to PS 3

PS 3

WL 141.15 + 0.10 = 141.25 (62.10')

02-001 MW

141.18 + 0.20 = 141.38 (62.30')

0920 Go to office to call San Antonio to get John Morris arrival time for New York.

Send daily progress report to Lee Perry at AMRC/CEUR

0940 E.P. and J.B. go to 03-001 MW to run a bailer down the well to check condition of well and see if any grout is left in the well.

Drillers are at the site. Loading up equipment.

1020 John Morris Jr moves pump to 01-001 MW to develop that one first.

Setting up pump and preparing 01-001 MW for development.

01-001 MW

WL = 62.52' AMSC

Bottom Screen = 53.50' AMSC

Well Volume =  $(0.0408) \times (4'')^2 \times (9.02')$   
= 5.88 gallons

3 Well volumes = 17.7 gallons

Water added during construction = 32.5 gallons

Will develop at least 40 gallons. Pump and hose cleaned w/ DI water and Methanol.

1125 Begin to lower pump into well lowering pump to 149' bcs (20' from bottom screen)

1140 Everything is set. Calibrate Hydraz PH using 7.0 and 10 pH Buffer solutions

Begin to Develop?

Time	Temp	PH	Initial
11:48:00	70°	2.89	10.30
11:48:30	70°	2.89	8.84
11:53:00	60.2°	2.54	21.2 gal
11:54:45	58.8°	2.61	31.8 gal
11:56:00	58.3°	2.55	37.1 gal
11:58:00	58.3°	2.51	42.4 gal

Obtain water for picture.

Shut off pump After 44.5 gallons developed. Avg pump rate was 4.5 gal/min.

Temp in F° Fahrenheit

Cond is at (x100)

Water cleaned up well during development

WLC at 12:08 is 141.98' bcs

11:50 Moving to 02-001 MW for development. Pump and hose cleaned w/ DI water and Methanol. Lower pump into well and set at 148.5' bcs. Will develop at least 30 gallons.

12:19 Everything is set. Calibrate Hydraz PH using 7.0 and 10 pH Buffer solutions

Begin to Develop

Time	Temp	PH	Initial
12:20:00	68.6°	2.43	7.33
12:27:00	62.8°	2.42	7.65
12:31:00	62.7°	2.43	7.37
12:33:00	61.0°	2.44	6.90
12:35:30	59.5°	2.45	6.55
12:38:00	60.2°	2.45	6.73
12:41:30	61.8°	2.56	6.61

Shut off pump after 64 gallons developed.

Temp in F° Avg pump rate was 3.0 gal/min

Conductivity at (x100)

Water cleaned markedly during development

Continued to develop to get water as clear as possible.

1255 Moving to 03-001 MW. Pump and hose cleaned with 01 water and Methanol. Lower pump into well. Setting pump at 145' BLS. Will develop at least 50 gallons.

1325 Everything is set. Calibrate Hydrex using 70 pH and 100 pH buffer solutions.

#### BEGIN TO DEVELOP

Time	Temp	Pressure	Flow	Initial
13:29:30	73.1°	1.66	8.10	Initial
13:30:00	66.1°	1.37	7.33	21.2 gal
13:38:45	61.6°	1.28	7.12	31.8 gal
13:41:00	61.3°	1.26	6.88	42.4 gal
13:42:30	61.3°	1.24	6.95	47.7 gal
13:44:00	61.3°	1.24	6.90	53.0 gal
	(T)	(Cond)	(pH)	(Volume)

Shut off pump after 53 gallons developed. Any pump rate was 3.7 gallons/min.

Temp in Fahrenheit

Conductivity at (x100)

Water cleaned up very well during well development.

Drillers complete well development. Decontaminate equipment and begin to clean up.

1410 Drillers begin to construct the flush surface mounts at the well heads.

E.O. and J.B. prepare to conduct round 1 of groundwater sampling.

Obtain groundwater levels from the Monitor wells to check for stabilization following development.

WLS

01-001 MW	144.97'	(62.50)	<-0.02'
02-001 MW	141.39'	(62.29)	<+0.01'
03-001 MW	139.88'	(62.96)	<-0.03'

1425 Move to 01-001 MW to sample.

First bailer into drum.

Collect VOC, SVOC, TPHAC, Cyanide,

Pest/PCB, Metals in 7 bottle Set.

1440 Move to dcon area and dcon  
bailer.

John Meins (Optech) at the  
Station. Talking to Ed Palma  
(Big Apple) to check progress  
of field work.

1510 Move over to 02-001 MW to  
collect Groundwater sample.

1530 Collect Groundwater samples. First bailer  
into development water drum. Collect  
VOC, SVOC, TPHC, Cyanide, Pest/PBB,  
Metals in 7 bottle set.

1548 move back to dcon area to clean  
bailer and prepare to collect sample  
from 03-001 MW.

1620 Begin to collect GW samples from  
03-001 MW. First bailer into  
drum. Collect - VOC-SVOC-Pest/PBB-  
Cyanide, -TPHC, Metals in 7  
Bottle set.

1640 Collect MS samples from 03-001 MW  
QA/QC MS sample collected for  
All compounds in 7 Bottle Set.

1700 Collect MSD samples from 03-001 MW  
QA/QC MSD sample collected for  
All compounds in 7 Bottle Set.

1720 Conclude sampling in Monitor wells.  
Decon bailer and collect the  
Equipment Blank (Rinsed Blank).

Collect for All compounds in the  
7 Bottle set. Using lab provided  
De-Ionized water in a Bottle to  
Bottle transfer procedure.

1740 Collect Station water for analysis.  
Using valve on Bldg 17. (North side).  
Source of water during well  
construction. Collect Station water  
for Analysis of All target  
compounds using 7 Bottle Set.



1755 Begin to prepare Chann-ct-Cashody  
and insure packing and accountability  
of all samples.


J.B. and John Miner begin to pack  
equipment.

1820 Drillers complete flush ment  
on all well heads (3 MW and  
2 PZ's).

E.P. and J.B. close by all well heads  
to check the work.

1825 Depart the station to go to NYTEST to  
deliver samples.

1830 Transfer all water samples to NYTEST.  
Depart for Hotel

  
S. E. F. 5/16/94 10.5 hrs

TUESDAY DAY 41 17 May 94

0800 Arrive at the Station.  
E.P. calls Lee Perry to inform him  
on status and progress.  
Prepares and fixes daily progress  
report to AMERICEUR

J.B. prepares the Field GC for  
operation and begins to perform  
maintenance and clean-up on  
equipment to be shipped back  
today.

0900 E.P. continues to consolidate  
information and compile project  
reports.

0920 Begin to organize equipment in  
van as to make place for the  
slug tests.

1100 Depart station to return Air truck  
to Air-weld.

1140 Break for lunch.

1240 Return to Station. Begin to set up  
Hermit to conduct rising head  
slug tests.

Set up over 01-001 MW.

Conduct Set-up on Hermit (Model SE 1000C)  
Input Transducer data. (From Transducer)  
Quad Coef. Linearity  $\phi. \phi 34$   
Scale  $2 \phi. \phi 871$   
Offset  $\phi. \phi 64$

Program Hermit w/ 100 Reference.

1330 Static water level: 142.27' BUS  
Slug placed after transducer. Allow  
w/ to fall back to static level.  
Conduct rising head slug test after  
well had stabilized.

- Data did not look correct. Rechecking

settings and test transducer.

- Had linearity scale as  $\phi. 6 \phi$   
instead of  $\phi. 66$ .

Reset and conduct rising head slug  
test.

1417 Completed rising head slug test at

01-001 MW. Data looks good and  
all settings were correct. Water  
level returned to static level and  
was stable. Slug test run time  
was 10 minutes.

1435 Break down and move to 02-001 MW

1450 Setting up over 02-001 MW. Checking  
setting on Hermit.

Obtain static water level: 141.62' BUS  
Place transducer in well. Place slug in  
well and allowing w/ to drop back  
to static level.



Conduct rising head slug test after well settled.

1520 Conduct slug test. Slug was not placed properly in the well. Will re-test the well. Check slug depth and allow the well to stabilize.

1545 Complete rising head slug test. Data looks good. Beginning to break down. Deco Slug for next location.

Moving to 03-001 MW.

1610 Setting up to 03-001 MW. Obtain a water level at 03:00 MW. Static water level = 139.64' BLS

Place transducer and slug into well. Allow well to move back to static water level before beginning test.

1618 Conduct rising head slug test.

Slug was not properly placed in water. Will re-configure well for another test.

1635 Test ready. Slug in water and well is stable. Run rising head slug test.

1652 Post test. The transducer was caught on the slug as it was pulled and affected the data. We will conduct another test but keep this data.

1710 Re-configure well for another test.


1715 Begin rising head slug test on 03-001 MW. Pull slug only enough to get it out of the water.

Data looks good. Complete testing the 3 monitor wells.

1740 Begin to pack up rental equipment to take it to FED-EX to send it back.

1755 DEPART STATION for FED-EX  
c. 4 hrs

1825 DEPART FED-EX Station to  
return to H&L



5/17/94 (9.5 hrs)

Wednesday	Day 43	18 May 94
0800	Depart H&L and arrive at NTEST to pick up sample kit for the days sampling	
0815	Arrive at the Station. Attempt to fix daily progress report to MARG/CEVE but the fix machine is down. E.H. and J.B. go to the site to prepare for 2 <sup>nd</sup> round of sampling.	
0830	John Barnes Jr. arrives at the site w/ submersible pump to pump the Monitor wells prior to sampling. Begin to set up over 01-001 MW to pump. E.P. and J.B. obtain a Water Level (01-001 MW) WL = 142.20' BLS Obtain a WL from PS2 WL = 142.72' BLS Well Volume at 01-001 MW = $(0.0408/\pi(4)^2 \times (8.8)) = 5.7$ gallons	

0900 Prepare to purge 01-001 MW.  
 Pump set at 149' BCS  
 Begin to pump. Will pump at least 18 gallons

	Temp	Cond	pH
09:14:30	55.3°	2.78	7.20
09:17:00	54.9°	2.69	7.13
09:19:30	55.0°	3.18	7.05
09:20:55	55.0°	3.18	6.95

Purging Complete. Pump shut off after 21.2 gallons. Purge water was very clear.

$T^{\circ}$  = Temp in Fahrenheit

Cond = x 100

pH = Calculated with 7 and 10 pH buffer solutions.

0930 Pull pump and decontaminate w/ DI water and Methanol. Move to next well, 02-001 MW

Obtain water level from 02-001 MW  
 WL = 141.58'

Volume of water in well is  
 $(0.0408) \times (4)^2 \times (8.82) = 5.8 \text{ gallons}$

Will pump at least 17.3 gallons.  
 Set pump at 148.5' BCS

0935 Begin to develop 02-001 MW

	Temp	Cond	pH
09:36:30	57.3°	3.27	7.22
09:40:00	56.6°	2.90	7.27
09:42:00	55.9°	2.75	7.05
09:44:00	55.6°	2.78	6.73

Purging Complete. Shut off pump after 21.2 gallons. Purge water was still only slightly silty following purging.

0950 Pull pump and decontaminate w/ DI water and Methanol. Move to 03-001 MW.

Obtain water level from 03-001 MW  
 WL = 139.76' BCS

Volume of water in well is  
 $(0.0408) \times (4)^2 \times (7.18) = 4.69$

Well pump at least 14.1 gallons  
Set pump at 145' BGS

1003

Begin to purge 03-001 MW

10:05:00	600'	1.66	8.30	Imperial
10:08:00	573'	1.47	8.07	10.6 gal
10:09:30	570'	1.45	7.63	15.9 gal
10:12:00	565'	1.43	7.53	21.2 gal

Purging complete, shut off pump after  
21.2 gallons. Purge water is very  
clear after purging.

1015

Diller is picking up pump. EP and  
J.B. prepare to sample wells

1030

Sample at 01-001 MW

WL = 142.20'

Obtain water for analytical analysis

1" Butler into purge drum

Obtain water for VOC, SVOC, TPHC, Metals,  
Cyanide, and Pest/PCBs.

1130

Sample at 02-001 MW

WL = 141.59' BGS

Conduct water sampling for VOC, SVOC,  
TPHC, Metals, Cyanide, Pest/PCBs

1230

Obtain Water Samples from 03-001 MW

WL = 139.72' BGS

Complete water sampling.

EP and J.B. close up drums at  
the wells and go to pack the  
box of supplies for shipment.

1300

EP goes to NY TEST to turn in  
water samples and relinquish custody  
of samples.

1340

Moving company arrives to take  
Equipment Boxes

1400

EP briefs Station Facility Manager  
on end of project. Gives keys  
to wells and provides outbrief.

1430

EP and J.B. depart the Station  
Check out of Hotel. Return Rental  
Van and Depart New York

ARRIVE IN SA. End Project 5/18/94

*Joe Esposito*




Sept 13 / TUE DAY / 413

Tracer

07:25 JA Arrived to the Base Target Personnel setting up to start (findup) soil Gas at site No 1

7:30 Earl, Myrna and I went to site No 3 to stake 2 more Soil Gas Points. GA Doe we are moving 2 points from site No 1 to site No 3, due to the fact that No. 1 is very clean, and there was a low hit in the side of No. 3



(CJA)


7:45 I am going to the Base CE office to request Capt. Johnson

to move some cars and equipment for us, so that Tracer can install their soil gas Survey Points in site 2 and the two additional ones in site 3.

7:50 Checking with Base personnel what equipment needs to be moved in both sites.

8:05 EP, MR, and JA will go to take water level measurements at a well next to the UST Gas canopy next to the Vehicle Mntc. Shop.

Site No 1



8:15 The depth to groundwater was determined to be at 19.54 ft. No obs were detected coming out from the well. Water could be seen with a mirror from the surface.

8:30 MR and JA start working on HRS. JA also checking on the soil Gas survey. EP leaves to the Lab to arrange things for the Lab analysis of samples.

10:55 Point 21 of the Soil Gas Survey is moved 1 ft to the south because (TRACER) they were not able to drill the pipe in. Maybe there was a boulder on the ground.

11:05 JA and MR noticed that another ARMY portable generator needs to be moved, so TRACER can install Gas point No 10 at site Number 3. JA will request Base personnel to move the generator.

11:15 Tracer personnel takes break for LUNCH. EP comes back to the Base.

11:45 Break for Lunch  $\frac{1}{2}$  hour

12:15 Back from Lunch.

13:10 JA leaves the site to pick up Zero Grade Air for GC.

15:45 JA got Back to the Base. Target personnel is working at site No 2. No major hits were detected at this site so far. They installed 5 points at site No. 2.


The two points that were moved from site No 1 to Site No 3 did not presented any hits. No major concentrations or no significant hits were encountered.

Site No 1 was finished Today.  
Tracer installed 17 points at  
this site today. Nothing significant  
was found at this site either.

15:50 EP, MR, JA determining the exact  
location of the points installed  
today at each site. The distance  
between points was measured  
with a Tape.

GA  
15:00 ~~Tracer~~ Tracer personnel starts  
wrapping up for the day.

16:35 JA, EP, MR Left the Base



JA JA JA JA JA

Sept 15 / Wednesday / 1993

07:35 JA arrives to the Base.  
Tracer is setting up to start  
soil gas survey at site No. 2

07:50 JA, EP, MR start locating the  
points where the soil borings  
and monitoring wells will be  
installed at ~~each~~ sites (1 and 3)

08:45 JA, EP, MR finished flagging  
MW's and boring locations.  
They will proceed to take the  
depth to groundwater at the  
well close to Building 16 (Next  
to the UST's).

08:55 The depth to groundwater was  
19.54' 73°

09:10 JA and EP leave the Base to  
pick up Methanol for cleaning

09:35 JA and EP get Back to the base



10:10 JA, EP, and MR start to determine the location of soil gas points at site No. 2. Soil borings and water well locations ~~where~~ at the site were also staked for future installation.

12:15 JA and MR leave the Base for lunch.

12:45 JA and MR get back to the Base.

14:00 Adolphia Co. Delivers the drums for cuttings and wastewater.

14:10 MR Leaves site to work on HRS


14:15 Soil Mechanics arrives to Base. EP and JA and Soil Mechanics personnel go over the locations on soil borings, wells, and piezometer to be installed at each site. All locations look OK to Soil Mech.

15:00 Soil Mechanics leaves the Base.

15:05 JA and EP meet with Captain Johnson. EP explains how things are developing.

JA

17:45 JA & EP leave Base.



Sept 16 / THURSDAY / 1993

8:30 JA arrive to base. MR LEP  
already there. It is raining  
and we cannot drill. We will  
wait a while.

IN-SITU, INC.  
1-800-446-7488 (BILL McCLARY)  
Call on 11 April  
Hermit 1000C

CALL Lab in New York  
ORDER BTEX Calorant

w/ MTBE.

• Called 29 March. They  
said they would call back

• "No" on CALIBRANT, "Yes" on  
DI WATER

0700 (CST) leave house for airport

1700 (EST) at hotel in Rashyn



Jan Byrd Jr

DAY 1

April 6 Wednesday

0800 Leave hotel

0815 at Station

Inventory supplies

0845 Go check site

0915 meet w/ CAPT. Johnson

1000 Mark sites for tomorrow

1115 Leave base. Go to hab.

1130 At Lab

1245 Leave Lab  
lunch

1330 Go to Air plane

1530 Breakfast Hotel

①

DAY 2

③

Thursday April 7

0730 Pack up equipment &  
Leave Harts

0745 On base.  
Set-up GC Room  
Decon Slinging & Caps

Drill crew arrives

0930 Set up field Decon area

Begin Drilling

(02-063BH, 01-002BH, 03-005, 04-001BH)

1430 Drilling ends  
Prepare Field, Equipment  
Blanks

1510 MARK BARRELS. Pack

Van

Labelled ALL FOUR BARRELS

Good Bye all

6.75



1550 leave base. Go to Lab  
to drop off samples

1630 Back at hotel

Jack Byrd Jr

9

Day 3

Friday 8 April

0900 Leave hotel  
0915 at Base

POLICE AREA

Site out & mark PZ sites  
& Monitor wells.

Meet with drillers &  
walk out sites.

1215 Leave base  
1230 At hotel for lunch

1445 leave hotel

1455 On Base

Close up for weekend

1600 Leave base

at Hotel

Jack Byrd Jr

4.8

3.5  
1.3  
4.8

5

Day 6

⑦

Monday April 11

0830 Leave hotel  
0845 On Base

Check out survey equip and  
Run elevations on auto

Decon VOA Vials

1210 Leave base  
Go to lunch

1400 Leave hotel  
1415 On base

Deconting VOA Vials

1618 Leave base

1630 At hotel

8 hrs

Drillers Dekey



Day 8

⑨

Wednesday 13 April

0730 Leave hotel

0740 On bus

Return to hotel for BTEX  
Std.

0800 On bus

Prep. for drillers arrival

0900 Driller arrives. No crew  
with him. They show

Decon drill rig

1120 Leave base go to lunch

1200 Back on base

1220 Set up rig on hole

1230 Safety mtg.

1240 Spud run

EP, JB, JB, WF

Get Fork lift operator & dump  
drums still the have tested

Clean. Stop drilling  
1400 Driller stop drilling

Must make adjustment to bit.  
They leave site with bit.  
Will be back tomorrow AM

1412 Take soil samples from  
cuttings and run through  
GC's determine if soil  
is clean or not.

Dump barrels of soil. Thor  
Tested clean

leave base

1530 Oth hotel

1540 Call INSIDE to order  
HERMIT 1000 C

1550 Done with call

7.7

Jack Byrd

DAY 9

11

Thursday 14 April

0730 Leave hotel  
0745 On base

Prepare for drillers arrival  
Waiting on drillers

0810 Driller arrives. He doesn't  
have right equipment. Leaves  
site to go back to yard

1000 Drill crew arrives. Begin day.  
preparations.

1005 Begin running equipment back  
into hole

1035 Hit bottom of hole. No progress  
Abandon hole. Move 20' & begin  
new hole

1045 Start on new hole

1130 Hit hard at  $\pm 70'$ . Pull out &  
move to 3rd location on  
same site. Will use smaller  
augers

13

1200 Lunch

1240 Back on base

Drillers spud in on new hole

1400 Test Oil-WATER INTERFACE Probe.  
Does not work. Will  
probably send back to  
HAZCO.


1430 Rig breaks down. Blows  
pop-off valve on hydraulic  
system.

Rig at end of run on this  
site. Will gear up for  
ODEC Rig for tomorrow.

Rig down. Police Area.  
Cover holes. Discuss plans  
for tomorrow.

1545 Drillers leave site

1600 At hotel



Joe Byrd Jr

DAY 10

15

FRIDAY APRIL 15

0740 LEAVE HOTEL  
0750 ON BASE

PREPARE FOR DRILLERS ARRIVAL

0900 JB IS TAUGHT GC BASICS  
BY ME

1000 GO TO DRILL SITE TO AWAIT  
DRILLERS

1030 NO DRILLERS.  
BEGIN TO LEARN GC WITH  
ME AS INSTRUCTOR.

1212 BREAK FOR LUNCH

1254 BACK LEARNING GC.

1345 DRILLERS ARRIVE. WOW!!  
THEY BEGIN UNLOADING EQUIPMENT

1430 CLOSE UP & PACK GC. GO WATCH  
DRILLERS PREP RIG.

1550 Leave base  
1600 at base

DAY 13

(17)

Monday 18 April

0745 leave hotel  
0800 ON BASE  
Set up GC. Since ME has  
returned to SATX, I will be  
GC operator.

0810 BTEX STD is at hotel.  
Will wait until driller  
arrives to determine if it will  
be needed. This bunch does not  
lead to optimism.

0815 Program GC.  
But Flow Adjustment knob does  
not work.

0910 CALL HAZCO. Determine what  
unit will be exchanged. Pack up  
equipment.

1130 DRILLERS ARRIVE. Begin working  
on Rig conversion to ODEC.

Joe Bygones

(19)

1145 I go to Fedex to drop off  
GE. EP stays with drillers  
to keep eye on them.

FEDEX didn't have HAZ-MAT  
Forms. Will return later

1245 lunch

1315 Return to base.

Drillers equipment has been  
delivered. Still preparing for  
drilling.

1430

Still waiting for air compressor  
to begin drilling.

1500

No compressor. Drill crew  
leaves

1530

Jeff arrives

We discuss situation

1606 Leave base

1815

at hotel

Realize we still need to  
drop off GC.

Go to FEDEX

1730 Back at hotel

Jack Byrnes

9.3



Day 14

(21)

Tuesday 19 April

0800 Leave hotel

0810 AT BASE. Leave EP to wait  
for drill crew. I go to  
FEDEX, because GC was not  
shipped last night.


0915 BACK AT BASE. WAITING ON  
AIR COMPRESSOR TO START  
drilling

0920 COMPRESSOR ARRIVES. BEGIN  
prep. for drilling

0940 SAND IN WITH ODEC.

1010 CALL HOTEL. NEW GC IS IN.  
Go to hotel.

1030 BACK AT BASE  
Set up GC.





1050 GAS FLOW 12 mL/min

~~TEST~~

1053 TEST

Field 30

Power 25

ALL events 0.0 0.0

ENTER > VALUES

1055

TEST

Field: 30

Power: 25

SAMPLE

CAL

Event 3

Event 4

Event 5

Event 6

Event 7

Event 8

8.0	10.0
0.0	0.0
0.0	100.0
0.0	0.0
0.0	0.0
0.0	0.0
0.0	0.0
0.0	0.0

GAIN 2<sup>nd</sup>  
WINDO ± 10%  
CHART 0.5 cm/min

Set: J Byrd JR.  
ROSLYN ANGUS

1100 PREPARE BTEX STD.  
MUST go to hotel to  
get STD.

NO. The compressor has  
Quit Running. CREW is TRYING  
to get it Running Again.

1210 Compressor is Running  
1215 " " Out

DRILLERS CALL REPAIRMAN.

1240 Lunch  
1310 Go to hotel & get BTEX  
1330 ON BASE

Compressor Mechanic is here & working on unit.

1345 Compressor is up & running. START DRILLING AGAIN.

1410 Go to room to Calibrate GC & make BTEx STD

BTEx STD: 10ml H<sub>2</sub>O DI  
5ul BTEx  
5ul MTBE

1430 Shoot BTEx(MTBE) STD #1

Flow Rate 12 ml/min

Analysis #1 J Byrd JR

Int. Temp 27 Roslyn ANG'S  
Gain 2 BTEx STD

NAME	PEAK	R.T.	AREA/PPM
UNK	1	30.8	844.9
UNK	2	49.1	1.3
UNK	3	74.3	4.9
UNK	4	112.6	211.0
UNK	5	143.3	4.3
UNK	6	303.4	10.7

25

1442 Shoot BTEx STD #2

Analysis #2 J Byrd JR

Int. Temp 27 Roslyn ANG'S

Gain 2 BTEx STD

NAME	PEAK	R.T.	AREA/PPM
UNK	1	30.8	766.3
UNK	2	49.1	716.3
UNK	3	74.1	2.5
UNK	4	117.4	139.6
UNK	5	143.3	1.6
UNK	6	303.4	3.6

1503 Shoot BTEx STD #3

Analysis #3 J Byrd JR

Int. Temp 28 Roslyn ANG'S

Gain 2 BTEx STD

NAME	PEAK	R.T.	AREA/PPM
MTBE	1		3.339 PPM
BENZENE	2		2.173 PPM
TOLUENE	3		1.861 PPM
E. Benzene	4		2.539 PPM
mP Xylene	5		2.028 PPM
O Xylene	6		1.975 PPM

# 1510 Clear Library

1515 AIR BLANK

ANALYSIS #4  
INT. Temp 28  
GAIN 2

Joe Byrd, Jr  
Roslyn ANG6  
AIR

UNK	1	30.8	731.1
UNK	2	74.1	29.0
UNK	3	118.2	48.3
UNK	4	143.3	72.5
UNK	5	303.4	470.5

# 1523 BTXE STD

ANALYSIS #5  
INT. Temp 28  
GAIN 2

Joe Byrd, Jr  
Roslyn ANG6  
BTXE STD

UNK	1	1.0
UNK MTBE	2	1.0
UNK BENE	3	3.9
UNK TOLU	4	223.0
UNK EBENZ	5	3.3
UNK MPXYL	6	7.2

# 1536 BTXE STD

ANALYSIS #6  
INT. Temp 28  
GAIN 2

J Byrd, Jr  
Roslyn ANG6  
BTXE STD

UNK	1	1.3
MTBE	2	1,218 ppm
BENZENE	3	1,056 ppm
TOLUENE	4	993.7 ppm
ETHYL benzene	5	1,048 ppm
MP XYLENE	6	1,102 ppm

# RENAMED LIBRARY

ANALYSIS #6  
INT. Temp 28  
GAIN 2

J B JR  
Roslyn ANG6  
BTXE STD

MTBE	1	1,000 ppb
BENZENE	2	1.0 ppm
TOLUENE	3	1,000 ppb
ETHYL Benzene	4	1,000 ppb
MP XYLENE	5	1,000 ppb
OXYLENE	6	1.00 ppm

1554 Shoot BTEX STD

Analysis # 7

INT. TEMP 28

GAIN 2

BTEX STD

MTBE	1	415.0 ppb
BENZENE	2	832.7 ppb
TOLUENE	3	1,021 ppm
ETHYLBENZENE	4	985.4 ppb
MP XYLENE	5	1,067 ppm
OXYLENE	6	980.4 ppb

CALIBRATE TO PEAK #2, BENZENE  
1,000 ppm

1606 GO TO RIG ABOUT  
TALK TO EP ABOUT  
FINE TUNING GC

(29)

1618 REDUCE AIR FLOW TO 8 ml/min  
INCREASE ANALYSIS TIME TO 500 sec.

1622 Shoot BTEX STD

Analysis # 8

INT. TEMP 28

GAIN 2

BTEX STD

UNK	1	41.5	10.4
TOLUENE	2	70.6	412.2 ppb
ETHYLBENZENE	3	111.6	26.31 ppm
UNK	4	217.9	3.9

1633 Shoot BTEX STD

Analysis # 9

INT. TEMP 28

GAIN 2

BTEX STD

UNK	1	41.0	7.8
TOLUENE	2	70.6	930.4 ppb
ETHYLBENZENE	3	110.7	37.8 ppm
UNK	4	217.9	3.7

1644 INCREASE AIR FLOW TO 15 ml/min  
REDUCE ANALYSIS TIME TO 400 SEC

1649 Shoot BTEX STD

ANALYSIS #10

INT. TEMP 28

GAIN 2 BTEX STD

MTBE	1	441.6 ppb
MTBE	2	661.2 ppb
BENZENE	3	1.994 ppm
TOLUENE	4	1.614 ppm
ETHYL benzene	5	794.2 ppb
MPXYLENE	6	1.424 ppm
O XYLENE	7	1.366 ppm

Shut down GC  
Go to Rig

1712 DRILLERS having trouble with pipe.  
ODEC has not been drilling very well.

HELP DRILLERS WITH RIG REPAIRS.

AIR VENTS ON THE BOTTOM OF THE  
BIT WERE CLOGGED WITH CLAY.

(31)

1838 Pipe back in hole.  
Ready to RESTART drilling

1900 Get joint down. At 40' BIS.  
Weld on next piece of casing.

1930 Begin drilling again

1940 Have this joint down.  
Set at 50',  
Drills. go home

2000 AT Hotel

Garbyudga

11.5

DAY 15

33

Wednesday 20 April

0745 leave hotel  
0800 ON BASE  
Set up GC.  
MAKE BTEX STD.

Air Flow: 13 ml/min

BTEX (MTBE) STD: 10ml H<sub>2</sub>O  
5ul BTEX  
5ul MTBE

0830 Calibration. Shoot BTEX STD

Analysis # 1 J BYRD JR  
Int. Temp 22 Roslyn ANG  
Gain 2 Calibration

MTBE	1	1,198	ppm
Benzene	2	803.5	ppb
Toluene	3	991.4	ppb
Ethylbenzene	4	461.4	ppb
mP XYLENE	5	306.7	ppb
O XYLENE	6	675.4	ppb



# CLEAR LIBRARY

35

0840 Calibration BTEX STD

ANALYSIS # 2 J Byrd JR  
INT. TEMP 23 Roslyn ANG6  
GAIN 2 CALIBRATION

UNK	1	1.0
UNK	2	927.3
UNK	3	4.2
UNK	4	114.7
UNK	5	3.3
UNK	6	6.8

0850 Change Air Flow to 10ml/min  
and Analysis Time to 500 sec.

I want to try to separate  
Ethyl Benzene & m-xylene peaks

0854 Calibration

ANALYSIS # 3  
INT. TEMP 23  
GAIN 2

UNK	1
UNK	2
UNK	3
UNK	4
UNK	5

0903 Change Air Flow to 14 ml/min  
and Analysis Time to 400 sec.

0909 Calibration BTEX STD

ANALYSIS # 4  
INT TEMP 24  
GAIN 2

UNK	1
UNK	2
UNK	3
UNK	4
UNK	5
UNK	7

BTEX STD

J. Byrd JR  
Roslyn ANG6  
CALIBRATION

3.1
1.0
3.1
1.3
3.4

CALIBRATION

4.0
56.7
11.2
699.8
2.1
527.8



⑪

9/17/93

0700 EP+MR ON SITE, WAITING  
FOR DRILLERS  
0710 JA ON SITE  
0745 DRILLERS ON SITE  
IT'S RAINING HARD, NEED TO  
DECIDE WHAT WE'RE GOING  
TO DO

0815 WATCH DRILLERS REMOVE  
AGARS (JA, MR)

0900 EP DECIDED TO STOP  
DRILLING AS FAR AS  
THE EQUIPMENT WILL  
ALLOW, JA+MR WATCHING  
THE DRILLING

0940 EP FOUND OUT H2O LEVEL  
IS AT 140 FT (57' ABOVE  
SEA LEVEL), WE ARE NOT  
DRILLING ANY FURTHER,  
DRILLERS CAN'T DRILL  
THAT DEEP, DRILLERS  
ARE TAKING OUT THE AGARS

⑫

1000 GROUTING BEGAN

(13)

9/20/93

0645 EP+MR ON SITE  
0705 DRILLERS ON SITE  
MARK, ROBERT  
0715 DECON SETUP

0820 SAFETY BRIEFING  
0830 BEGIN DRILLING

1230 LUNCH  
1245 DECON

1500 PUT THINGS AWAY,  
DO CHAIN OF CUSTODY

1630 MR, JA, EP OFF SITE

*Myrna Rodriguez* 9/20/93

MR DOES  
2030 HRS WORK  
2130 HRS WORK FINISHED

10.5 HRS

9/21/93

0700 EP+MR ON SITE  
0715 DRILLERS ARRIVE  
0720 SETUP DECON

~~0900 STARTS BUT PFS FOR~~  
~~SURVEYORS~~

0730 DECON TIME

1500 JA, MR, EP OFFSITE, GO TO  
LAB

1545 LEAVE LAB

*Myrna Rodriguez* 9/21/93

9 HRS

10.5 HRS

9/22/93

0800 MR DOING 6 HRS WORK

1030 MR ON SITE

1045 MR OFFSITE TO  
PICK UP JA, MORE  
HRS PHONE CALLS

1130 LUNCH

1230 ON SITE (MR, JA, EP)  
SETUP FOR  
HAND AUGERS  
1330 DECON

1430 MR OFFSITE, GOES TO  
LAB FOR SOIL  
CONTAINERS

1530 MR ON SITE

1700 JA, MR, EP OFFSITE

8 HRS Myrna Rodriguez

9/23/93

0930 JA + MR ON SITE  
1000 CAPT JOHNSON IN SITE  
SPOKE ABOUT WHAT IS  
BEING DONE TODAY  
1115 PICKED UP POLE DIGGER  
1130 DECON

1745 JA, MR, EP OFFSITE

1815 LEAVE LAB

9 HRS Myrna Rodriguez

9/24/93

0800 JA+MR ON SITE, WAITING  
FOR GROUTING CREW

0815 DRILLERS ARRIVE

0920 DRILLERS OFFSITE

CLEANUP TIME

1145 JA, EP, MR OFFSITE

1230 JA, EP, MR ON SITE

1240 JA, EP, MR OFF SITE

MR GOES TO LIBRARY  
FOR HRS

1800 MR BACK FROM LIBRARY

Myrona Rodriguez 9/24/93  
9 HRS

INVENTORY

YELLOW BOOKS 3  
SHARPIES 7  
STAETLER 5

9/25/93

1400 MR + JA GO TO  
LIBRARY FOR HRS  
WORK

1500 LEAVE LIBRARY

1800 MR + JA WORK ON GC

1900 STOP GC WORK

2 HRS Myrona Rodriguez

9/27/93

0800 MR, EP, JA ON SITE  
MR + JA TALKED TO AARONS  
ABOUT BENCH MARK LOCATION  
ON BASE, THERE IS NONE

0835 MET WITH SURVEYOR,  
WALKED W HIM + SHOWED  
HIM PTS (BH + SGS)

0920 SURVEYOR OFFSIDE

0950 EP, MR, JA OFFSIDE



0920 Go to drillsite to see if there is a 10gal syringe in VAN

0930 ~~Back~~ No Syringe  
CALL M.E. in SATX  
So that he can send us some

0945 DONE on phone with ME

BASE MAINTENANCE PERSONNEL ARE using a lot of mowers & blowers & other equipment whose exhaust is very heavy in this room.

Am discontinuing GC CALIBRATION until later when ~~the~~ the AIR will hopefully be clearer

0950 At Rig Drilling very slow. I suspect that AIR holes are clogged.

1010 Decide to cut casing and pull bit.

1130 Go to GC Room to continue calibration

1140 AIR Flow 0.14 m/min  
BTX STD CALIBRATION

ANALYSIS #	5
INT. TEMP	24
GAIN	2
CALIBRATION	
UNK	1
UNK	2
UNK	3
UNK	5
UNK	6
UNK	7
	4.7
	503.7
	1.0
	455.6
	1.2
	244.6

# 1145 CALIBRATION BTX STD

ANALYSIS # 6	INT. TEMP 24	GAIN 2	CALIBRATION
UNK	1		3.8
UNK	2		1.0
UNK	3		2.8
UNK	4		59.0
UNK	5		1.8
UNK	6		3.1

# 1155 AIR BLANK

ANALYSIS # 7	INT. TEMP 24	GAIN 2	AIR BLANK
UNK	1		4.4
UNK	2		217.8
UNK	4		120.9
UNK	5		301.6
UNK	6		40.3

# 1204 AIR BLANK

ANALYSIS # 8	INT. TEMP 24	GAIN 2	AIR BLANK
UNK	1		1.7
UNK	2		63.2
UNK	4		8.8
UNK	5		167.6
UNK	6		5.1

# 1213 CALIBRATION BTX STD

ANALYSIS # 9	INT. TEMP 25	GAIN 2	CALIBRATION
UNK	1		801.7
UNK	2		401.9
UNK	3		1.6
UNK	5		931.7
UNK	6		2.8



⑥

1310 JA OFFSITE

1330 FINISHED SITE #1 11.5

1340 READY TO START 2 PTS  
@ SITE #3

1420 REMEASURED PT. DIST @  
SITE #1, SGS CREW  
FINISHED 24 PTS TODAY

1640 EP, MR, JA OFFSITE

8 1/2 HRS

Mylene Rodriguez  
9/14/93

11.5

24

10

12.5

24

14.5

24

13

16.5

24

17.5

24

24

13

16.5

24

17.5

24

⑦

9/15/93

0730 EP, MR ON SITE  
SGS ALREADY IN  
PROGRESS

0745 JA ON SITE

0800 JA, EP, MR STAKING OUT  
MW, PZ, BH LOCATIONS

0845 JA, EP, MR FINISHED  
STAKING MW, BH, PZ SITES  
FOR SITES #1+3  
CAPT JOHNSON WILL LOOK  
AT THE SITES + GIVE  
US THE GO AHEAD LATER

0855 19.53' H<sub>2</sub>O LEVEL FOR  
OLD WELL

0915 JA, EP OFFSITE

0945 JA, EP ON SITE

1230 JA + MR OFFSITE FOR  
LUNCH

⑧

1255 JA, MR ON SITE

1300 JA, EP, MR AWAIT DRILLERS  
+ DRUMS

1400 MR OFFSITE, NEEDS TO CALL  
ABOUT HRS INFO

1600 MR FINISH HRS CALLING

8 HRS

Myrna Rodriguez 9/15/93

⑨

9/16/93

0815 EP + MR ON SITE, RAINY  
ON SITE

0930 DRILLERS ARRIVE, TIME  
TO SET THINGS UP

0940 SAFETY BRIEFING W  
DRILLERS

DRILLERS } ROBERT ROGERS (JR)  
DAVID VERNICK (DV)  
(BRETT T. BORNER (BB))

1000 SPOKE W CAPT JOHNSON  
ABOUT WHERE TO SET UP  
DECON

1100 WATCH DRILLING

A = 10' BLS  
B = 20' BLS

⑩

1130 CALIBRATING + SETTING  
UP GC

1230 JAY + MR. LEAVE SITE  
FOR LUNCH

1300 JAY + MR ON SITE

~~1340~~

1315 WATCHING DRILLING P2  
@ SITE # 3

1500 READY TO QUIT FOR  
TODAY  
90 FT + NO H2O!

EP, MR, JAY OFF SITE

6 1/2 HRS

*Mym Rodriguez* 9/16/93

1220 Lunch is over with the  
main tenance guys. Engines &  
exhaust is back in force.  
I go back over to rig

1230 Drillers are at 70'.  
Pick up next joint & weld  
casing

1300 Earl & I run get lunch

1350 Back at site. They have already  
drilled next 15' ft interval

1400 Begin to pull string to inspect bit.

1420 Go play with GC.

Air Flow: 14 ml/min

(41)

# 1425 Calibration BTEX STD

ANALYSIS # 10

INT. Temp 26

GAIN 2

CALIBRATION

UNK	1	2.0
UNK	2	1.0
UNK	3	3.3
UNK	5	2.6
UNK	6	5.5
UNK	7	1.5

# 1440 BTEX STD

ANALYSIS # 11

INT. Temp 27

GAIN 2

CALIBRATION

UNK	1	1.3
UNK	2	967.2
UNK	3	3.0
UNK	5	2.1
UNK	6	4.2
UNK	7	1.2

<< ABORTED ANALYSIS # 12 >>  
PLUMBER FELL ON ME

1450 CALIBRATION BTEX STD

ANALYSIS # 13  
INT. Temp 27  
GAIN 2

CALIBRATION

UNK	1	757.6
UNK	2	1.4
UNK	3	4.6
UNK	4	2.9
UNK	5	7.2
UNK	6	2.1

Set Library

1505 BTEX  
ANALYSIS # 14  
INT. Temp 27  
GAIN 2

BTEX

UNK	1	361.5
MTBE	2	408.0
BENZENE	3	498.9
Toluene	4	586.5
ETHYLB-MPX	5	1,483
OXYLENE	6	471.6

43

1516 Methanol  
ANALYSIS # 15  
INT. Temp. 27  
GAIN 2

Methanol

UNK	1	28.7
BENZENE	2	150.3
ETHYLB-MPX	3	87.26
OXYLENE	4	22.11

1527 BTEX STD  
ANALYSIS # 16  
INT Temp 27  
GAIN 2

BTEX STD

UNK	1	885.4
MTBE	2	382.5
BENZENE	3	500.5
Toluene	4	530.0
ETHYLB-MPX	5	1,566
OXYLENE	6	539.8



1538 BTEX STD

ANALYSIS # 17  
INT Temp 27  
GAIN 2

BTEX STD

UNK	1	560.1
MTBE	2	319.4
BENZENE	3	401.4
Toluene	5	345.9
ETHYLB-MPX	6	931.9
O XYLENE	7	306.3

1552 Return to Rig

They have stopped drilling for  
the day.  
Return to GC Room & shut it  
down

1610 LEAVE BASE  
1620 AT HOTEL

3

Joe Byrd

8.0 hrs

DAY 16

45

THURSDAY 21 APRIL

0745 LEAVE HOTEL  
0800 ON BASE

Set up GC. Need 100L syringe  
to make up BTEX STD.

0815 ON DRILL SITE, WAITING FOR DRILL  
CREW TO ARRIVE

0855 DRILLERS ARRIVE ON SITE.  
PULL OUT STRING. CLEAN UP DRILL BIT  
NEW COMPRESSOR ARRIVES.

Run in pipe.  
1000 Pick up west joint of pipe.  
Weld casing.

1045 Begin drilling again. Today  
we are starting at 100' BLS.

1110 CALL M.E. to find out when  
syringe will be here. He sent  
it FEDEX Reg. Overnight.

1130 AT 115' BLS. Welding casing

1245 AT 130' BLS.

Lunch (.7 hr)

1324 BACK AT BASE  
welding casing  
1415 DRILLING Again

1430 Go to front gate to talk to  
gate guard about our FEDEX  
Delivery.

1435 BACK AT RIG,  
1445 AT 145' BLS.

Add on next joint & weld casing

1517 Done welding casing  
Begin drilling next interval, to  
160' BLS

1600 TD at 158' BLS.

1635 Drillers leave site  
1645 leave base. Go to store to get  
rope for bakers

1707 AT hotel

8.7 hrs  
S. J. Byrd Jr

8.7 hrs

DAY 17

47

FRIDAY 22 APRIL

0745 Leave hotel  
0800 ON BASE  
Set up GC.  
Go get ice.

0830 PROGRAM GC.  
MAKE BTEX MTBE STD  
10 ml H<sub>2</sub>O  
5 ml BTEX  
5 ml MTBE

0855 BTEX CALIBRATION  
AIR Flow 11 ml/min

ANALYSIS #1 J BYRD JR  
INT. TEMP 24 Roslyn ANG  
GAIN 2 BTEX CALIBRAT

UNK	1	15
UNK	2	779.9
UNK	3	3.8
UNK	4	3.4
UNK	5	2.5
UNK	6	5.1
UNK	7	1.6



0903 Program Library  
CALIBRATE FOR Benzene

0908 BTEX STD  
ANALYSIS # 2  
INT. Temp 24  
GAIN 2

	BTEX STD
UNK	1
MTBE	1.5
BENZENE	808.3 ppb
TOLUENE	834.8 ppb
ETHYLBENZENE	733.0 ppb
MP XYLENE	740.3 ppb
	806.9 ppb

0919 Re Calibrate to Benzene

Prepare "DIRTY" sample.  
A mixture of gasoline & soil  
that was used last week

(49)

0930 GAS SOIL  
ANALYSIS # 3  
INT Temp 24  
GAIN 2

Soil wt.: 10g

GAS SOIL

MTBE	4	1.048 ppm
MTBE	5	902.0 ppb
Toluene	14	1.835 ppm
ETHYLBENZENE	18	1.048 ppm
ETHYLBENZENE	19	350.7 ppb
MP XYLENE	20	171.9 ppb
O XYLENE	21	1.961 ppm
O XYLENE	22	1.383 ppm

0945 BTEX STD

ANALYSIS # 4

INT Temp 24

GAIN 2

BTEX STD

MTBE	2	1.317 ppm
BENZENE	3	909.8 ppb
TOLUENE	4	774.0 ppb
ETHYLBENZENE	5	781.4 ppb
ETHYLBENZENE	6	1.618 ppm
O XYLENE	7	832.8 ppb

(51)

0955 AIR BLANK  
ANALYSIS # 5  
INT Temp 2  
GAIN 2

AIR BLANK

Benzene	2	16.61	ppb
Toluene	3	45.34	ppb
Ethylbenzene	4	55.47	ppb
Ethylbenzene	5	127.8	ppb
Oxylene	6	48.14	ppb

Put new pin in plotter  
on GC.

1020 AIR BLANK  
ANALYSIS # 6  
INT Temp 23  
GAIN 2

AIR BLANK

Benzene	2	3.794	ppb
Toluene	3	<del>15.03</del> 15.03	ppb
Ethylbenzene	4	8.952	ppb
Ethylbenzene	5	30.68	ppb

1037 Go to Rig. Help them with  
A chore. (BREAK APART a tool)

1110 Back at GC.

1112 BTEX STD  
ANALYSIS # 7  
INT Temp 23  
GAIN 2

BTEX STD

MTBE	2	829.8	ppb
Benzene	3	855.6	ppb
Toluene	4	600.7	ppb
Ethylbenzene	5	738.7	ppb
Ethylbenzene	6	1,494	ppm
Oxylene	7	764.0	ppb

1120 Check Library

53

1120 BTEX STD  
ANALYSIS # 8  
INT Temp 23  
GAIN 2

BTEX STD

unk	1	1.5
unk	2	424.4
unk	3	2.2
unk	4	1.7
unk	5	1.3
unk	6	2.7
unk	7	949.0

SAVE INFORMATION

1140 BTEX STD  
ANALYSIS # 9  
INT Temp 24  
GAIN 2

BTEX STD

MTBE	2	973.1 PPb
BENZENE	3	989.6 PPb
TOLUENE	4	1,108 PPM
ETHYLBENZENE	5	1,098 PPM
ETHYLBENZENE	6	2,297 PPM
O XYLENE	7	1,042 PPM

CALIBRATE

1153 AIR BLANK  
ANALYSIS # 10  
INT Temp 24  
GAIN 2

AIR BLANK

BENZENE	2	17.18 PPb
TOLUENE	3	68.51 PPb
ETHYLBENZENE	4	103.3 PPb
MP XYLENE	5	118.1 PPb
O XYLENE	6	89.9 PPb

1206 Goto Rig site

BRIDG soil samples back

1230 PZ-01 A

ANALYSIS # 11

INT Temp 24

GAIN 2

PZ-01 A

SOIL Wt.: 10g

Toluene

MP xylene

MP xylene

2

3

4

10.49 ppb

2.737 ppb

21.82 ppb

24.557

1240 PZ-01 B

ANALYSIS # 12

INT. Temp 24

GAIN 2

PZ-01 B

SOIL Wt.: 10g

Toluene

MP xylene

MP xylene

2

3

4

8.245 ppb

4.837 ppb

13.80 ppb

18.637

55

1250 PZ-01 C

ANALYSIS # 13

INT Temp 24

GAIN 2

PZ-01 C

SOIL Wt.: 10g

UNK

1

2.0

1300 ~~AIR~~ PZ-01 D

ANALYSIS # 14

INT Temp 25

GAIN 2

PZ-01 D

SOIL Wt.: 12g

UNK

1

2.3

1308 AIR BLANK

ANALYSIS # 15

INT Temp 24

GAIN 2

AIR BLANK

UNK

1

3.3

57

1327 BTEX STD

Analysis # 16

Int Temp 24

Gain 2

BTEX STD

MTBE	2	554.3	ppb
BENZENE	3	361.7	ppb
TOLUENE	4	401.6	ppb
MPXYLENE	5	235.4	ppb
MPXYLENE	6	523.8	ppb
OXYLENE	7	526.8	ppb
		1286.0	

1340 Go to Rig site  
Get sample of soil from  
the disposal pile to  
check background readings

1408 PILE DIRT

Analysis #

Int. Temp

Gain

Soil wt.: 20g

PILE DIRT

BENZENE	2	26.22	ppb
TOLUENE	3	27.16	ppb
ETHYLBENZENE	4	18.42	ppb
MPXYLENE	5	28.43	ppb
OXYLENE	6	5.688	ppb
		34.13	

1420 Go to PZ-01 area to  
police area & cleanup  
stuff

1450 Go to PZ-02 site

1530 Leave base

1545 At water

Jack Byrnes

8.0 hrs

DAY 18

59

SATURDAY 23 APRIL

0845 leave hotel

0900 On Base

check water level AL PZ-01

0905 Set up GC & make BTEX STD  
CALIBRATE GC

BTEX MTBE STD

10 ml H<sub>2</sub>O

5  $\mu$ l BTEX

5  $\mu$ l MTBE

AIR Flow 11 ml/min

Clear Library

0930 CALIBRATION

ANALYSIS #1

INT Temp 20

GAIN

CALIBRATION

UNK  
UNK  
"  
"  
"  
UNK  
"

1  
2  
3  
4  
5  
6  
7

2.8  
372.1  
2.5  
1.7  
1.0  
2.7  
661.8

# 0940 CALIBRATION

ANALYSIS # 2

INT. Temp 21

GAIN 2

CALIBRATION

UNK	1
UNK	2
UNK	3
UNK	4
UNK	5
UNK	6
UNK	7

1.9  
453.6  
2.7  
1.7  
1.1  
2.4  
714.9

SET LIBRARY  
CALIBRATE TO BENZENE

# 0955 BTEX STD

ANALYSIS # 3

INT. Temp 21

GAIN 2

BTEX STD

UNK	1
MTBE	2
BENZENE	3
TOLUENE	4
ETHYL BENZENE	5
MP XYLENE	6
XYLENE	7

1.2  
501.1 ppb  
638.5 ppb  
732.5 ppb  
753.3 ppb  
726.4 ppb  
729.9 ppb

(61)

1005 GO TO DIRT DISPOSAL PILE  
TO GET SAMPLES FOR  
BACK GROUND READINGS

## 1020 PILE DIRT C

ANALYSIS # 4

INT. Temp 21

GAIN 2

PILE DIRT C

SOIL WT.: 10g

UNK	1
TOLUENE	3
ETHYL BENZENE	4
MP XYLENE	5

501.1  
18.58 ppb  
23.27 ppb  
58279, 37.36 ppb

## 1030 PILE DIRT D

ANALYSIS # 5

INT. Temp 21

GAIN 2

PILE DIRT D

SOIL WT.: 12g

UNK	1
TOLUENE	2
MP XYLENE	4

2.0  
4.313 ppb  
15.57 ppb



(63)

1040 PILE DIRT B

ANALYSIS # 6

INT. Temp 22

GAIN

PILE DIRT B

SOIL WT.: 12 g

unk

MP Xylene

1

4

3.5

9.391 ppb

1050 PILE DIRT B Reshoot

ANALYSIS # 7

INT. Temp 22

GAIN

PILE DIRT B Reshoot

unk

1

1.6

1100 BTEX STD

ANALYSIS # 8

INT. Temp 22

GAIN

BTEX STD

unk

MTBE

BENZENE

TOLUENE

ETHYLBENZENE

MP XYLENE

O XYLENE

1

2

3

4

5

6

7

4.7

1.483 ppm

715.9 ppb

671.8 ppb

623.6 ppb

644.2 ppb

648.3 ppb

1292.5

1110 Go to PZ-02 for drilling

HAVE 1<sup>st</sup> 7' in ground

picking up next joint &

welding casing

1130 START DRILLING

7' → 22' interval

1140 Get soil sample for GC.

PZ-02 15'

2

T

SOIL WT.: 10g

1155 PZ-02 15'  
ANALYSIS # 9  
INT. Temp 22  
GAIN 2

PZ-01 15'

UNK	1	862.0
TOLUENE	2	6.636 ppb
ETHYLBENZENE	3	8.331 ppb
MPXYLENE	4	20.79 ppb

1205 Lunch (0.6 hr)

1240 AT drill site  
DRILLER is welding casing

1245 Begin drilling  
25' → 40' inter val

1250 TAKE cuttings sample

PZ-02 30'  
Return to GC room &  
Test sample

1300 PZ-02 30  
ANALYSIS # 10  
INT. Temp 23  
GAIN 2

SOIL WT.: 14g

PZ-02 30

UNK 1 2.5

1308 INT. Temp has RISEN 3° since this morning.

1310 AIR  
ANALYSIS # 11  
INT. Temp 23  
GAIN 2  
AIR

UNK 1 4.0

1316 BTEx STD  
ANALYSIS # 12  
INT. Temp 24  
GAIN 2

BTEx STD

UNK	1	2.7
MTBE	2	1,293 ppm
BENZENE	3	882.2 ppb
TOLUENE	4	975.6 ppb
ETHYL BENZENE	5	874.0 ppb
MPXYLENE	6	784.3 ppb
OXYLENE	7	849.8 ppb

67

1325 Calibrate GC

1330 PZ-OZ 30 Reshoot

ANALYSIS # 13  
INT. Temp 24  
GAIN 2

SOIL WT.: 14g

PZ-OZ 30 RESHOT

UNK	1	2	3	4	5	6
Benzene		2.2	14.00	40.72	30.15	45.18
Toluene						12.06
Ethylbenzene						
MPXylene						
O xylene						

1335 Go to Rig  
welding casing

1342 Begin drilling 40' → 55' interval

1352 Take sample PZ-OZ 45'

Go to GC Room

Prepare sample

1400 PZ-OZ 45'

ANALYSIS # 14  
INT. Temp 24  
GAIN 2

PZ-OZ 45'

UNK	1	3
Ethylbenzene	1.6	22.62

1412 Return to Rig  
welding casing

1430 Begin drilling 55' → 70' interval

1435 Take sample PZ-OZ 60'  
Return to GC Room to  
run sample

Prepare sample

1445 PZ-02 60'

ANALYSIS # 15

INT. Temp 24

GAIN 2

SOIL WT.: 20g

PZ-02 60

UNK

1

135.4

1455 RETURN TO RIG  
welding casing

1510 Begin drilling 70'-85' interval

1515 Take sample PZ-02 75

RETURN TO GC ROOM  
PREPARE SAMPLE

1527 PZ-02 75

ANALYSIS # 16

INT. Temp 25

GAIN 2

PZ-02 75

SOIL WT.: 20g

UNK

1

3.6

1535 RETURN TO RIG

Welding casing

1603 Begin drilling 85' → 100' interval

~~TAKE SAMPLE PZ-02 90~~

DECIDE NOT TO SAMPLE THIS  
INTERVAL

1610 GO TO GC ROOM TO SHUT IT  
DOWN

1615 BACK AT RIG

1645 AT 96'. NO RETURNS. SEEMS  
LIKE LOST CIRCULATION.

TRY TO PULL UP PIPE & IT IS  
STUCK.

1650 NOW IT IS BLOWING SAND  
LIKE THE DICKENS

DRILL DOWN TO 98'

1700 DRILLERS SHUT DOWN & LEAVE  
WE POLICE AREA

Leave BASE

1715 At hotel

DAY 20

(71)

MONDAY 25 APRIL

0745 Leave Hotel  
0800 On BASE

CALL IN-SITU. Must wait until  
0900 EST. We want to delay  
ARRIVAL of HERMIT until MAY 6

0810 TURN ON & set up GC.  
0815 CHRIS (equipment operator) is  
AVAILABLE to dump drums of  
soil.

0845 DRILLERS ARRIVE  
0900 CALL IN-SITU  
BILL McLEARY not in

Begin programming & calibrating  
GC. Build BTEX MTBE STD

Air Flow @ 11 ml/min

BTEX MTBE STD  
10ml H<sub>2</sub>O  
5µl BTEX  
5µl MTBE

Joe Byrdgr

1000 Go to Rig  
 Drilling 100' → 115' interval  
 1030 At 112' BLS.  
 Pick up next joint & well casing  
 1100 Get soil sample that has the vegetable oil in it that the drillers use to lube the drill b.t.

1108 Veg Oil  
 Analysis # 3  
 Int Temp 26  
 Gain 2  
 Veg Oil

soil wt: 20g

UNK	1	144.0
TOluENE	2	6.164 ppb
ETHylbenzene	3	14.56 ppb
MP Xylene	4	2448 ppb
UNK	5	7.3

0938	CALIBRATION	ANALYSIS #	INT. Temp	23	GAIN	2	CALIBRATION
unk	1	641.1					
unk	2	675.1					
unk	3	3.4					
unk	4	2.9					
unk	5	2.3					
unk	6	4.6					

Set LIBRARY  
 CALIBRATE to Benzene

0954	CALIB BTEX STD				
	ANALYSIS # 2				
	Int. Temp 24				
	GAIN 2				
					BTEX STD
<hr/>					
UNK	1	2.7			
MTBE	2	1,885	ppm		
BENZENE	3	1,022	ppm		
TOluENE	4	881.2	ppb		
ETHylbenzene	5	752.5	ppb		
MP Xylene	6	747.4	ppb		



1122 Int. Temp has risen 3°  
Recalibrate GC

1125 BTEX STD  
ANALYSIS #4

Int Temp 26  
Gain 2

BTEX-STD

UNK	1	3.4
MTBE	2	1.087 ppm
BENZENE	3	787.9 ppb
TOLUENE	4	721.4 ppb
ETHYLBENZENE	5	657.2 ppb
ETHYLBENZENE	6	1.282 ppm
MP XYLENE	7	203.2 ppb

CALIBRATE to Benzene

(75)

1135 BTEX STD  
ANALYSIS # 5  
Int. Temp 26  
Gain 2 BTEX STD

UNK	1	3.5
MTBE	2	1,327 ppm
BENZENE	3	924.6 ppb
TOLUENE	4	752.1 ppb
ETHYLBENZENE	5	645.8 ppb
MP XYLENE	6	638.0 ppb
O XYLENE	7	777.6 ppb

1145 Return to Rig

HAVE DRILLED 115' → 130' INTERVAL.  
Pick up next joint & weld casing.

ARE @ 128' BLS

1205 Begin drilling 130' → 145' interval  
1235 At 143' BLS  
BREAK FOR LUNCH (0.8 lunch break)



1324 BACK ON BASE

Pick up next joint  
DRILLERS ARE WELDING CASING

1335 Begin drilling 145' → 160' INTERVAL.

1400 TD @ 159' BLS  
Grab sample for GC

1415 PZ-02 160

ANALYSIS # 6

INT. Temp 26

GAIN 2

PZ-02 160

SOIL WL.: 30 g

UNK

MP XYLENE

1

3

127.8

5.238 ppb

1425 Return to Rig

POLICE AREA. Secure wellhead  
with marked drum. Dump  
drums of soil, sweep up AREA  
Load & move equipment.

77

1601 BTEX STD

ANALYSIS # 7

INT. Temp 25

GAIN 2

BTEX STD

UNK

MTBE

BENZENE

TOLUENE

ETHYL BENZENE

MP XYLENE

O XYLENE

1

2

3

4

5

6

7

90.2

791.0

919.5

898.5

758.0

725.4

927.9

ppb

ppb

ppb

ppb

ppb

ppb

1611 Shut down GC.

CONTINUE to move equipment  
to new site, PZ-03.

DRILLERS LEAVE SITE

1626 Go to PZ-02 to take

WATER LEVEL READING

Water at 144.46' BLS

1644 LEAVE BASE  
 GO TO FEDEX BOX  
 1700 AT HOTEL

DAY 21

79

TUESDAY 26 APRIL

0745 LEAVE HOTEL  
 0800 AT BASE

Set-up, CALIBRATE GC.

BTEX MTBE STD: 10 ml H<sub>2</sub>O  
 5ul BTEX  
 5ul MTBE

AIR FLOW RATE: 11 ml/min.

0821 CALIBRATION

ANALYSIS # 1

INL. Temp 21

GAIN 2

CALIBRATION

UNK	1	1.2
UNK	2	652.1
UNK	3	3.5
UNK	4	2.9
UNK	5	1.9
UNK	6	3.8

INCREASE ANALYSIS TIME  
 TO 450 s.

8.5 hrs

Jan Byrd Jr

0840 CALIBRATION

ANALYSIS # 2

INT. Temp 22

GAIN 2

CALIBRATION

UNK	1	2.6
UNK	2	357.1
UNK	3	2.1
UNK	4	1.3
UNK	5	919.9
UNK	6	1.9
UNK	7	594.8

Set LIBRARY

CALIBRATE to Benzene

0854 BTEX STD

ANALYSIS # 3

INT. Temp 22

GAIN 2

BTEX STD

UNK	1	1.4
MTBE	2	831.2 ppb
BENZENE	3	856.4 ppb
TOLUENE	4	840.1 ppb
ETHYLBENZENE	5	746.1 ppb
MP XYLENE	6	741.8 ppb
O XYLENE	7	719.8 ppb

GC is set. WAIT ON drillers.

0915 DRILLERS ARRIVE.

~~DO~~ CLEAN-UP GC ROOM while drillers prep rig for drilling

1100 DRILLERS ARE HAVING A PROBLEM with drill bit. It seems to have seized up.

1130 Spud in  
 1140 At 10' BLS. (0'-8' BLS interval)  
 Pick up next joint & weld casing

1215 Done welding. Begin drilling  
 10' → 25' interval.

1228 Take soil sample PZ-03 15'

PREPARE SAMPLE

PZ-03 15'  
 ANALYSIS # 4  
 INT Temp 23  
 GAIN 2

soil wt.: 20g

PZ-03 15'

NOTHING

1243 Go back to Rig

1300 lunch (0.6)  
 1336 AT Rig

1350 Begin drilling 25' → 40' interval  
 1353 Take soil sample PZ-03 30'

1400 PZ-03 30  
 ANALYSIS # 5  
 INT. Temp 24  
 GAIN 2

soil wt.: 20g

PZ-03 30

UNK 1 48.1

1415 Return to Rig.

Welding casing

1430 Begin drilling 40' → 55' interval

1435 Take soil sample PZ-03 45'

Recalibrate GC

1440 BTEX STD  
 ANALYSIS # 6  
 INT Temp 24  
 GAIN 2 BTEX STD

ABORT RUN

1450 BTEX STD  
 ANALYSIS # 7  
 INT Temp 24  
 GAIN 2 BTEX STD

UNK 33 2.4  
 MPBIE UNK 234.2  
 BENZENE UNK 1.2  
 TOLUENE UNK 687.9  
 ETHYLBENZENE 1065 ppm  
 MPXYLORE UNK 394.6  
 OXYLORE UNK 160.7 ppb  
 MPXYLORE

Reshoot BTEX STD

1500 BTEX STD  
 ANALYSIS # 8  
 INT Temp 25  
 GAIN 2 BTEX STD

UNK 1 2.7  
 UNK 2 433.2  
 UNK 3 2.1  
 UNK 4 1.6  
 UNK 5 1.0  
 ETHYLBENZENE 2.676 ppm  
 MPXYLORE 429.1 ppb

1515 BTEX STD  
 ANALYSIS # 9  
 INT Temp 25  
 GAIN 2 BTEX STD

UNK 1 890.6  
 UNK 2 331.4  
 UNK 3 1.8  
 UNK 4 1.3  
 UNK 5 874.0  
 ETHYLBENZENE 2.321 ppm  
 MPXYLORE 373.9 ppb

Calibrate to Benzene

1525 PZ-03 45

ANALYSIS # 10

SOIL Wt.: 20g

INT. Temp 25

GAIN 2

PZ-03 45

UNK	1	2.4
Benzene	2	16.12 ppb
Toluene	3	37.17 ppb
Ethylbenzene	4	27.39 ppb
MP Xylene	5	44.66 ppb
OXylene	6	9.717 ppb

1535 Return to Rig

Get sample PZ-03 60

Prepare sample

87

1543 PZ-03 60

ANALYSIS # 11

INT. Temp 25

GAIN 2

PZ-03 60

SOIL Wt.: 20g

UNK	1	2.6
Toluene	2	6.581 ppb
MP Xylene	4	4.127 ppb

1553 Return to Rig

DRILLERS ARE PACKING UP FOR THE DAY. Hole is at 70' BLS.

PACK up equipment & shut down GC.

1600 leave site

1604 ~~leave~~ site Take water level reading at PZ01 & PZ-02

Check day well

1630  
~~1620~~

LEAVE BASE

1643

AT HOTEL

DAY 22

89

Wednesday 27 APRIL

0748 Leave hotel

0800 ON BASE

Set up GC, CALIBRATE GC.  
MAKE BTEX MTBE STD

Air Flow Rate: 12 ml/min

BTEX STD: 10 ml H<sub>2</sub>O  
5  $\mu$ l BTEX  
5  $\mu$ l MTBE

0815 Go dump drums of soil

0905 DRILLERS ARRIVE

0928 CALIBRATION

ANALYSIS # 1

INT. Temp 24

GAIN 2

CALIBRATION

UNK  
UNK  
UNK  
UNK  
UNK  
UNK  
UNK

1  
2  
3  
4  
5  
6  
7

5.7  
435.7  
2.5  
2.1  
1.4  
2.9  
874.5

8.4 hr

Joel Byrd



0944 CALIBRATION

ANALYSIS #	2	24	2
INT. TEMP			
GAIN			
unk	1	301.5	
unk	2	318.4	
unk	3	1.8	
unk	4	1.2	
unk	5	840.9	
unk	6	1.7	
unk	7	548.0	

Set LIBRARY

CALIBRATE to Benzene

1000 BTEx STD

ANALYSIS #	3	25	2
INT. TEMP			
GAIN			
MTBE	2	1.349	ppm
BENZENE	3	1.328	ppm
TOLUENE	4	1.584	ppm
ETHYL benzene	5	1.67	ppm
MP XYLENE	6	1.622	ppm
OXYLENE	7	1.561	ppm

6 1010 Go to Rig

1015 Begin drilling 70' → 85' interval

~~Get soil sample PZ-03 7~~  
Will get soil sample for next interval

1030 Drilled to 83' BLS

Pick up next joint & work casing

1105 Begin drilling 85' → 100' interval

1109 Get soil sample PZ-03 90'

Prepare sample

1118 PZ-03 90  
 ANALYSIS # 4  
 INT. Temp 25  
 GAIN 2 PZ-03 90

SOIL WT.: 20g

ETHYL benzene	3	30.02 ppb
MP XYLENE	4	50.14 ppb
O XYLENE	5	10.81 ppb

1130 Return to Rig

Drilled down to 10' 98' BLS

Pick up next intervals & weld casing

1155 Begin drilling 100' → 115' interval

TAKE SOIL SAMPLE PZ-03 105

PREPARE SAMPLE

93

1208 PZ-03 105  
 ANALYSIS # 5  
 INT. Temp 25  
 GAIN 2 PZ-03 105

SOIL WT.: 20g

ETHYL benzene	2	7.667 ppb
ETHYL benzene	3	9.005 ppb

1220 AIR BLANK  
 ANALYSIS # 6  
 INT. Temp 26  
 GAIN 2 AIR BLANK

UNK 1

1227 Return to Rig

BREAK FOR LUNCH (0.6)

1303 ON BASE

CATCH UP ON PAPERWORK

1430 Return to Rig

1440 AT 145' BLS

Pick up next joint & weld casing

1507 Begin drilling 145' → 160' interval

1524 Take sample PZ-03 15<sup>th</sup> 15<sup>th</sup> 15<sup>th</sup>

Prepare sample

1530 PZ-03 155

Analysis # 7 Soil wt.: 22g  
Int. Temp at 2  
Gain PZ-03 155

UNK 1 66.6

Recalibrate due to Int. Temp increase

Talked to EP. Said it was not important since there was no reading on last sample.

(95)

1545 BTEX STD

Analysis # 8

Int. Temp at 27

Gain 2

BTEX STD

	1	2	3	4	5	6	7
UNK							
MTBE							
BENZENE							
TOLUENE							
ETHYLBENZENE							
ETHYLBENZENE							
MP Xylene							

1600 <sup>846</sup>SHUT DOWN GC.  
2468.6

Drilling is done at site PZ-03. Begin rigging down equipment

EP & JB survey in sites PZ-01, PZ-02, PZ-03

1630 Driller Leave site

FP & JB TAKE WATER LEVEL  
READINGS AT SITES  
PZ-01, PZ-02, PZ-03

1715 LEAVE BASE

1730 AT HOTEL

0745 LEAVE HOTEL  
0800 ON BASE

CHECK WATER LEVELS  
PZ-03, PZ-02, PZ-01

0900 LEAVE BASE  
0910 AT HOTEL

DAY 23

THURSDAY 28 APRIL

97

9.1 hrs

Joe Byrd Jr

1.5	hrs	ON BASE
9.5	hrs	TRAVEL
11.0		TOTAL

Joe Byrd Jr

DAY 40

99

Sunday 15 MAY 1994

TRAVEL TO

ROSLYN NY

(EST) 1000 Leave house for Airport

1840 (EST) AT Roslyn hotel

Jan Byrck

7.6 hrs

DAY 41

101

Monday 16 MAY 1994

0800 Leave hotel  
Go to Lab & get sampling equip.

0830 On Base  
Take water level readings  
on PZ's & MW's

0950 Call ABF Trucking to pickup  
cargo boxes on Wednesday 18 May  
between 11:00-14:00. Contact Bob

1030 Begin purging MW-001

1200 Move to MW-002. Purge.

1300 Move to MW-003. Purge.

1350 Set-up to sample MW-001  
Sample all wells

1815 Drillers leave

1820 Leave base. Take samples to  
Lab.

1845 At Hotel

Joe Byrnes

10.8 hrs

Joe Byrnes



DAY 42

Tuesday 17 MAY 1994

0800 leave hotel  
0815 ON BASE

Analysis Time: 450 sec

Calibrate GC 10mb H<sub>2</sub>O

GAIN: 2

Windo:  $\pm 10\%$

Chart: 0.5 cm/min

Gas Flow: 10 mlb/min

Over Temp: 40°C

0842 BTEX

ANALYSIS # 1

INT. Temp 23

GAIN 2

BTEX

unk  
unk  
unk  
unk  
unk  
unk

1  
2  
3  
4  
5  
6

118.1  
4.0  
3.4  
3.3  
7.4  
3.7

Set LIBRARY. Calibrate to

~~Toluene + Benzene~~

Toluene by mistake.

0902 Calibrate to Benzene. Checks

Out OK

103

0905 MW-001

ANALYSIS # 2

INT. Temp 23

GAIN 2

20 mb H<sub>2</sub>O

MW-001

unk

1

351.9 mVS

0918 MW-002

ANALYSIS # 3

INT. Temp 22

GAIN 2

20 mb H<sub>2</sub>O

MW-002

unk

1

1.2

Ethylbenzene

2

12.0 ppb

0926 MW-003

ANALYSIS # 4

INT. Temp 22

GAIN 2

20 mb H<sub>2</sub>O

MW-003

unk

1

1439 mVS



0935 BTX STD

Analysis # 5

Int. Temp 22

Gain 2

BTX STD

UNK	1	128.4
Benzene	2	956.7 ppb
Toluene	3	1.046 ppm
Ethylbenzene	4	1.081 ppm
MP-Xylene	5	1.085 ppm
O-Xylene	6	1.041 ppm

0945 Begin Cleaning room & packing boxes

1030 Go to Return Ultra Air  
1105 Done at Air Weld. Return to BASE

Take lunch (0.6)

1200 On BASE. Begin prepping for slug Test.

1220 At MW-001. Do slug Test

105

1504 Move to MW-002. Do Slug Test.

1600 Move to MW-003. Do Slug Test.

1745 Done at MW-003. Package equipment to Return to HAZCO.

1755 Leave BASE. Go to FEDEX.

1824 Leave FEDEX.

1840 At Hotel

10.1 hrs

Jack Byrd

DAY 43

Wednesday 18 MAY 1994

10754 leave hotel. Goto Lab to get sampling supplies

0815 AT BASE.  
Prep. to purge wells for  
Delayed sampling

0930 Done at MW-001. Move to  
MW-002. Purge

0955 Done at MW-002. Move to  
MW-003. Purge.

Done Packing

1040 Begin Sampling MW-001

1150 Done sampling.

1315 Done packing equipment  
EP goes to Lab to drop off  
samples. I wait for  
truck to ship equipment

107

1350 Load Boxes on  
ABF Freight Line Truck.  
Shipment # 289054221

1410 Inventory barrels

1420 leave base

1430 at Hotel

(est) leave hotel

(est) Home  
2140

6.6 on base  
7.6 TRAVEL  
14.2 hrs

Joe Brydson

part  
base  
of

# DRUM INVENTORY

109

ROAD

- ①
- ②
- ③
- ④
- ⑤
- ⑥
- ⑦
- ⑧
- ⑨
- ⑩
- ⑪
- ⑫
- ⑬
- ⑭
- ⑮
- ⑯
- ⑰
- ⑱
- ⑲
- ⑳
- ㉑
- ㉒
- ㉓
- ㉔
- ㉕
- ㉖
- ㉗
- ㉘
- ㉙
- ㉚
- ㉛
- ㉜
- ㉝
- ㉞
- ㉟
- ㊱
- ㊲
- ㊳
- ㊴
- ㊵
- ㊶
- ㊷
- ㊸
- ㊹
- ㊺
- ㊻
- ㊼
- ㊽
- ㊾
- ㊿

TRAILERS

- ① MW-003 WATER
- ② MW-003 WATER
- ③ MW-001 WATER
- ④ MW-001 WATER
- ⑤ MW-002 WATER
- ⑥ MW-002 WATER
- ⑦ MW-002 SOIL
- ⑧ MW-002 SOIL
- ⑨ MW-003 SOIL
- ⑩ MW-003 SOIL
- ⑪ BG-001 BH SOIL
- ⑫ 03-005 BH SOIL
- ⑬ 03-003 BH SOIL
- ⑭ 03-006 BH & 03-002 BH SOIL
- ⑮ 01-004 BH & 01-004 BH SOIL
- ⑯ 02-003 BH SOIL
- ⑰ 03-001 BH & 03-004 BH SOIL
- ⑱ 01-002 BH SOIL
- ⑲ 01-001 BH SOIL
- ⑳ DECON WATER
- ㉑ DECON WATER
- ㉒ 02-002-BH & 02-001 BH SOIL
- ㉓ 01-006 BH } SOIL
- ㉔ 02-007 BH } SOIL
- ㉕ 02-008 BH } SOIL
- ㉖ 01-004 BH } SOIL
- ㉗ 01-005 BH } SOIL



②

9/11/93 No Work

9/12/93 No Work

Myrna Rodriguez  
0 HRS

9/13/93 (3)

0740 EP + MR ARRIVE ON SITE  
TRACER RESEARCH ON SITE  
MET W LAWRENCE S. FROM  
TRACER + ROBERT

0750 SHOWED SGS PEOPLE THE  
SITES

0800 SAFETY BRIEFING

0820 SGS READY TO BEGIN  
GOING DOWN 5 FT

0845 3-2 SAMPLE TAKEN  
CLEAN

0850 PT # 3-1  
AL AARONS CAME ON SITE

0857 CHRIS HENCHEY (ELECTRICIAN)  
DN SITE

0920 REMEASURED SGS PTS.

1020 JERRY ARRIAGA (JA) ON SITE  
1030 FINISH SITE #3



CLEANUP TIME FOR SGS, THEY'RE  
FILLING UP THE HOLES (4)

1105 PREPARING ~~FOR~~ SITE #2.1

1115 BEGIN SGS FOR SITE #1

1145 BREAK FOR LUNCH, OFF  
SITE (EP, MR, JA)

1245 ON SITE (EP, JA, MR)  
CONTINUE SGS SITE #1

1300 HELPED EP MEASURE SITE #3

1500 FINISHED THE 20 POINTS,  
WE'RE CONTINUING  
20 MORE POINTS

1650 FINISHED FOR TODAY  
SGS OFFSITE, EP, JA, MR  
OFFSITE

Myma Rodriguez 9/13/93  
11 9 HRS



9/14/93 (5)

0725 EP + MR ON SITE, SGS HAS  
BEGUN

0735 JA ON SITE

0740 RELOCATED TWO PIS FROM  
SITE #3 TO SITE #1

0815 EP, JA, MR READY TO CHECK  
WELLS

19.54' FROM TOP OF  
CASING (H<sub>2</sub>O LEVEL)

0835 EP OFFSITE, JA, MR WORKING  
ON HRS USING CELLULAR  
PHONE + WATCHING SGS

1055 SGS CREW HAVE TO REDO  
PT., IT SEEMS LIKE THEY  
HIT ROCK

1145 EP, JA + MR OFF SITE  
LUNCH

1215 EP, JA, MR ON SITE

**THIS PAGE INTENTIONALLY LEFT BLANK**

**APPENDIX G**

**HRS DATA PACKAGE**

**THIS PAGE INTENTIONALLY LEFT BLANK**

**PRELIMINARY ASSESSMENT (PA) SITE INSPECTION (SI)  
DATA REQUIREMENTS FOR FEDERAL FACILITY DOCKET SITES**

**Roslyn ANGS, Roslyn, New York**

- \*1. Supply copies of all sampling data, on-site and off-site, including location map, detection limits (see definitions below), raw data sheets, QA/QC documents, date(s) sampled, analytical method(s) used, well or boring logs, and sampling technique(s).**

- \*2. Locate and identify on a map all known or suspected sources (see definition below). Supply all information about source(s) such as: dates of operation, use, or spillage; amounts of material deposited, stored, or spilled; dimensions of source(s); known or suspected hazardous substances (see definition below), etc.**

**\*This information can be found in Section 4 of the work plan.**

- \*3. Provide a description of all aquifers beneath the site, including description of overlying materials, depth first encountered, thickness, and composition.**


**\*This info can be found in Section 4.3.4 of the work plan.**

- 4. For each source, choose one description from Table 1 that describes the groundwater contaminant. Provide complete documentation (i.e., engineering diagrams, photographs [originals]) as to why the source meets that description and not any other in the Table.**

None of the source descriptions from Table 1 apply to this particular site.

- 5. Provide the location of all drinking water wells in all aquifers beneath the site in a 4-mile radius from the site (property boundary) by HRS distance ring and locate the wells within a one-mile radius on a 7.5-minute topographic map. Provide information on depth of well(s), screening interval(s), depth of aquifer(s) encountered, population served for multiple wells (i.e., municipal system), provide the number of wells, location of all wells (regardless of 4-mile limit), average annual pumpage of each well (regardless of 4-mile limit), and total population served by system. Include information on all standby wells.**

Three public supply wells in the Roslyn Water District are significant because of their proximity to the Station (Figure G.1). Wells N-5852 and N-4265 are located approximately 1,600 feet north-northwest and 1,000 feet northeast from the Station boundary, respectively. Well N-2400 is located approximately 1,800 feet south from the surface from the surface water retention basin (Nassau County NO. 72) receiving surface water runoff from the Station property. Each of these wells are screened in the principle



DRAFT  
FIGURE G.1

ROSLYN ROSLA-10

PUBLIC AND PRIVATE WATER WELLS  
WITHIN 1 MILE RADIUS OF ANG  
Roslyn Air National Guard Station  
New York Air National Guard  
Roslyn, New York

OPTECH  
OPERATIONAL TECHNOLOGIES  
CORPORATION

JULY 1994

Figure G.1



aquifer and were drilled to total depths ranging between 439 and 490 FBLs. Approved water yield capacities for these wells range from 1,000 GPM to 1,200 GPM.

Seven observation wells in the vicinity of Roslyn ANGS were also located and are shown on Figure G.1. Of these wells, three are in the upper glacial aquifer (N-09711, N-10246, and N-11672), three are in the Magothy Aquifer (N-09190, N-10732, and N-11732), and one is in the Lloyd aquifer (N-11574). Historical well information, sampling information, and chemical examinations, (including chemical analyses for Volatile Organic Compounds) for these seven observation wells are found in Appendix B.

According to the U.S. Geological Survey Water-Supply Paper, approximately 66 public wells exist within a 4-mile radius of the site.

6. **Provide information and location (on 7.5-minute topographic map) of wells within 4 miles that are used to irrigate five or more acres of commercial food or forage crops, or watering of commercial livestock, or ingredient in commercial food preparation, or supply for aquaculture, or supply for a major or designated water recreation area, excluding drinking water use.**

According to the U.S. Geological Survey Water-Supply Paper, approximately 88 domestic wells exist within a 4-mile radius of the site. Two of these wells can be found within a 1-mile radius from the site. (Figure G.1)


7. **Provide average number of persons per residence for county (or counties) that site is located in per the U.S. Census Bureau.**

The average number of persons per residence for county is 2.94 people per household. (Source: Nassau County Clerk)

8. **Identify and locate all surface water bodies within two miles of site, marking off the drainage routed (shown on 7.5-minute topographic map) from each source to applicable surface water bodies. Provide the average annual cubic feet per second flow for each surface water body within 15 miles downriver or radius from the point of probable entry into surface water. For lakes, provide information on inflow and outflow.**

The drainage route from the site is shown on Figure G.2. Water from the site drains directly into a retention basin, not any other surface water bodies since there are no surface water bodies the site can drain into. The average annual cubic flow is 0 since there are no surface bodies of water downriver of the site. (Source: U.S. Department of the Interior Geological Survey, 1968)

9. **For each source, choose one description from Table 2 that describes the surface water containment. Provide complete documentation (i.e., engineering diagrams, photographs [originals]) as to why the source meets that description and not any other in the Table.**



DRAFT  
FIGURE G.2

M:\ROSLYN\SURFDRAN

SURFACE WATER DRAINAGE  
Roslyn Air National Guard Station  
New York Air National Guard  
Roslyn, New York

OPTTECH  
OPERATIONAL TECHNOLOGIES  
CORPORATION

JULY 1994

Figure G.2

The description from Table 2 that best describes the surface water containment is:

No evidence of hazardous substance migration from the source areas and: (a) Neither of the following present: (1) maintained engineered cover, or (2) functioning and maintained run-on control system and runoff management.

**10. Provide the number of acres in each drainage basin.**

This information is not yet available. The County of Nassau, Department of Public Works is working on acquiring this information at the present time. (Source: County of Nassau, Department of Public Works)

**11. From Table 3, choose the predominant soil group (surface soil) which comprises the largest total area within each drainage area.**

The best surface soil description from Table 3 is medium to coarse textured soils with moderately rapid to very rapid infiltration rates.

**12. Provide the two-year, 24-hour rainfall.**

The two-year, 24-hour rainfall for the Roslyn area is 3.07" on December 11, 1992. (Source: La Guardia AP- Climatology Department)

**13. From Table 4, choose the floodplain category of each source (supply FEMA floodplain map) and determine if each source meets the criteria from Table 5 (engineer's certification).**

The floodplain category from Table 4 that best describes this area is:  
None of the above.

**14. Provide the location of all drinking water intakes within 15 downstream miles (rivers) or 15-mile radius (lakes, bays, etc.). Provide information on population served. For multiple intakes (i.e., municipal system), provide information on the number of intakes, location of all intakes (regardless of 15-mile limit), and total population served by system. Include information on all standby intakes.**

This question does not apply to this area since surface water is not being used for the above purposes. (Source: Public Works)

**15. Provide information and location of intakes within 15 miles downriver (radius in lake or bay) that are used to irrigate five or more acres of commercial food or forage crops, or watering of commercial livestock, or ingredient in commercial food preparation, or supply for aquaculture, or supply for a major or designated water recreation area, excluding drinking water use.**

This question does not apply to this area since surface water is not used for the above purposes. (Source: Public Works)

16. Provide any surface water body 15 miles downriver (radius in lakes or bay) used for drinking water.

No surface water body is used for drinking purposes. (Source: Public Works)

17. Provide the average human food chain production (pounds per year) for each surface water body 15 miles downriver or 15-mile radius in lake.

This question cannot be answered for this site since it has not been calculated. (Source: Public Works)

18. Within a 4-mile radius from the site and 15 miles downriver, or radius in lake, identify all sensitive environments that exist. Provide original documentation (USF&W, Natural Heritage Database, State agencies, NOAA, etc.), multiple sensitive environments within a sensitive environment.

No sensitive environments exist within a 4-mile radius of the site. (Source: U.S. Department of the Interior Fish and Wildlife Service)

19. What is the linear frontage of all wetlands 15 miles downriver or 15-mile radius in lake?

The linear frontage for all wetlands 15 miles downriver or 15-mile radius in lake is 0 since there are no rivers or lakes in the vicinity of the site. (Source: U.S. Department of the Interior Fish and Wildlife Service)

20. Provide the location and number of persons residing, working, attending school, or day care within 200 feet. This includes both the Air and Army Guard.

The average population within 200 feet of the site during the week is as follows:

Bldg. #19 = 10	UTA = 20
#20 = 0	6
#36 = 2	18
#6 = 3	160
#17 = 2	2
#9 = 2	6
#16 = 5	20
#26 = 4	20

Avg = 50

During Unit Training Assembly (UTA) weekends the population is approximately 340. (Source: Capt Larry Johnson, NYANG)

21. Identify all terrestrial sensitive environments that exist on-site. Provide original documentation (USF&W, Natural Heritage Database, State agencies, NOAA, etc.)

and locate each on a 7.5-minute topographic map. Note that there could be multiple sensitive environments within a sensitive environment.

No sensitive environments exist on site. (Source: U.S. Department of the Interior Fish and Wildlife Service)

22. For each source, choose one description from Table 8 that describes the accessibility to a human population. Provide complete documentation (i.e., engineering diagrams, photographs [originals]) as to why the source meets that description and not any other in the Table.

The best description from Table 8 is: Surrounded by maintained fence or combination of maintained fence and natural barriers.

23. Provide the total number of people in following distance rings from source(s)?

- **0 - 1/4 mile**  
This ring includes block #401, 403, 404, 405, 320, 319, 318, 301, 33, 302, 304, 414, 409, 406, 405, 404, 402, 403, 120 and 119 with an **approximate total population of 385.7.**
- **1/4 - 1/2 mile**  
This ring includes block #403, 401, 404, 406, 405, 407, 408, 411, 320, 317, 316, 315, 318, 314, 313, 307, 306, 305, 202, 220, 221, 217, 222, 301, 303, 304, 101, 414, 415, 413, 412, 411, 410, 408, 409, 406, 404, 405, 407, 315, 316, 317, 201, 202, 205, 401, 402, 403, 120, 119, 118, 117, 108, 109, 110, 118, 116, 111, 112, 113, 114, 115, 101, 102 and 107 with an **approximate total population of 2272.26.**
- **1/2 - 1 mile**  
This ring includes track #3021.01, 3020, 3022, 3021.02, 3025.02 and 5177.05 with an **approximate total population of 7466.38.**
- **1 - 2 miles**  
This ring includes track #5177.01, 5175, 3020, 3014, 3016, 3019, 3009, 3022, 3021.01, 3023, 3024, 3025.01, 3034, 3021.02, 3025.02, 5177.05 and 5177.04 with an **approximate total population of 10,041.06.**
- **2 - 3 miles**  
This ring includes track #5176, 5174, 5175, 3020, 3010, 3014, 3016, 3017, 3019, 3009, 3022, 3023, 3031.02, 3024, 3033.01, 3033.02, 3036, 3034, 3037, 3025.01, 3021.02, 3038, 3040.01, 3039, 3040.02, 3021.01, 3025.02, 5177.06, 5177.05, 5177.04 and 5177.01 with an **approximate total population of 47,083.10.**

- **3 - 4 miles**

This ring includes track #5177.01, 5173.02, 5172, 5176, 5171.01, 5174, 5175, 3020, 3010, 3014, 3013, 3012, 3015, 3016, 3018, 3017, 3019, 3022, 3021.01, 3021.02, 3023, 3024, 3025.01, 3031.01, 3031.02, 3029, 3032.02, 3032.01, 3035, 3036, 3034, 3037, 4064, 4066, 3038, 3039, 3040.01, 3040.02, 3041, 3042.2, 3042.01, 3025.02, 5185.01, 5177.06, 5177.05 and 5177.04 with an approximate total population of 78,812.51.

Use 1990 Census data and/or actual house counts. Document how calculated.

24. For each source, choose one description from Table 9 that describes the gaseous containment. Provide complete documentation (i.e., engineering diagrams, photographs [originals]), as to why the source meets that description and not any other in the Table. From Table 10, choose the appropriate description of each source type. For each source, choose one description from Table 11 that describes that particulate containment. Provide complete documentation (i.e., engineering diagrams, photographs [originals]) as to why the source meets that description and not any other in the Table.

None of the descriptions from tables 9-11 apply to this site. (Source: 1990 Census)

25. Provide the location and area (in acres) of all wetlands within 4 miles of the site.

The area of all wetlands within 4 miles of the site is approximately 270 acres. (Source: U.S. Department of the Interior Fish and Wildlife Wetlands Map)

26. Contact EPA Regional Office immediately if any radionuclides are present or suspected at site and supply all radiological information known to date.

No radionuclides are present or suspected at this site. (Source: Capt Larry Johnson, NYANG)

27. For all of the above information, use primary data source and supply two copies or specify where copies may be obtained.

28. Provide any removals or remedial actions taken place at site.

Seven Underground Storage Tanks have been removed as of September 1, 1993. A map showing the tanks has been included (See Figure G.2).

<u>Tanks</u>	<u>Size</u>	<u>Product</u>
18A	8,500	Diesel
18B	6,000	"
17B	5,000	#2 Fuel Oil
17C	5,000	"
0016	1,000	"



016D	2,000	Gasoline
009W	275	Waste Oil

Approximately 40 tons of contaminated soil is scheduled to be reacquimated through an Asphalt Batching Facility. (Source: Capt Larry Johnson, NYANG)

29. If information relevant to a question already has been provided to the EPA, your answer may precisely cite the previous submittal by title, date, page, and paragraph number rather than resubmitting the information. To assist in your efforts, also enclosed is a copy of EPA's draft Preliminary Assessment Guidance.

Table 1

All Sources (Except Surface Impoundments, Land Treatment, Containers, and Tanks)

Evidence of hazardous substance migration from source area (i.e., source area includes source and any associated containment structures).

No liner.

No evidence of hazardous substance migration from source area, a liner, and:

- (a) None of the following present: (1) maintained engineered cover, (2) functioning and maintained run-on control system and runoff management system, or (3) functioning leachate collection and removal system immediately above liner.
- (b) Any one of the three items in (a) present.
- (c) Any two of the items in (a) present.
- (d) All three items in (a) present plus a functioning groundwater monitoring system.
- (e) All items in (d) present plus no bulk or non-containerized liquids nor materials containing free liquids deposited in source area.

No evidence of hazardous substance migration from source area, double liner with functioning leachate collection and removal system above and between liners, functioning groundwater monitoring system, and:

- (f) Only one of the following deficiencies present in containment: (1) bulk or noncontainerized liquids or materials containing free liquids deposited in source area, or (2) no or nonfunctioning or nonmaintained run-on control system and runoff management system, or (3) no or nonmaintained engineered cover.
- (g) None of the deficiencies in (f) present.

Source area inside or under maintained intact structure that provides protection from precipitation so that neither runoff nor leachate is generated, liquid or materials containing free liquids not deposited in source area, and functioning and maintained run-on control present.

Surface Impoundment

Evidence of hazardous substance migration from surface impoundment.

No liner.

Free liquids present with either no diking, unsound diking, or diking that is not regularly inspected and maintained.

No evidence of hazardous substance migration from surface impoundment, free liquids present, sound diking that is regularly inspected and maintained, adequate freeboard, and:

- (a) Liner.
- (b) Liner with functioning leachate collection and removal system below liner, and functioning groundwater monitoring system.
- (c) Double liner with functioning leachate collection and removal system between liners, and functioning groundwater monitoring system.

No evidence of hazardous substance migration from surface impoundment and all free liquids eliminated at closure (either by removal of liquids or solidification of remaining wastes and waste residues).

Land Treatment

Evidence of hazardous substance migration from land treatment zone.

No functioning, maintained, run-on control and runoff management system.

No evidence of hazardous substance migration from land treatment zone and:

- (a) Functioning and maintained run-on control and runoff management system.
- (b) Functioning and maintained run-on control and runoff management system, and vegetative cover established over entire land treatment area.
- (c) Land treatment area maintained in compliance with 40 CFR 264.280.

## Containers

All containers buried.

Evidence of hazardous substance migration from container area (i.e., container area includes containers and any associated containment structures).

No liner (or no essentially impervious base) under container area.

No diking (or no similar structure) surrounding container area.

Diking surrounding container area unsound or not regularly inspected and maintained.

No evidence of hazardous substance migration from container area, container area surrounded by sound diking that is regularly inspected and maintained, and:

- (a) Liner (or essentially impervious base) under container area.
- (b) Essentially impervious base under container area with liquids collection and removal system.
- (c) Containment system includes essentially impervious base, liquids collection system, sufficient contain 10 percent of volume of all containers, and functioning and maintained run-on control; plus functioning groundwater monitoring system, and spilled or leaked hazardous substances and accumulated precipitation removed in timely manner to prevent overflow of collection system, at least weekly inspection of containers, hazardous substances in leaking or deteriorating containers transferred to containers in good condition, and containers sealed except when waste is added or removed.
- (d) Free liquids present containment system has sufficient capacity to hold total volume of all containers and to provide adequate freeboard, single liner under container area with functioning leachate collection and removal system below liner, and functioning groundwater monitoring system.
- (e) Same as (d) except: double liner under container area with functioning leachate collection and removal system between liners.

Containers inside or under maintained intact structure that provides protection from precipitation so that neither runoff nor leachate would be generated from any unsealed or ruptured containers, liquids or materials containing free liquids not deposited in any container, and functioning and maintained runoff control present.

No evidence of hazardous substance migration from container area, containers leaking, and all free liquids eliminated at closure (either by removal of liquid or solidification of remaining wastes and waste residues).

## Tank

Belowground tank.

Evidence of hazardous substance migration from tank area (i.e., tank area includes tank, ancillary equipment such as piping, and any associated containment structures).

Tank and ancillary equipment not provided with secondary containment, (e.g., liner under tank area, vault system, double wall).

No diking (or no similar structure) surrounding tank and ancillary equipment

Diking surrounding tank and ancillary equipment unsound or not regularly inspected and maintained.

No evidence of hazardous substance migration from tank area, tank and ancillary equipment surrounded by sound diking that is regularly inspected and maintained, and:

- (a) Tank and ancillary equipment provided with secondary containment.
- (b) Tank and ancillary equipment provided with secondary containment with leak detection and collection system.
- (c) Tank and ancillary equipment provided with secondary containment system that detects and collects spilled or leaked hazardous substances and accumulated precipitation and has sufficient capacity to contain 110 percent of volume of largest tank within containment area, spilled or leaked hazardous substances and accumulated precipitation removed in timely manner, at least weekly inspection of tank and secondary containment system, all leaking or unfit-for-use tank systems promptly responded to, and functioning groundwater monitoring system.
- (d) Containment system has sufficient capacity to hold volume of all tanks within tank containment area and to provide adequate freeboard, single liner under that containment area with functioning

leachate collection and removal system below liner, and functioning groundwater monitoring system.

- (e) Same as (d) except double liner under tank containment area with functioning leachate collection and removal system between liners.

Tank is aboveground, and inside or under maintained intact structure that provides protection from precipitation so that neither runoff nor leachate would be generated from any material released from tank, liquids or materials containing free liquids not deposited in any tank, and functioning and maintained run-on control present.

Table 2

All Sources (Except Surface Impoundments, Land Treatment, Containers, and Tanks)

Evidence of hazardous substance migration from source area (i.e., source area includes source and any associated containment structures).

No evidence of hazardous substance migration from source areas and:

- (a) Neither of the following present: (1) maintained engineered cover, or (2) functioning and maintained run-on control system and runoff management system.
- (b) Any one of the two items in (a) present.
- (c) Any two of the following present: (1) maintained engineered cover, or (2) functioning and maintained run-on control system and runoff management system, or (3) liner with functioning leachate collection and removal system immediately above liner.
- (d) All items in (c) present.
- (e) All items in (c) present, plus no bulk or non-containerized liquids nor materials containing free liquids deposited in source area.

No evidence of hazardous substance migration from source area, double liner with functioning leachate collection and removal system above and between liners, and:

- (f) Only one of the following deficiencies present in containment: (1) bulk or noncontainerized liquids or materials containing free liquids deposited in source area, or (2) no or nonfunctioning or nonmaintained run-on control system and runoff management system, or (3) no or nonmaintained engineered cover.
- (g) None of the deficiencies in (f) present.

Source area inside or under maintained intact structure that provides protection from precipitation so that neither runoff nor leachate is generated, liquids or materials containing free liquids not deposited in source area, and functioning and maintained run-on control present.

Surface Impoundment

Evidence of hazardous substance migration from surface impoundment.

Free liquids present with either no diking, unsound diking, or diking that is not regularly inspected and maintained.

No evidence of hazardous substance migration from surface impoundment, free liquids present, sound diking that is regularly inspected and maintained, adequate freeboard, and:

- (a) No liner.
- (b) Liner.
- (c) Liner with functioning leachate collection and removal system below liner.
- (d) Double liner with functioning leachate collection and removal system between liners.

No evidence of hazardous substance migration from surface impoundment and all free liquids eliminated at closure (either by removal of liquids or solidification of remaining wastes and waste residues).

Land Treatment

Evidence of hazardous substance migration from land treatment zone.

No functioning and maintained run-on control and runoff management system.

No evidence of hazardous substance migration from land treatment zone and:

- (a) Functioning and maintained and maintained run-on control and runoff management system.
- (b) Functioning and maintained run-on control and runoff management system, and vegetative cover established over entire land treatment area.
- (c) Land treatment area maintained in compliance with 40 CFR 264.280.

#### Containers

All containers buried.

Evidence of hazardous substance migration from container area (i.e., container area includes containers and any associated containment structures).

No diking (or no similar structure) surrounding container area.

Diking surrounding container area unsound or not regularly inspected and maintained.

No evidence of hazardous substance migration from container area and container area surrounded by sound diking that is regularly inspected and maintained.

No evidence of hazardous substance migration from container area, container area surrounded by sound diking that is regularly inspected and maintained, and:

- (a) Essentially impervious base under container area with liquids collection and removal system.
- (b) Containment system includes essentially impervious base, liquids collection system, sufficient capacity to contain 10 percent of volume of all containers, and functioning and maintained run-on control; and spilled or leaked hazardous substances and accumulated precipitation removed in timely manner to prevent overflow of collection system, at least weekly inspection of containers, hazardous substances in leaking or deteriorating containers transferred to containers in good condition, and containers sealed except when waste is added or removed.
- (c) Free liquids present containment system has sufficient capacity to hold total volume of all containers and to provide adequate freeboard, and single liner under container area with functioning leachate collection and removal system below liner.
- (d) Same as (c) except: double liner under container area with functioning leachate collection and removal system between liners. Containers inside or under maintained intact structure that provides protection from precipitation so that neither runoff nor leachate would be generated from any unsealed or ruptured containers, liquids or materials containing free liquids not deposited in any container, and functioning and maintained run-on control present.

No evidence of hazardous substance migration from container area, containers leaking, and all free liquids eliminated at closure (either by removal of liquids or solidification of remaining wastes and waste residues).

#### Tank

Belowground tank.

Evidence of hazardous substance migration from tank area (i.e., tank area includes tank, ancillary equipment such as piping, and any associated containment structures).

No diking (or no similar structure) surrounding tank and ancillary equipment.

Diking surrounding tank and ancillary equipment unsound or not regularly inspected and maintained.

No evidence of hazardous substance migration from tank area and tank and ancillary equipment surrounded by sound diking that is regularly inspected and maintained.

No evidence of hazardous substance migration from tank area, tank and ancillary equipment surrounded by sound diking that is regularly inspected and maintained, and:

- (a) Tank and ancillary equipment provided with secondary containment (e.g., liner under tank area, vault system, double wall) with leak detection and collection system.
- (b) Tank and ancillary equipment provided with secondary containment system that detects and collects spiked or leaked hazardous substances and accumulated precipitation and has sufficient capacity to contain 110 percent of volume of largest tank within containment area, spilled or leaked hazardous substances and accumulated precipitation removed in a timely manner, at least

- weekly inspection of tank and secondary containment system, and all leaking or unfit-for-use tank systems promptly responded to.
- (c) Containment system has sufficient capacity to hold total volume of all tanks within the tank containment area and to provide adequate freeboard, and single liner under tank containment area with functioning leachate collection and removal system below liner.
  - (d) Same as (c) except double liner under tank containment area with functioning leachate collection and removal system between liners.

Tank is aboveground, and inside or under maintained intact structure that provides protection from precipitation so that neither runoff nor leachate would be generated from any material released from tank, liquids or materials containing free liquids not deposited in any tank, and functioning and maintained run-on control present.

Table 3  
Surface Soil Description

Coarse-textured soils with high infiltration rates (for example, sands, loamy sands).  
 Medium-textured soils with moderate infiltration rates (for example, sandy loams, loams).  
 Moderately fine-textured soils with low infiltration rates (for example, silty loams, silts, sandy clay loams).  
 Fine-textured soils with very low infiltration rates (for example, clays, sandy clays, silty clay loams, clay loams, silty clays); or impermeable surfaces (for example, pavement).

Table 4  
Floodplain Categories

Source floods annually.  
 Source in 10-year floodplain.  
 Source in 100-year floodplain.  
 Source in 500-year floodplain.  
 None of the above.

Table 5  
Flood Containment

Documentation that containment at the source is designed, constructed, operated, and maintained to prevent a washout of hazardous substances by the flood being evaluated (see floodplain category).

Table 6  
Sensitive Environments

Critical habitat<sup>a</sup> for Federal designated endangered or threatened species.  
 Marine Sanctuary.  
 National Park.  
 Designated Federal Wilderness Area.  
 Areas identified under Coastal Zone Management Act<sup>b</sup>.  
 Sensitive areas identified under National Estuary Program<sup>c</sup> or Near Coastal Waters Program<sup>d</sup>.  
 Critical areas identified under the Clean Lakes Program<sup>e</sup>.  
 National Monument<sup>f</sup>.  
 National Seashore Recreational Area.  
 National Lakeshore Recreational Area.  
 Habitat known to be used by Federal designated or proposed endangered or threatened species.  
 National Preserve.

National or State Wildlife Refuge.  
 Unit of Coastal Barrier Resources System.  
 Coastal Barrier (undeveloped).  
 Federal land designated for protection of natural ecosystems.  
 Administratively Proposed Federal Wilderness Area.  
 Spawning areas critical<sup>a</sup> for the maintenance of fish/shellfish species within river, lake, or coastal tidal waters.  
 Migratory pathways and feeding areas critical for maintenance of anadromous fish species within river reaches or areas in lakes or coastal tidal waters in which the fish spend extended periods of time.  
 Terrestrial areas utilized for breeding by large or dense aggregations of animals<sup>b</sup>.  
 National river reach designated as Recreational.  
 Habitat known to be used by State designated endangered or threatened species.  
 Habitat known to be used by species under review as to its Federal endangered or threatened status.  
 Coastal Barrier (partially developed).  
 Federal designated Scenic or Wild River.  
 State land designated for wildlife or game management.  
 State designated Scenic or Wild River.  
 State designated Natural Areas.  
 Particular areas, relatively small in size, important to maintenance of unique biotic communities.  
 State designated areas for protection or maintenance of aquatic life<sup>c</sup>.

---

<sup>a</sup>Critical habitat as defined in 50 CFR 424.02.

<sup>b</sup>Areas identified in State Coastal Zone Management plans as requiring protection because of ecological value.

<sup>c</sup>National Estuary Program study areas (Subareas within subareas) identified in Comprehensive Conservation and Management Plans as requiring protection because they support critical life stages of key estuarine species (Section 320 of Clean Water Act, as amended).

<sup>d</sup>Near Coastal Waters as defined in Sections 104(b)(3), 304(1), 319, and 320 of Clean Water Act, as amended.

<sup>e</sup>Clean Lakes Program critical areas (subareas within lakes, or in some cases entire small lakes) identified by State Clean Lake Plans as critical habitats (Section 314 of Clean Water Act, as amended).

<sup>f</sup>Use only for air migration pathway.

<sup>g</sup>Limit to areas described as being used for intense or concentrated spawning by a given species.

<sup>h</sup>For the air migration pathway, limit to terrestrial vertebrate species. For the surface water migration pathway, limit to terrestrial vertebrate species aquatic or semiaquatic foraging habits.

<sup>i</sup>Areas designated under Section 305(a) of Clean Water Act, as amended.

Table 7  
 Terrestrial Sensitive Environments

Terrestrial critical habitat<sup>a</sup> for Federal designated endangered or threatened species.  
 National Park.  
 Designated Federal Wilderness Area.  
 National Monument.  
 Terrestrial habitat known to be used by Federal designated or proposed threatened or endangered species.  
 National Preserve (terrestrial).  
 National or State Terrestrial Wildlife Refuge.  
 Federal land designated for protection of natural ecosystems.  
 Administratively proposed Federal Wilderness Area.  
 Terrestrial areas utilized for breeding by large or dense aggregations of animals<sup>b</sup>.  
 Terrestrial habitat known to be used by State designated endangered or threatened species.  
 Terrestrial habitat known to be used by species under review as to its Federal designated endangered or threatened status.  
 State lands designated for wildlife or game management.  
 State designated Natural Areas.  
 Particular area, relatively small in size, important to maintenance of unique biotic communities.

---

<sup>a</sup>Critical habitat as defined in 50 CFR 42.

<sup>b</sup>Limit to vertebrate species.



Table 8  
Area of Observed Contamination

Designated recreational area.  
 Regularly used for public recreation (for example, fishing, hiking, softball).  
 Accessible and unique recreational area (for example, vacant lots in urban area).  
 Moderately accessible (may have some access improvements – for example, gravel road), with some public recreation use.  
 Slightly accessible (for example, extremely rural area with no road improvement), with some public recreation use.  
 Accessible, with no public recreation use.  
 Surrounded by maintained fence or combination of maintained fence and natural barriers.  
 Physically inaccessible to public, with no evidence of public recreation use.

Table 9  
Gas Containment Description

All situations except those specifically listed below.  
 Evidence of biogas release.  
 Active fire within source.  
 Gas collection/treatment system functioning, regularly inspected, maintained, and completely covering source.  
 Source substantially surrounded by engineering windbreak and no other containment specifically described in this table applies.  
 Source covered with essentially impermeable, regularly inspected, maintained cover.  
 Uncontaminated soil cover >3 feet:  
     Source substantially vegetated with little exposed soil.  
     Source lightly vegetated with much exposed soil.  
     Source substantially devoid of vegetation.  
 Uncontaminated soil cover  $\geq 1$  foot and  $\leq 3$  feet:  
     Source heavily vegetated with essentially no exposed soil.  
     Cover soil resistant to gas migration<sup>a</sup>.  
     Cover soil type not resistant to gas migration<sup>a</sup> or unknown.  
     Source substantially vegetated with little exposed soil and cover soil type resistant to gas migration<sup>a</sup>.  
     Other.  
 Uncontaminated soil cover <1 foot:  
     Source heavily vegetated with essentially no exposed soil and cover soil type resistant to gas migration<sup>a</sup>.  
     Other.  
 Totally or partially enclosed within structurally intact building and no other containment specifically described in this table applies.  
 Source consists solely of intact, sealed containers:  
     Totally protected from weather by regularly inspected, maintained cover.  
     Other.

---

<sup>a</sup>Consider moist fine-grained and saturated coarse-grained soils resistant to gas migration; consider all other soils nonresistant.

Table 10  
Source Type

Active fire area.  
 Burn pit.  
 Containers or tanks (buried/belowground):  
     Evidence of biogas release.  
     No evidence of biogas release.

Containers or tanks, not elsewhere specified.  
Contaminated soil (excluding land treatment).  
Landfarm/land treatment.

Landfill:

Evidence of biogas release.  
No evidence of biogas release.

Pile:

Tailings pile.  
Scrap metal or junk pile.  
Trash pile.  
Chemical waste pile.  
Other waste piles.

Surface impoundments (buried/backfilled):

Evidence of biogas release.  
No evidence of biogas release.

Surface impoundment (not buried/backfilled):

Dry.  
Other.

Other types of sources, not elsewhere specified.

Table 11  
Particulate Containment Description

All situations except those specifically listed below.

Source contains only particulate hazardous substances totally covered by liquids.

Source substantially surrounded by engineered windbreak and no other containment specifically described in this table applies.

Source covered with essentially impermeable, regularly inspected, maintained cover.

Uncontaminated soil cover > 3 feet:

Source substantially vegetated with little or no exposed soil.  
Source lightly vegetated with much exposed soil.  
Source substantially devoid of vegetation.

Uncontaminated soil cover  $\geq 1$  foot and  $\leq 3$  feet:

Source heavily vegetated with essentially no exposed soil:  
Cover soil type resistant to gas migration<sup>a</sup>.  
Cover soil type not resistant to gas migration<sup>a</sup>.  
Source substantially vegetated with little exposed soil and cover soil type resistant to gas migration<sup>a</sup>.  
Other.

Uncontaminated soil cover < 1 foot:

Source heavily vegetated with essentially no exposed soil and cover soil type resistant to gas migration<sup>a</sup>.  
Other.

Totally or partially enclosed within structurally intact building and no other containment specifically described in this table applies.

Source consists solely of containers:

All containers contain only liquids.  
All containers intact, sealed, and totally protected from weather by regularly inspected, maintained cover.  
All containers intact and sealed.  
Other.

---

<sup>a</sup>Consider moist fine-grained and saturated coarse-grained soils resistant to gas migration; consider all other soils nonresistant.

**THIS PAGE INTENTIONALLY LEFT BLANK**